


AD-A105 653 ARMY ENGINEER WATERWAYS EXPERIMENT STATION VICKSBURG--ETC F/G 13/2
CONDITION SURVEY, REPAIR AND REHABILITATION, LOCK AND DAM NUMBE--ETC(U)
AUG 81 R L STOWE, H T THORNTON
UNCLASSIFIED WES/MP/SL-81-21 NL


1 of 2

AD-A
105 653





LEVEL II



MISCELLANEOUS PAPER SL-81-21

**CONDITION SURVEY
REPAIR AND REHABILITATION
LOCK AND DAM NO. 24, MISSISSIPPI RIVER**

by

Richard L. Stowe, Henry T. Thornton, Jr.

**Structures Laboratory
U. S. Army Engineer Waterways Experiment Station
P. O. Box 631, Vicksburg, Miss. 39180**

August 1981

Final Report

Approved For Public Release; Distribution Unlimited

AD A105653



Prepared for U. S. Army Engineer District, St. Louis
210 Tucker Blvd., North, St. Louis Mo. 63101

81 10 14

**DTIC
ELECTE
OCT 16 1981**

DTIC FILE COPY

131

Destroy this report when no longer needed. Do not return
it to the originator.

The findings in this report are not to be construed as an official
Department of the Army position unless so designated
by other authorized documents.

The contents of this report are not to be used for
advertising, publication, or promotional purposes.
Citation of trade names does not constitute an
official endorsement or approval of the use of
such commercial products.

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

| REPORT DOCUMENTATION PAGE | | READ INSTRUCTIONS BEFORE COMPLETING FORM |
|---|---|---|
| 1. REPORT NUMBER Miscellaneous Paper SL-81-21 | 2. GOVT ACCESSION NO. AR A105653 | 3. RECIPIENT'S CATALOG NUMBER |
| 4. TITLE (and Subtitle) CONDITION SURVEY, REPAIR AND REHABILITATION, LOCK AND DAM NO. 24, MISSISSIPPI RIVER. | 5. TYPE OF REPORT & PERIOD COVERED Final report. | 6. PERFORMING ORG. REPORT NUMBER |
| 7. AUTHOR(s) Richard L. Stowe Henry T. Thornton, Jr. | 8. CONTRACT OR GRANT NUMBER(s) 14 WE 11/81-1-1 | 9. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS |
| 10. PERFORMING ORGANIZATION NAME AND ADDRESS U. S. Army Engineer Waterways Experiment Station Structures Laboratory P. O. Box 631, Vicksburg, Miss. 39180 | 11. CONTROLLING OFFICE NAME AND ADDRESS U. S. Army Engineer District, St. Louis 210 Tucker Blvd., North, St. Louis, Mo. 63101 | 12. REPORT DATE Aug 81 |
| 13. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) | 14. SECURITY CLASS. (of this report) Unclassified | 15. NUMBER OF PAGES 137 |
| 16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited. | | |
| 17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) | | |
| 18. SUPPLEMENTARY NOTES Available from National Technical Information Service, 5285 Port Royal Road, Springfield, Va. 22151. | | |
| 19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Concrete dams Concrete deterioration Laboratory tests Lock and Dam No. 24, Mississippi River Locks (Waterways) | | |
| 20. ABSTRACT (Continue on reverse side if necessary and identify by block number) A condition survey of the concrete was performed at Lock and Dam No. 24 on the Mississippi River. Field studies indicated that 32 percent of the concrete bridge support columns are moderately to severely deteriorated, 48 percent are slightly deteriorated, and 20 percent show no sign of damage. A small zone of concrete downstream of the trunnion shafts is severely deteriorated. Cores were recovered from areas representative of the different degrees of damaged concrete and examined and tested in the laboratory. Some of the | | |

(Continued)

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

48/115

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

20. ABSTRACT (Continued)

cores were extensively damaged by cycles of freezing and thawing to depths of 2 ft. Compressive strengths of the cores ranged from 2010 to 9770 psi. The minimum remaining compressive strength in the columns is estimated at 1000 psi. Techniques for removal and repair of damaged concrete are recommended. Removal of concrete by water jet is suggested.

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

PREFACE

The work described herein was performed for the U. S. Army Engineer District, St. Louis (SLD), by personnel of the U. S. Army Engineer Waterways Experiment Station (WES). The work was authorized by DA Form 2544 No. ED 80-75 dated 3 September 1980, No. ED 80-75 R1 dated 25 September 1980, and ED 80-75 R2 dated 18 November 1980.

The testing program was accomplished under the direction of Mr. Bryant Mather, Chief of the Structures Laboratory (SL), WES, and Mr. John M. Scanlon, Jr., Chief of the Concrete Technology Division (CTD), SL. Mr. H. T. Thornton, CTD, was Project Leader and was assisted in performing the laboratory work by Messrs. R. L. Stowe, F. S. Stewart, and G. S. Wong and Mrs. Joyce C. Alvin, all of CTD. The core drilling was conducted by personnel of the Geotechnical Laboratory (GL), WES, under the direction of Mr. Mark A. Vispi. SLD personnel furnished the photographs in Appendix D. This report was largely written by Messrs. Stowe and Thornton; Messrs. Wong and J. E. McDonald, CTD, contributed portions.

Directors of WES during the conduct of the investigation and the publication of this report were COL N. P. Conover, CE, and COL T. C. Creel, CE. Technical Director was Mr. F. R. Brown.

| | |
|----------------------|--|
| Accession For | |
| NTIS GRA&I | <input checked="checked" type="checkbox"/> |
| DTIC TAB | <input type="checkbox"/> |
| Unannounced | <input type="checkbox"/> |
| Justification | |
| By _____ | |
| Distribution/ _____ | |
| Availability Codes | |
| Dist | Avail and/or Special |
| A | |

DTIC
ELECTE
OCT 16 1981
S D

CONTENTS

| | <u>Page</u> |
|---|-------------|
| PREFACE | 1 |
| CONVERSION FACTORS, INCH-POUND TO METRIC (SI) | |
| UNITS OF MEASUREMENT | 3 |
| PART I: INTRODUCTION | 4 |
| Location and General Description | 4 |
| Background | 4 |
| Objectives | 5 |
| Scope | 5 |
| PART II: PRELIMINARY ENGINEERING STUDY | 7 |
| Review of Reports and Drawings | 7 |
| Inspection of Dam | 7 |
| PART III: DRILLING AND EXCAVATION | 10 |
| Drilling | 10 |
| Excavation Around Trunnion Shaft | 11 |
| PART IV: TEST SPECIMENS AND TEST PROCEDURES | 13 |
| Cores Received | 13 |
| Selection of Test Specimens | 13 |
| Physical Property Test Procedures and Petrographic Examination | 14 |
| PART V: RESULTS AND DISCUSSION | 15 |
| Petrographic Examination | 15 |
| Extent of Damaged Concrete | 16 |
| Physical Property Tests | 18 |
| PART VI: SUMMARY AND RECOMMENDATIONS | 25 |
| Trunnion Shaft Area | 25 |
| Remaining Strength of Concrete | 25 |
| Columns Adequate to Support Bridge | 26 |
| Extent and Cause of Damaged Concrete | 27 |
| Structural Cracking | 28 |
| Removal and Repair of Damaged Concrete | 29 |
| REFERENCES | 33 |
| TABLES 1-3 | |
| PLATES 1-46 | |
| APPENDIX A: TYPICAL PHOTOGRAPHS SHOWING DAMAGED CONCRETE | A1 |
| APPENDIX B: FIELD CORE LOGS | B1 |
| APPENDIX C: REPORT OF PETROGRAPHIC EXAMINATION OF CONCRETE CORES | C1 |
| APPENDIX D: PHOTOGRAPHS SHOWING BURST PIPE | D1 |

CONVERSION FACTORS, INCH-POUND TO METRIC (SI)
UNITS OF MEASUREMENT

Inch-pound units of measurement used in this report can be converted to metric (SI) units as follows:

| <u>Multiply</u> | <u>By</u> | <u>To Obtain</u> |
|--------------------------------|-------------|--------------------------------|
| Fahrenheit degrees | 5/9 | Celsius degrees or Kelvins* |
| feet | 0.3048 | metres |
| feet per second | 0.3048 | metres per second |
| inches | 0.0254 | metres |
| miles (U. S. statute) | 1.609344 | kilometres |
| pounds (force) per square inch | 0.006894757 | megapascals |
| pounds (mass) | 0.45359237 | kilograms |
| pounds (mass) per cubic foot | 16.01846 | kilograms per cubic metre |
| square feet | 0.09290304 | square metres |

* To obtain Celsius (C) temperature readings from Fahrenheit (F) readings, use the following formula: $C = (5/9)(F - 32)$. To obtain Kelvin (K) readings, use: $K = (5/9)(F - 32) + 273.15$.

CONDITION SURVEY
REPAIR AND REHABILITATION
LOCK AND DAM NO. 24, MISSISSIPPI RIVER

PART I: INTRODUCTION

Location and General Description

1. Lock and Dam No. 24, Mississippi River, is situated at Clarksville, Missouri, 93.5 miles* upstream from St. Louis, and 273.5 miles above the mouth of the Ohio River. It is close to the Missouri shore at the base of a high, steep hill. The project consists of a main lock and upper gate bay of an auxiliary lock; a dam containing a movable section of 15 tainter gates; and a fixed submersible stone-covered earth dike reaching to the Sny Island Drainage and Levee District.

2. The regulating portion of the dam consists of fifteen 80-ft-wide tainter gates. Dam piers are pile supported. The submersible dike extending from the storage yard to the Illinois shore is constructed with a core of steel pile cells covered with stone and slush concrete.

Background

3. In 1973, ultrasonic pulse velocity measurements were made through selected piers of Locks and Dams No. 24 and 25. The results of these tests were reported to the St. Louis District (SLD) by letter dated 29 October 1973, subject, "Results of Soniscope Survey of Lock and Dam No. 24 and 25, Mississippi River." In 1976,¹ the presence of alkali-silica reaction in concrete from an intermediate wall of Lock and Dam No. 24 was established by the examination of 6-in. and 4-in.-diameter cores. The concrete cores were from an area of undeteriorated concrete. In October 1978, five NX (2-1/8-in. diameter) concrete cores were received from the U. S. Army Engineer District, St. Louis, for examination.

* A table of factors for converting inch-pound units of measurement to metric (SI) units is presented on page 3.

These cores were taken from the downstream portions of three piers in the dam of Lock and Dam No. 24. The cores were in fragments with the longest intact piece of core being about 2-1/2 in. Results of the examination of these cores were reported in December 1978.²

4. In September 1979 members of the Structures Laboratory, Waterways Experiment Station (SL, WES), performed a more extensive ultrasonic pulse velocity investigation of the concrete portion of the dam structure at Lock and Dam No. 24. This investigation included selected concrete columns that support the service bridge as well as piers No. 2 through 15. The objectives of this investigation were to determine, by nondestructive means, the extent and severity of cracking near the trunnion shafts on the downstream portions of the piers and to determine the extent of cracking in the columns. The results of this investigation were reported in WES Miscellaneous Paper SL-80-2.³

Objectives

5. The objectives of the investigation reported herein were to:
 - a. Determine the effect of water intrusion (if any) on the reinforcing steel and tainter gate anchorage steel in the area around the trunnion shaft. Pier No. 9 was selected to be examined.
 - b. Determine the remaining compressive strength of the concrete in the piers and the service bridge support columns.
 - c. Determine the extent, severity, and cause of the concrete deterioration in the piers and support columns.
 - d. Determine the location, extent, and cause of any structural cracks.
 - e. Suggest repair materials and repair methods.

Scope

6. The investigation included:
 - a. Preliminary engineering study.
 - (1) Visual inspection of dam.
 - (2) Collection and review of all available records and data.

- b. Drilling and excavation of concrete.
- c. Laboratory testing and analysis of concrete core.

PART II: PRELIMINARY ENGINEERING STUDY

Review of Reports and Drawings

7. All available reports, records, and drawings pertinent to this study were collected and reviewed. The items available for review included construction drawings and photographs, postconstruction concrete reports, Periodic Inspection Reports including instrumentation data and analysis, concrete core test and examination reports, a report of field ultrasonic velocity measurements, and boring logs. Specific references to these reports and drawings are made in appropriate parts of this report.

Inspection of Dam

8. Personnel from the WES, SLD, and Lock and Dam No. 24 inspected the dam to observe the extent of damaged concrete on exposed surfaces, locate any structural cracks, obtain information from maintenance, repair, and operational records, and to talk with lock personnel. Persons inspecting the dam are given in Table 1. Photographs showing typical damaged concrete are presented in Appendix A, pages A2 through A5.

9. The piers and the service bridge support columns of the dam were examined to ascertain the physical condition of the exposed concrete surfaces. As a result of the examination, the exposed concrete was classified into five categories based upon crack width and frequency and the amount of exudation present. The "Concrete Condition" terms were established by the authors. The crack width ranges are given in the "Guide for Making a Condition Survey of Concrete in Service;" see Reference 4. The different concrete conditions are tabulated below:

| <u>Concrete Condition</u> | <u>Description</u> |
|---------------------------|---|
| "OK" | No signs of deterioration |
| Very light | Local cracks (infrequent), closed hairline, one per 3- by 3-ft area, slight exudation |

| <u>Concrete Condition</u> | <u>Description</u> |
|---------------------------|---|
| Light | Local cracks (infrequent), fine (0.1 mm, 0.04 in.), one per 3- by 3-ft area, slight exudation |
| Moderate | Zone cracking, medium (1 to 2 mm, 0.04 to 0.08 in.), one crack every 3 to 4 in., heavy exudation covering 50 percent of zone |
| Severe | Zone cracking, medium to wide (wide 2 mm, 0.08 in.), one crack every 2 to 3 in. apart, heavy exudation covering 75 percent of zone. |

10. Zones of damage were sketched (to scale) for the upstream and the downstream surfaces of the bridge columns. If a small zone of damage exists, then the whole bridge column was classified based upon the condition of the small zone. Some damaged zones extended over a few square feet while others over tens of square feet. No sketches were made for the zones of damaged concrete just downstream of the trunnion shafts in the piers. The exterior and interior extent of concrete damage in the piers and bridge columns is presented and discussed in Part V of this report.

11. A number of structural cracks were observed in the bridge columns on piers No. 9 and No. 16. The extent and width of structural cracks were mapped. For purposes of this report structural cracks are defined as those cracks caused by external applied loads. The extent of the structural cracks is presented in Part VI of this report.

12. Mr. Dan Buckley, Lockmaster at Lock and Dam No. 24, was on the inspection team. He explained to the team the difficulty encountered, on a number of occasions, in passing thick ice over a couple of the tainter gates. The ice would build up behind the gates. When it broke loose and was passing the gate, he observed a trunnion shaft oscillating due to the vibrations caused by ice hitting the piers and the gates. He also related that the townspeople, adjacent to the lock, complained of inordinate vibrations on occasions when thick ice was being passed; windows rattling and vibration felt through the floors of houses.

13. In addition to the ice problem, Mr. Buckley told us that the tainter gates are now not lowered to their design depth. When they are lowered to their maximum depth, inordinate vibrations result due to the applied water loads.

PART III: DRILLING AND EXCAVATION

Drilling

14. Information gathered during the inspection of the dam indicated that 32 percent of the service bridge support columns (total of 64) are moderately to severely deteriorated; 48 percent of the columns are very light to lightly deteriorated; and 20 percent have no signs of deterioration. Columns representative of the different concrete conditions were drilled. Six of the severely and three of the moderately deteriorated columns had short horizontal borings placed in them. Four columns showing no evidence of deterioration had borings placed in each of them. Borings in the columns were drilled through to the opposite side.

15. Three of the piers were drilled to obtain information on the quality of the concrete with depth. Vertical borings were located in those piers where nondestructive testing (Reference 3) indicated poor concrete and where survey data indicated the greatest amount of settlement and downstream movement of the piers.⁵ The measured settlement and downstream movement are relatively small, 0.03 ft and 0.06 ft, respectively. In general, the piers indicating the greatest movement also indicate the greatest settlement. Short horizontal borings were also placed in the piers. Borings in the piers were drilled in the vicinity of the trunnion shafts. See Plate 1 for general boring locations; specific boring locations are given on plates presented in Part V of this report.

16. Boring designations appearing on Plate 1 are explained as follows; S WES P04.1 and S WES C02.2N are used as examples: S, sponsor (St. Louis District); WES, drilling agency (Waterways Experiment Station); P&C, for pier and column; first two numbers for pier numbers; third number is column number 1 through 4; and last letter represents north, east, south, or west face of a column. See Plate 1 for order of column numbers.

17. A total of 4 vertical borings and 21 horizontal borings were drilled. A total of 161 ft of core was recovered. Core recovery was

99 percent. See Table 2 for detailed boring information. The following information is presented for each boring; the direction of the boring, the location, the elevation of the top of boring, the elevation bottom of boring, depth of horizontal borings, and the date when the boring was started. Core logs are presented in Appendix B.

18. A WES drill crew conducted the drilling at Lock and Dam No. 24. Drilling equipment consisted of an Acker Toredon Mark II and a Sprage and Henwood skid-mounted rotary drill rig. A Diamond Core Drill Manufacturers Association standard 4-in. by 5-1/2-in. double tube swivel tube core barrel and 5-7/8- by 6-1/8-in. thin wall barrel were used with diamond bits to obtain the concrete core. Access to the dam was by a marine floating plant supplied by the SLD; once on the dam, the crane on top of structure was used to position and move drill equipment. The crane was operated by a WES operator. Continuous samples were obtained in all borings. A Concord portable electric drill rig was used in drilling horizontal borings in the columns.

19. All borings were backfilled with concrete using packaged dry combined materials. To each 50 lb of materials was added 10 lb of portland cement. To each 60 lb of materials, enough water was added to make a stiff mixture. Prior to adding the required water to the materials, 1 ml of air-entraining admixture was mixed in the water. After a 24-hr period, the crown area of the backfilled horizontal borings in the columns were sealed. A slightly expanding cement grout (aluminum powder was added to cement) was pumped into and along the crown area of the borings. The sealing operation was necessary due to the shrinkage of the concrete away from the crown area of the horizontally drilled hole. It was directed that all borings in the columns be backfilled and sealed before the crane was allowed to pass over those columns that were drilled.

Excavation Around Trunnion Shaft

20. Concrete from around the trunnion shaft in pier No. 9 was excavated to expose a small portion of the tainter gate anchorage steel. This work was done to reveal the physical condition of the anchorage

steel. With evidence of cracked concrete and impounding water in the area of the trunnion shaft, there was concern that rusting of the anchorage steel had reduced the steel's cross section. See Plate 2 for a cross section of the zone examined. Photographs No. 8 through 13, Appendix A, show the excavated zone.

21. The concrete was removed from around the anchorage steel using a hand held air-hammer. The first foot of concrete was removed without great difficulty as compared to the remaining 1-1/2 ft. The concrete was hard and tough to remove. Occasional cracks were encountered that were lightly stained; the staining resulted from infiltrating rain water.

22. A plastic cork, as described on the original plans, was found bonded to the anchorage steel. It was intact and had to be torn away from the steel except near the top of the pier. The area crossed hatched in Plate 2 indicates the zone of rusting that was detected. The rusting reduced the steel cross section about 1/64 in. on the trunnion collar; original thickness of collar is 2 in. The damage to the steel is considered insignificant. See photographs No. 11, 12, and 13 (Appendix A) for rusted zone.

23. An asphaltic bonding material was applied to the anchorage steel prior to backfilling the excavated hole. The hole was cleaned of loose material, air blown, and backfilled with air-entrained concrete. The concrete was vibrated in 1-ft lifts, finished, and cured.

PART IV: TEST SPECIMENS AND TEST PROCEDURES

Cores Received

24. Concrete core from 25 borings was received at the WES. Shipment of the core was handled by the WES drill crew. Cores were shipped in sawdust lined core boxes. Upon receipt of the core, it was inspected for damage; there was no damage due to handling and shipping. The core that was not selected for testing remains at the WES; it will be discarded or shipped to the SLD after completion of the investigation.

Selection of Test Specimens

25. A detailed visual examination of all the core was made to assist in the selection of representative test specimens. The examination was further used to verify the depth of damaged concrete in the core. Test specimens were selected from the top, middle, and bottom portions of all the vertical cores and on those horizontal drilled cores where core was intact and could be tested. Many test specimens contained portions of damaged concrete; i.e., horizontal and inclined cracks and weathered concrete. Some specimens were pieced back together for compressive strength testing; e.g., on some cores where an inclined or horizontal crack caused separation of the core, pieces were placed back together and tested. Nominal 6-in.-diameter by 12-in.-long specimens were used for the various physical property tests. Test specimen locations on the cores are given on appropriate drawings and sketches in Part V of this report.

26. After examining the core in detail, a comparison between the condition of the core and the condition of the in-place surface concrete was made. The core and in-place surface concrete compared quite well; i.e., where severe deteriorated core exists, severe deteriorated in-place surface concrete existed. This comparison enables one to say that other columns with the same classification ("OK", moderate, and severe) would likely contain internal concrete similar to the columns that were cored.

This information will be helpful if the damaged concrete is replaced.

27. Portions of concrete from five cores were selected for detailed petrographic examination. A general description of the 6-in.-diameter concrete cores is as follows:

| <u>Field Identification No.</u> | <u>Description</u> |
|---------------------------------|--|
| S WES-C16.2 N-80 | Horizontal core into badly deteriorated concrete, from column |
| S WES-C16.3 E-80 | Horizontal core into moderately deteriorated concrete, from column |
| S WES-C13.2 N | Horizontal core into good concrete, from column |
| S WES-P04.1 | Vertical core into good concrete, from pier |
| S WES-P09.1 | Vertical core into good concrete, from pier |

Physical Property Test Procedures
and Petrographic Examination

28. The physical property tests were conducted in accordance with the appropriate test methods tabulated below:

| <u>Property</u> | <u>Test Method</u> |
|---------------------------------------|------------------------------|
| Unit Weight (As Received), γ_m | CRD-C 107-69 ⁶ |
| Water Content, w | CRD-C 113-80 (ASTM C 566-78) |
| Pulse Velocity, V_p | CRD-C 51-72 (ASTM C 597-687) |
| Compressive Strength, q_u | CRD-C 27-78 (ASTM C 42-77) |
| Elastic Modulus, E | CRD-C 19-75 (ASTM C 469-65) |
| Poisson's Ratio, ν | CRD-C 19-75 (ASTM C 469-65) |

29. Applicable portions of CRD-C 57-78 (ASTM C 856-77) were used in conducting a petrographic examination on representative concrete core; see Appendix B for specific works accomplished.

PART V: RESULTS AND DISCUSSION

Petrographic Examination

30. The results of the petrographic examination of the concrete cores are presented in detail in Appendix C. A brief summary is presented in the following paragraphs.

31. The concrete is not air entrained. The concrete contains gravel and sand of mixed composition; maximum size aggregate is about 1-1/2 in. Coarse aggregate consists of sandstone, quartz, chert, carbonate rock particles, igneous rock particles, and some particles of ironstone. Chalcedony in the chert particles was identified as the common reactive material in the concrete. This finding is similar to the observations made in previous reports. (1,2)

32. The major deterioration consists of parallel to subparallel cracking occurring parallel to the formed core surfaces. This type of cracking is characteristic of freezing and thawing action. The concrete tends to be saturated with white alkali-silica gel. The alkali-silica reaction contributed to the concrete cracking. The gel is present as coatings (exudation) on cracks and exterior core surfaces. The calcium hydroxide has carbonated to calcite on exposed surfaces.

33. The black coating observed on a cracked core surface at about 12.5 ft of core S WES-P04.1 is a pliable tar-like substance; it appears to be a bond-breaker material that was applied to the surface examined or that flowed from somewhere else to its present location.

34. It is not possible to determine how much of the damage in the cores was due to freezing and thawing and alkali-silica reaction. An additional mechanism could have caused some of the observed cracking or initiated cracking which allowed freezing and thawing and alkali-silica reaction to begin.

Extent of Damaged Concrete

35. The extent of concrete damage was ascertained from the field investigation and the detailed examination of the core. The photographs of cores presented in Plates 3 through 11 are typical examples of three different concrete conditions, the "OK" (no deterioration), moderate, and severe deterioration. Cross section and orthographic projection drawings were made to show the extent of damaged concrete in the downstream portions of the piers and in the bridge columns; see Plates 12 through 31.

36. There is a distinct difference in the physical condition of the cores representing the "OK" (no deterioration) and the moderately and severely deteriorated concrete; view Plates 3 through 13. The "OK" cores represent sound concrete with an occasional natural break. The term natural break is used to describe a break in the concrete when the mechanism that caused the break is unknown. The cores representing the moderately and severely deteriorated concrete show clear evidence of damage by frost action, i.e., subparallel cracks to the formed surfaces (end of cores). Note that the majority of the damaged concrete is near the formed surfaces; there is little or no damage towards the middle of the core. For all practical purposes the core representing the moderate and severe class concrete can be grouped together when considering their physical condition. Cores from both classifications contain about the same amount of damaged concrete. Core S WES C09.2N is of poor quality; however, it looks worse as a core than the concrete it represents in-place. The broken condition of the core is due to frost action, alkali-silica reaction, and core barrel blockage. The concrete was cracked in place as evidenced by its weathered nature, but broken somewhat during drilling and upon removal from the core barrel.

Piers

37. Cross sections for the three piers (No. 4, No. 9, and No. 15) in which vertical and horizontal borings were drilled are presented in Plates 12, 13, and 14. A small zone of severely deteriorated concrete exists below and downstream of the trunnion shaft for the full 10-ft

width of the pier. The zone extends from station 99.75 ft to a maximum depth at station 98.5 ft in pier No. 4. In pier No. 9 the zone is 0.9 ft deep and in pier No. 15 the zone is 0.4 ft deep. The depth of the zone could be deeper in the piers not drilled. Major cracks in the core recovered from the piers are presented on these three cross sections. The cracks help to explain some of the "no readings, NR," in the downstream portions of the piers.³ Plate 13b shows the location of the ultrasonic velocity measurements taken on pier No. 9 and the cracks observed in borings S WES P09.1 and P09.3. The uppermost crack in P09.1 could account for the "no reading" at stations No. 6 and 7. This plate also indicates that other "no readings" are accounted for by the anchor-
age steel; the interface between the concrete, plastic cork, and the steel would attenuate the transmitted pulse. The in-place velocities obtained by Thornton³ compare well with the velocities recorded on the laboratory test specimens.

38. The physical properties from the pieces of core tested are presented on Plates 12 through 14. Stress-strain curves for selected core from the piers are presented in Plates 15 through 18. Circled numbers adjacent to the borings indicate the location (elevation) from which a test specimen was taken. Like circled numbers, on-line with the various physical properties, represent those numbers adjacent to the cores. The physical properties obtained on the core recovered from the three piers indicate good quality concrete throughout the downstream portion of the piers. The lowest strength is 5840 psi on the uppermost piece of concrete from S WES P15.1. There is no reason to suspect that interior concrete in the other piers has less quality than the concrete tested during this investigation. The concrete in the piers is sound although a few natural breaks are present. These breaks could be sealed by injecting a bonding agent into the breaks.

Columns

39. The extent of damaged concrete in the bridge columns is presented in Plates 19 through 35. Physical property test results for core taken from the columns is included on appropriate plates. The surface extent and depth of damaged concrete can be readily seen on Plates 19

through 35. For those columns where borings were made, the actual depth of damaged concrete is shown. Some of the backsides of the columns (opposite side of columns from the side the drill entered) contained damaged concrete; it is shown where it occurs. The average depth of damaged concrete on the outside in the moderately and severely deteriorated columns is 1 ft. For the moderately and severely deteriorated columns that were not drilled, the 1-ft depth of damaged concrete is believed to exist and is shown. The average depth of damaged concrete on the backside for both the moderate and severe classiflicated columns is 0.25 ft. The middle of the columns do not show freeze-thaw damage. The following tabulation summarizes the depth of damaged concrete in the columns. The greatest amount of damaged concrete was recovered from the downstream and the upstream faces of the columns.


| <u>Core Location</u> | <u>Depth of Damage</u> | |
|----------------------|-------------------------------|-----------------------------|
| | <u>Moderate Deterioration</u> | <u>Severe Deterioration</u> |
| Outside | 1 ft (0.7 ft - 1.7 ft) | 1 ft (0.6 ft - 2.0 ft) |
| Middle | Slight | None |
| Backside | 0.2 ft | 0.3 ft |

The plan cross sectional area of a column is 10.5 ft^2 . Considering the average depth of damage for the full width of a column, the damaged concrete occupies 3.75 ft^2 , there remains within a column 6.75 ft^2 of undamaged concrete.

Physical Property Tests

40. A summary of the physical properties for the "OK", moderate, and severely deteriorated concrete is presented in Figures 1 through 3. Stress-strain curves for selected core taken from the columns are presented in Plates 36 through 43. Some of the compression test specimens were selected to include the damaged concrete; some of the outside and the backside specimens contain damaged concrete. In several cases core that was separated by the action of freezing and thawing was put back together and tested in compression. See photographs in Plates 44 through

"OK"(NO DETERIORATION), COLUMNS




AVERAGE PROPERTIES WITH RANGES

| <u>TEST</u> | <u>OUTSIDE</u> | <u>MIDDLE</u> | <u>BACKSIDE</u> |
|-------------------------------|----------------|------------------------|-----------------|
| γ , lb/ft ³ | 157.5 | 152.5 (152.2-152.8) | 158.0 |
| w , pct | 4.8 | 4.4 | 4.4 |
| V_p , Fps | 15,333 | 15,665 (15,134-16,196) | 15,073 |
| q_u , psi | 9,770 | 9,080 (8,870-9,770) | 10,310 |
| E , $\times 10^6$ psi | 5.04 | 5.55 | 5.34 |
| ν , | 0.25 | 0.19 | 0.18 |

| | <u>Lowest</u> | <u>Average</u> | <u>Highest</u> |
|-------------------------------------|---------------|----------------|----------------|
| Original concrete strength, Class B | 4,710 psi | 5,930 psi | 7,040 psi |

Figure 1. Average physical properties with ranges for the OK class concrete

MODERATE DETERIORATION, COLUMNS




AVERAGE PROPERTIES WITH RANGES

| TEST | OUTSIDE | MIDDLE | BACKSIDE |
|-------------------------------|------------------------|------------------------|----------|
| γ , lb/ft ³ | 156.3 (154.7-160.8) | 151.0 (150.2-152.6) | |
| w , pct | 5.3 (5.0-5.7) | 5.2 (4.9-5.6) | |
| V_p , fps | 11,995 (10,757-14,179) | 13,140 (12,125-13,555) | |
| q_u , psi | 6,630 (6,490-6,720) | 7,650 (7,350-8,250) | |
| E , $\times 10^6$ psi | 1.55 (1.42-1.72) | 3.95 (2.42-3.52) | |
| α | 0.16 (0.14-0.17) | 0.15 (0.14-0.18) | |

| | Lowest | Average | Highest |
|-------------------------------------|-----------|-----------|-----------|
| Original concrete strength, Class B | 4,710 psi | 5,930 psi | 7,040 psi |

Figure 2. Average physical properties with ranges for the moderate class concrete

SEVERE DETERIORATION, COLUMNS



AVERAGE PROPERTIES WITH RANGES

| TEST | OUTSIDE | MIDDLE | BACKSIDE |
|------------------------------|---------------------|------------------------|----------------------|
| γ_c, ft^3 | 152.5 (148.7-160.3) | 150.0 (146.5-154.3) | 150.7 (147.8-154.6) |
| w, pcf | 5.6 (4.9 - 6.2) | 5.4 (4.4 - 6.4) | 5.4 (5.1 - 5.7) |
| $v_p, \text{ft/s}$ | 4,381 (2,774-8,924) | 11,961 (11,111-14,303) | 9,730 (9,090-10,707) |
| μ, psi | 2,760 (2,070-5,450) | 4,700 (3,080-6,050) | 3,770 (2,010-5,750) |
| $E, \times 10^6 \text{ psi}$ | 0.21 (0.18-0.25) | 0.85 (0.38-1.50) | 0.28 (0.20-0.36) |

| | <u>Lowest</u> | <u>Average</u> | <u>Highest</u> |
|-------------------------------------|---------------|----------------|----------------|
| Original concrete strength, Class B | 4,700 psi | 5,930 psi | 7,040 psi |

Figure 3. Average physical properties with ranges for the severe class concrete

46. This procedure was used to determine the lowest remaining concrete strength in the columns. The physical properties will be discussed under the "OK", moderate, and severe classes of concrete. Strengths of cylinders that were cast during construction show the following strengths:

| <u>Lowest</u> | <u>Average</u> | <u>Highest</u> |
|---------------|----------------|----------------|
| 4710 psi | 5930 psi | 7040 psi |

41. "OK". The densities of the outside, middle, and backside core are reasonable for sound concrete; the range is from 152.2 to 158.0 lb/ft³; the average outside, middle, and backside densities are 157.5, 152.5, and 158.0 lb/ft³, respectively. There is a 5- to 6-lb/ft³ difference between the density of the near surface and middle core; the difference is attributed to, in part, the presence of reinforcing bars contained within the near surface cores. The water content of the near surface cores is about the same as the middle core. The moderate and severely deteriorated cores have a water content about 1 percent higher than the "OK" class cores. This higher water content is attributed to the presence of the damaged concrete; the cracked concrete with its increased surface area contains additional water.

42. The velocities are indicative of good quality concrete. The range in velocity is 15,073 to 16,196 ft/sec. The compressive strengths for the near surface and middle concrete are higher than the highest cylinder break obtained during construction. The range in strength is 8,870 to 10,310 psi. The modulus was figured as a secant value to 40 percent of the compressive strength. The modulus ranges from 5.04×10^6 psi to 5.55×10^6 psi. The Poisson's ratio is reasonable for good quality concrete; it ranges from 0.18 to 0.25.

43. Moderate. The outside and middle concrete show about the same difference in the average density, i.e., 5 lb/ft³, as does the "OK" class concrete. The outside core has a greater range in density (154.7-160.8 lb/ft³) than the middle core (150.8-152.6); again the higher density of the outside core is due to the inclusion of reinforcing bar in the outside specimens. The average outside and middle densities are

156.8 lb/ft³ and 151.7 lb/ft³, respectively. The average water contents are 5.3 and 5.2 percent for the outside and middle cores.

44. The difference between the average velocities of the outside and middle core is indicative of the damaged outside concrete. The outside velocity averages 11,995 ft/sec (range is 10,757-14,178 ft/sec) while the middle average is 13,140 ft/sec (range is 12,725-13,555 ft/sec). Note the smaller range of the middle cores, indicating more consistency of the concrete. The average strength of the outside and middle cores is above the average of the cylinder strengths cast during construction. The average outside and middle strengths are 6630 psi and 7650 psi. The average modulus of the outside concrete is about one-half the average modulus of the middle cores. The modulus of the moderately deteriorated concrete is considerably below the modulus of the "OK" classified concrete. The reason for the difference is probably due to the fact that the moderately deteriorated concrete contains cracks and voids that closed up under the compressive load applied to the core, resulting in larger axial deformations and hence lower modulus values. The Poisson's ratio for the outside and middle core is 0.16.

45. Severe. The average density values for the three sections of core are considered the same, 152.5, 150.0, and 150.7 lb/ft³ for the outside, middle, and backside, respectively. The range over the full length of the cores is 146.5-160.3 lb/ft³. The lowest density (146.5 lb/ft³) was obtained for the severe class of concrete and is attributed, in part, to the damage caused by freezing-thawing and alkali-silica reaction. The greatest water content was measured on a piece of core from the severe class of concrete, i.e., 6.4 percent. The average water content for the severe class concrete is slightly above the average water content of the moderate class concrete.

46. There is no appreciable difference between the water contents in cores taken from the top of the columns to near the base of the piers. It was thought that the water contents, with depth, might be different, and if so, help to explain why some of the concrete was more heavily damaged.

47. The velocities measured on this class concrete were the lowest measured on all the cores tested. A velocity of 2,774 ft/sec was obtained on an outside core. The average outside, middle, and backside velocities are 4,381, 11,961, and 9,730 ft/sec, respectively. These relatively low values are indicative of poor quality concrete; the low velocities were anticipated considering the damaged condition of the severe class concrete. The middle cores have velocities ranging from 11,111 to 14,303 ft/sec. Again the middle cores are of better quality than the near surface core.

48. The lowest strengths were obtained from the severe class concrete; 2,070 psi for an outside core and 2,010 psi from a backside core. The lowest strength middle core is 3,080 psi; the lowest strength middle core in the other classes of concrete is 7040 psi. The average modulus values for outside and backside core are 0.21×10^6 psi and 0.28×10^6 psi. Again, large deformations of the core due to cracks and voids in the damaged concrete account for the very low modulus values. The stress-strain curves for the cores containing portions of damaged concrete show the typical stress-strain relation for cores containing open cracks; see Plates 37, 38, 40, and 42. Note the concave upwards portion of the curves which represents closure of the cracks and the voids within the specimen. Poisson's ratios are not available because lateral deformation was not measured on the severe class concrete. There was no easy way of mechanically or electrically monitoring lateral movement of the core due to its broken nature.

PART VI: SUMMARY AND RECOMMENDATIONS

Trunnion Shaft Area

49. A few fine (<1 mm, 0.04 in.) and wide (>2 mm, 0.08 in.) cracks in the concrete exist near and intersect with the trunnion shaft on all piers. Rain water has permeated the concrete along these cracks as evidenced by the presence of stains on surfaces of concrete excavated from around portions of the tainter gate anchorage steel on pier No. 9. An insignificant amount of rusting has occurred on the top 2-ft portion of the trunnion shaft collar on pier No. 9. Because all the piers have cracks in the concrete around the trunnion shafts, it is reasonable to assume that a portion of the collars on all piers is lightly rusted. The H beams of the anchorage are protected by plastic cork and are not rusted in pier No. 9. In conclusion, there is no significant damage due to rusting of the anchorage steel.

Remaining Strength of Concrete

50. The remaining compressive strength of the concrete in the piers is considered to be at least equal to the lowest compressive strength obtained on the core from the piers; that strength is 5840 psi. Except for a small zone of damaged concrete downstream of the trunnion shafts on all the piers, the interior pier concrete is sound and will serve its original intended purpose. A few natural breaks occur in the piers, but these breaks should not affect the structural integrity of the piers.

51. The remaining concrete compressive strength in the columns with the greater amount of damaged concrete is probably between 1000 and 2,000 psi; the exterior 1 ft having the 1,000-psi strength and the interior section having the 2,000-psi strength. The lowest exterior and interior core strengths were 2,010 psi and 3,080 psi, respectively. These strengths have been reduced by 1000 psi to account for a reduction

in strength. The reason for reducing the strength has to do with the difference in strength between horizontal and vertically aligned core that is cracked.

52. All cores from the columns were drilled horizontally and the cracks (closely spaced) caused by frost damage are subparallel to the core axis. Laboratory tests, from an unreported study by the principle author, of jointed concrete specimens indicate that when the joints are perpendicular to the axis of applied load, as were the cracks in the horizontally drilled core, the strength is higher than when the joints are parallel to the applied load. With closely spaced joints parallel to the applied load, eccentric loading results as individual jointed members of the specimen flex. The eccentric loads cause reduced strengths. It is not known how much the actual core strengths should be reduced; however, a 1,000-psi reduction is considered conservative.

53. Columns containing the moderately and severely deteriorated concrete that were not drilled could contain low strength concrete equal to the reduced 1,000- to 2,000-psi strengths.

Columns Adequate to Support Bridge

54. This investigation shows that the columns are not weak enough to crumble under static compressive loads. The study shows that compressive strength between 1,000 and 2,000 psi exists which is about one-half the acceptable value of the lowest original strength of 4,710 psi. Some of the concrete in the columns is now not serving its originally intended purpose. The static analysis that a SLD technical staff member conducted on 1 May 1980, "Dam 24 Service Bridge Pier," shows that 240-psi strength is required from the concrete. Based upon these computations and our strength test results, there is no problem at the present time. The concrete strength will decrease with time if the deterioration of the concrete is allowed to continue. We can not assure the adequacy of the columns due to structural movement or dynamic stresses caused by inordinate vibrations from ice loading or other conditions at the dam. It is

suggested that a dynamic stability analysis of the piers and columns be made to see if they are adequate against some critical loading conditions with the present low strength concrete.

Extent and Cause of Damaged Concrete

55. A small zone of severely deteriorated concrete exists below and downstream of the trunnion shaft for the full width of the pier; i.e., the upper part of the downstream vertical face of the piers. This condition exists on all piers. Depth of the zone is about 1.0 ft.

56. The top portions of the columns contain the greatest amount of damaged concrete; the concrete towards the bottom of the columns is sound. Trapped water on the top of the columns probably infiltrated the concrete and the freezing and thawing action caused damage near the top of the columns. With time the damaged zone has extended downwards. The downstream and upstream faces of the columns contain more damaged concrete than any other column surfaces. These column faces have more exposure to the sun and are subject to more cycles of freezing and thawing. The average depth of damage for the moderately and severely deteriorated columns is 1 ft on the upstream and downstream faces.

57. The lack of entrained air in this concrete caused the concrete to be susceptible to frost damage. The repeated freezing and thawing of the concrete while critically saturated has caused delamination of the concrete, especially near surfaces. The opening of the concrete by frost action has accelerated the alkali-silica reaction. This deleterious chemical reaction has caused additional disaggregation of the frost-damaged concrete. The interior concrete shows slight indications of alkali-silica reaction, but has not caused any significant damage to the interior concrete.

58. Another mechanism could have initiated cracking in selected piers in order for action to begin. For instance, vibration of the dam could have caused microcracking to occur at specific locations along the dam, i.e., on piers No. 5, No. 9, and No. 16. Frost action then could have started at these specific locations. The columns on these three

piers contain much more damaged concrete than do the other columns on any other piers. With all columns exposed to the same environment, and assuming that all the concrete in the columns was of the same quality, some unknown mechanism probably contributed to the damaged concrete that exists in piers No. 5, No. 9, and No. 16.

Structural Cracking

59. District personnel visited the dam and found a burst pipe on pier No. 16. They believe that the structural cracks in the columns on piers No. 9 and No. 16 were caused by bursting pipes and freezing water associated and adjacent to the pipe. Some WES personnel agree that the bursting pipe could cause the concrete to split as was found. However, it should not be overlooked that some of the structural cracks observed at the dam could have been caused in part or in whole by some loading condition other than freezing water. See Appendix D for photographs of the damage concrete due to the burst pipe.

60. The broken section of column No. 3 on pier No. 16 was removed and a 1-1/2-in. diameter pipe, a section of electrical conduit (ref drawing ML 24 56/1), was found to be split as if it had burst. The top of the conduit was once flush with the top of the columns and capped, however, it is now rusted off; see Photograph 5 in Appendix D. Evidently, rain water collecting on the top of the columns had drained into the conduit, frozen, burst the pipe, and cracked portions of the column. The columns on pier No. 9 were examined and it is believed that a similar situation to the one that caused the cracks on pier No. 16 developed on pier No. 9.

61. Original drawings show that 1-1/2-in. diameter electrical conduits are present in all downstream columns. Additionally, the downstream column on the Missouri side of each pier contains a 1-1/2-in. diameter drum-heater conduit which makes a 90-deg bend below the column and continues to a cast-iron junction box located above the trunnion shaft. A single 1/2-in. diameter conduit was provided for drainage of this entire line. According to lock personnel, the junction box and

drain line are silt laden. Also, short conduit elbows, plugged at both ends, were installed in the upstream and downstream cross walls which span between tops of the columns. The electrical conduits, the drum-heater conduits, drain conduits, and conduit elbows are potential sources of water which could be responsible for some of the deterioration of columns and the zone below and downstream of the trunnion shaft. Since these conduits are no longer in use, and if they are not proposed to be used in the future, it is recommended that they be cleaned out, grouted, and capped.

Removal and Repair of Damaged Concrete

62. The basic phenomena which initiated cracking in the concrete columns and piers were not identified in this study; therefore, it is impossible to suggest a repair procedure with any assurance that the same phenomena will not cause similar problems in the repair. It is most important that the basic cause of the cracking be ascertained before final selection of any repair procedure aimed at eliminating future cracking. Lacking this information, any repairs at present must be considered as only remedial work to improve the current condition of the columns and piers.

63. The surface cracks on the piers should be adequately sealed to keep water from infiltrating the concrete, especially in the area of the trunnion shaft. If the water is kept out, rusting of anchorage steel, frost action, and alkali-silica reaction will be greatly reduced.

64. There appear to be two basic approaches for repair of the concrete pier columns. The first approach should be considered an interim repair aimed at reducing the current rate of deterioration. The second approach would involve major rehabilitation of the pier columns.

65. The orientation and extent of cracking in the columns is such that the ingress of moisture (rain, snow, ice, etc.) from the top surfaces of the columns and cross members contributes to freezing and thawing and alkali-silica reaction within the concrete. Potential procedures to minimize this ingress of moisture would include (1) sloping the tops

of the columns and cross members to insure drainage towards the interior opening between the columns, (2) drilling holes along the lift joint between the columns and column facing to allow drainage to the outside of the columns, and (3) sealing the top surfaces of the columns and cross members. In this case the latter approach appears to offer ease of construction and the greatest potential for success. A number of materials are available to seal these horizontal surfaces; however, based on previous experience a heavy duty membrane of rubberized asphalt integrally bonded to polypropylene mesh is suggested. The use of such a membrane should be restricted to horizontal surfaces with the possible exception of those vertical surfaces within 3 to 6 in. of the tops of the columns. Such an overlap would allow installation of a mechanical band around the columns to further secure the membrane. Specifications for this membrane are included in Table 3. This approach should reduce the rate of deterioration while additional work is being done to determine the basic cause of deterioration or until major rehabilitation of the pier columns is initiated.

66. Major rehabilitation would involve removal of unsound concrete from those areas previously described as moderately or severely deteriorated and replacement with new concrete; i.e., the upper part of the downstream face of the piers and certain pier columns. It is anticipated that the location and extent of reinforcing steel and the strength of the existing concrete will be such that concrete removal may be difficult. The concrete removal operation should be closely monitored to insure that the amount of concrete removed is kept to the minimum necessary for replacement with new concrete. In general this minimum depth would be that necessary to completely expose the outer layer of reinforcing.

67. It is recommended that the surface removal of distressed/deteriorated concrete from the piers and the bridge columns be done using high-pressure water jets. The reasoning behind the selection of the water jet over conventional removal methods is amount of reinforcing steel in the concrete. The water jet leaves the steel reinforcing clean and undamaged for reuse, thus eliminating the need for replacement steel. In addition to reinforcing the concrete, the steel will act as a dowel

between the existing and replacement concrete allowing loads to be transferred between them. Other advantages of the water jet are:

- a. Minimal damage to the concrete that remains is produced.
- b. Irregular shaped volumes can be removed.
- c. No dust and little noise are produced.

The main concern with the water jet is its variable productivity rate. Under certain conditions, such as cutting concrete containing large abrasive-resistant aggregate, this rate can be very low. To avoid contracting a jet with undesirable productivity rate, it is recommended that a short-term (say, 3 days) pilot test program be used to determine the productivity and acceptability of the jet. The following contractors are among the most promising for doing a satisfactory removal job:

Flow Industries
Kent, Washington
(206) 872-8500

McCartney Mfg Co., Inc.
Baxter Springs, Kansas
(316) 856-2151

iIT Research Institute
Chicago, Illinois
(312) 567-4400

Daedalean Associates, Inc.
Woodbine, Maryland
(301) 442-2620

68. In those cases where 50 percent or more of the concrete column area is expected to require removal, consideration should be given to providing temporary support for the column loads and completely removing and replacing the existing columns. Either sawing or explosives is suggested for concrete removal in these instances.

69. Replacement concrete should be proportioned in accordance with current standard practice. Particular attention should be given to freezing and thawing resistance and the potential for alkali-silica reaction.

70. Some recent rehabilitation projects have encountered cracking in the replacement concrete. In general these problems were associated with concrete overlays which were rather thin relative to the remaining

concrete monoliths. Such problems appear to be the result of the tremendous restraint provided by the existing concrete making thermal considerations during construction even more important than in new construction. While the concrete sections involved in this work are relatively small, the potential for thermal cracking still exists. Attention should be given to minimize temperature differentials between existing and replacement concrete during placing and curing of the replacement concrete. Also, differentials in temperature between the replacement concrete and ambient at the time of form removal and immediately following should be within 25 F or less.

71. Depending upon when this repair is scheduled, a vacuum polymer impregnation technique currently under development may have potential application. This technique consists of wrapping the structure in polyethylene and creating a vacuum through the use of a vacuum pump. A resin is then injected and flows, through the cracks in the structure, towards the source of the vacuum. The vacuum evacuates water and fine contaminants from the fissures prior to impregnation with the resin. With the aid of the vacuum, resin penetrates throughout the crack system and dust or loose particles acts as a filler in the resin. Repair is accomplished without removal of damaged concrete. Fine aggregate may be mixed with the resin to repair large cracks, voids, or badly deteriorated surfaces. The technique is currently being investigated by application to damaged 6-in. by 12-in. cylinders and 3-1/2- by 4-1/2- by 16-in. beams. Damage is being produced for laboratory testing by compressive and splitting tensile testing, exposure to high temperature (1000⁰ F), accelerated freezing and thawing, and accelerated alkali-silica reaction. If laboratory testing continues to show favorable results, this technique may warrant field testing on one or more of the damaged piers or columns.

REFERENCES

1. U. S. Army Engineer Waterways Experiment Station Petrographic Report, dated 23 January 1976, subject, "Tests and Examination of Concrete Cores from Lock and Dam 24 and Lock and Dam 25," Vicksburg, Miss.
2. U. S. Army Engineer Waterways Experiment Station Petrographic Report, dated 4 December 1978, subject, "Project Examination of Fragmented Concrete Cores from Lock and Dam 24, U. S. Army Engineer District, St. Louis," Vicksburg, Miss.
3. Thornton, Henry T., Jr. and Glass, Dale, "Ultrasonic Velocity Measurements in Concrete, Lock and Dam No. 24, Mississippi River," WES Miscellaneous Paper SL-80-2, Apr 1980, Vicksburg, Miss.
4. ACI Committee 201, "Guide for Making a Condition Survey of Concrete in Service," ACI Journal, Proceedings, Vol 65, No. 11, Nov 1968, pp 905-918.
5. U. S. Army Engineer District, St. Louis, "Periodic Inspection Report No. 3, Lock and Dam No. 24, Mississippi River," Sep 1977.
6. U. S. Army Engineer Waterways Experiment Station, CE, "Handbook for Concrete and Cement," with quarterly supplements, Vicksburg, Miss., Aug 1949.

Table 1

Inspection Team, Lock and Dam No. 24

| <u>Name</u> | <u>Organization</u> |
|----------------|---------------------|
| Riley Pope | SLD-ED |
| Mel Stegall | SLD-ED |
| Don Buckley | Lockmaster |
| Carl Pace | WESSC |
| Henry Thornton | WESSC |
| Richard Stowe | WESSC |

Table 2


Directions, Locations, Elevations, Horizontal Boring Depths, and Starting Dates

| Boring No. S WES | Direction of Boring | Location | El Top of Boring ft | El Bottom of Boring ft | Depth of Horizontal Boring, ft | Start Date |
|---------------------|------------------------|-------------------|---------------------------|------------------------------|--------------------------------------|-------------|
| P04.1-80 | Vertical | Pier, D/S portion | 454.0 | 440.3 | | 30 Oct 1980 |
| P04.2-80 | Inclined 90° | Pier, D/S portion | 448.0 | 448.0 | 6.4 | 28 Nov 1980 |
| P09.1-80 | Vertical | Pier, D/S portion | 454.0 | 439.8 | | 28 Oct 1980 |
| P09.3-80 | Vertical | Pier, D/S portion | 444.0 | 431.2 | | 24 Nov 1980 |
| P09.2-80 | Inclined 90° | Pier, D/S portion | 448.0 | 448.0 | 5.9 | 06 Nov 1980 |
| P15.1-80 | Vertical | Pier, D/S portion | 454.0 | 412.9 | | 21 Oct 1980 |
| P15.2-80 | Inclined 90° | Pier, D/S portion | 448.1 | 448.1 | 6.55 | 07 Nov 1980 |
| C02.2N-80 | Inclined 90° | Column | 468.6 | 468.6 | 3.5 | 21 Nov 1980 |
| C07.3N-80 | Inclined 90° | Column | 464.7 | 464.7 | 3.5 | 13 Nov 1980 |
| C13.2N-80 | Inclined 90° | Column | 462.0 | 462.0 | 3.5 | 11 Nov 1980 |
| C13.3N-80 | Inclined 90° | Column | 460.0 | 460.0 | 3.55 | 21 Nov 1980 |
| C09.2N-80 | Inclined 90° | Column | 469.2 | 469.2 | 3.6 | 12 Nov 1980 |
| C09.3N-80 | Inclined 90° | Column | 467.3 | 467.3 | 3.5 | 19 Nov 1980 |
| C16.3N-80 | Inclined 90° | Column | 475.4 | 475.4 | 3.5 | 10 Nov 1980 |
| C16.3E-80 | Inclined 90° | Column | 469.0 | 469.0 | 3.0 | 20 Nov 1980 |
| C05.1W-80 | Inclined 90° | Column | 466.5 | 466.5 | 3.1 | 18 Nov 1980 |
| C05.1S-80 | Inclined 90° | Column | 465.5 | 465.5 | 3.5 | 17 Nov 1980 |
| C05.4S-80 | Inclined 90° | Column | 466.5 | 466.5 | 3.5 | 18 Nov 1980 |
| C09.1W-80 | Inclined 90° | Column | 466.0 | 466.0 | 3.05 | 14 Nov 1980 |
| C09.1S-80 | Inclined 90° | Column | 468.0 | 468.0 | 3.50 | 14 Nov 1980 |
| C09.4S-80 | Inclined 90° | Column | 465.7 | 465.7 | 3.5 | 19 Nov 1980 |
| C16.1S-80 | Inclined 90° | Column | 475.45 | 475.45 | 3.6 | 08 Nov 1980 |
| C16.1W-80 | Inclined 90° | Column | 466.9 | 466.9 | 3.1 | 13 Nov 1980 |
| C16.2N-80 | Inclined 90° | Column | 467.45 | 467.45 | 3.5 | 10 Nov 1980 |
| H5.1-80 | Inclined 90° | Column | 471.6 | 471.6 | 0.72 | 01 Dec 1980 |

Table 3
Description of Asphaltic Membrane


| TYPE AND CONSTRUCTION | | SPECIFICATIONS | | APPLICATIONS | |
|----------------------------|-------|---|-----------------------------|--|---|
| | | PROPERTY | AVERAGE TEST VALUE | TEST METHOD | WATERPROOFING |
| STANDARD GRADE | | PERMEANCE SI (Ng m ² Sec Pa) Polyethylene Rubberized Bitumen | 5.72 1.43 | ASTM E 96 METHOD B | Above & Below Ground foundations tanking, plazas and terraces, non-exposed roofing and reservoirs |
| Polyethylene Sheet | 0.1mm | WATER ABSORPTION % by weight in 72 hours | 0.22% | ASTM D 1228 | |
| Bitumen-Rubber Compound | 1.5mm | PLIABILITY 180° bend over 25mm mandrel at -32 C | Unaffected | ASTM D 146 | |
| Total | 1.6mm | CYCLING over crack at -26° C | Unaffected | 100 cycles over 0-6.4mm distance | |
| Interwound Release Paper | 0.2mm | 25mm joint at -26° C | Unaffected | 1000 cycles over 19.0-31.8mm distance | |
| | | TENSILE STRENGTH Polyethylene | 280 kg sq. cm 27 580 kPa | ASTM D 412 (Die C) modified | |
| | | ELONGATION % of original distance at ultimate failure Rubberized Bitumen | 300% | ASTM D 412 (Die C) modified | |
| | | PUNCTURE RESISTANCE Stretched by Blunt Object | 25kg | ASTM E 154 | |
| | | PEEL ADHESION Membrane is peeled at 90° angle | 1.86kg/cm width | 7 days dry at 21 C 7 days dry at 49 C 7 days wet at 21 C | |
| HEAVY DUTY | | Specifications as for STANDARD GRADE except for the following | | | Vehicular traffic structures, parking decks, bridge decks and highways |
| Polypropylene Mesh | 0.3mm | PUNCTURE RESISTANCE Stretched by blunt Object | 118kg | ASTM E 154 | |
| Bitumen-Rubber Compound | 1.5mm | | | | |
| Total | 1.8mm | | | | |
| Interwound Release Paper | 0.2mm | | | | |
| BITUTHENE CRM* | | Specifications as for STANDARD GRADE except | | | New Roofing Re-Roofing Remedial Roofing |
| Polyethylene Sheet | 0.2mm | PLIABILITY 180° bend over 6.4mm mandrel at -37 | Unaffected | ASTM D 146 | |
| Bitumen-Rubber Compound | 1.5mm | CYCLING over crack at -32 C | Unaffected | 200 cycles over 0-6.4mm | |
| Total | 1.7mm | 6.4mm joint at -32 C | Unaffected | 3 000 cycles over 3.2-9.5mm distance | |
| Interwound Release Paper | 0.2mm | PUNCTURE RESISTANCE Stretched by blunt object | 120kg | ASTM E 154 | |
| | | | | | |

CRM = Compliant roofing membrane



PLAN VIEW

| SYMBOL | CONCRETE CONDITION | DESCRIPTION | No. of COLUMNS | PERCENT TOTAL |
|--------|---|--|----------------|---------------|
| OK | OK | No signs of deterioration | 12 | 20 |
| VL | Very light deterioration | Local hairline, one per 9 m ² area, slight exudation | 12 | 20 |
| L | Light deterioration | Local cracks, fine, one per 9 m ² area, slight exudation | 17 | 28 |
| | Moderate deterioration | Zone cracking, medium, one crack per 3 to 4-in. heavy exudation covering 50% of zone | 10 | 17 |
| | Severe deterioration | Zone cracking, medium to wide, one crack per 2 to 3-in. heavy exudation covering 75% of zone | 9 | 15 |
| * | Fine 1 mm (0.04 in.) Medium 1 to 2 mm (0.04 to 0.08 in.) Wide 2 mm (0.08 in.) | | | |
| ⊙ | Vertical boring 6 × 6 1/2-in. (157-in. core) | | | |
| — | Horizontal boring in pier 6 × 6 1/2-in. (157-in. core) | | | |
| NOTE | Vertical and horizontal arrows denote horizontal borings in columns 6 × 6 1/2-in. (157-in. core). A small area of severely deteriorated concrete exists downstream of the trunnion shaft; the zone is not shown on this plate; see Photo No. 1, Appendix A, for typical damage zone. | | | |



PLAN VIEW DAM





PLATE 1

3



C 13.25






PLATE 3




C. 13. 38





C. 100, 25



C. 100, 30

NO. 101 RATT



C 09.3N

MODERATE



C 16.2N




C 16.1S



SEVEN




C 5.18



C 05.28

SECRET



C 09.1K




SEVERE

C 09.1S




P 09.2
PIER

| | γ <u>lb/ft^3</u> | w <u>pct</u> | V_p <u>psf</u> | q_u <u>psi</u> | E <u>$\times 10^6 \text{ psi}$</u> | ν |
|---|--|-------------------|---|---|--|-------|
| ① | 155.4 | 5.0 | 15,651 | 8,050 | | |
| ② | 153.5 | 4.7 | 15,873 | 10,410 | | |
| ③ | 152.3 | 4.6 | 14,166 | 10,020 | 5.53 | 0.17 |
| ④ | 154.0 | 4.6 | 14,416 | 7,180 | 1.99 | 0.12 |
| ⑤ | 151.4 | 3.9 | 16,527 | 7,800 | | |
| ⑥ | 152.4 | 4.6 | 16,639 | 6,970 | 6.03 | 0.18 |




CROSS SECTION PIER #4

| | γ <u>lb/ft³</u> | w <u>pcf</u> | V_p <u>fps</u> | q_u <u>psi</u> | E <u>*10⁶psi</u> | ν |
|---|--------------------------------------|-------------------|---------------------|---------------------|----------------------------------|-------|
| ① | 152.3 | 4.5 | 13,715 | 6,830 | 2.98 | 0.13 |
| ② | 152.3 | 4.7 | 15,037 | 7,910 | | |
| ③ | 151.6 | 5.0 | 15,064 | 9,130 | 5.20 | 0.18 |
| ④ | 152.1 | 5.6 | 13,515 | 7,970 | 2.89 | 0.21 |
| ⑤ | 148.6 | 4.0 | 15,625 | 8,300 | 4.95 | 0.18 |
| ⑥ | 151.0 | 4.5 | 14,987 | 7,960 | | |
| ⑦ | 154.3 | 5.2 | 15,024 | 9,010 | 5.34 | 0.18 |
| ⑧ | 152.3 | 4.1 | 15,172 | 8,550 | | |




CROSS SECTION PIER #9


PIER NO. 9



| | γ lb/ft ³ | w pcf | V_p fps | q_u psi | E $\times 10^6$ psi | ν |
|---|--------------------------------|------------|--------------|--------------|--------------------------|-------|
| ① | 151.0 | 6.0 | 14,404 | 5,840 | 2.80 | 0.14 |
| ② | 151.6 | 4.2 | 15,126 | 8,380 | 5.84 | 0.22 |
| ③ | 151.0 | 4.3 | 15,625 | 7,000 | | |



CROSS SECTION PIER #15









PLATE 16

PLATE 18



COLUMNS PIER #1



| <u>CLASS</u> | <u>CORE</u> | <u>TEST</u> |
|-----------------|-------------|-------------|
| <u>CONCRETE</u> | <u>NO.</u> | |


| <u>PHYSICAL PROPERTIES</u> | | |
|----------------------------|---------------|-----------------|
| <u>OUTSIDE</u> | <u>MIDDLE</u> | <u>BACKSIDE</u> |
| | | |

No damaged concrete, no core take
 * Column numbers

| | | |
|--|--|--|
|  OK |  MODERATE |  SEVERE |
|--|--|--|

SCALE 1/8" = 1'

COLUMNS PIER #2





| <u>CLASS</u> | <u>CORE</u> | <u>TEST</u> |
|-----------------|-------------|--|
| <u>CONCRETE</u> | <u>NO.</u> | |
| OK | C 02.2N | γ , lb/ft ³ W, pct Vp, fps q _u , psi |

| <u>PHYSICAL PROPERTIES</u> | | |
|----------------------------|---------------|-----------------|
| <u>OUTSIDE</u> | <u>MIDDLE</u> | <u>BACKSIDE</u> |
| | 152.9 | |
| | 4.4 | |
| | 16,196 | |
| | 8,870 | |



SCALE 1/8" = 1'




COLUMNS PIER #3



| <u>CLASS</u> | <u>CORE</u> | <u>TEST</u> |
|-----------------|-------------|-------------|
| <u>CONCRETE</u> | <u>NO.</u> | |



| <u>PHYSICAL PROPERTIES</u> | | |
|----------------------------|---------------|-----------------|
| <u>OUTSIDE</u> | <u>MIDDLE</u> | <u>BACKSIDE</u> |
| | | |

Lt damage over columns, no core taken.

| | | |
|---|--|--|
|  LIGHT |  MODERATE |  SEVERE |
|---|--|--|

SCALE 1/8" = 1'

COLUMNS PIER #4



| CLASS | CORE | TEST |
|----------|------|------|
| CONCRETE | NO. | |


| PHYSICAL PROPERTIES | | |
|---------------------|--------|----------|
| OUTSIDE | MIDDLE | BACKSIDE |
| | | |

No core taken.

| | | |
|---|--|--|
|  LIGHT |  MODERATE |  SEVERE |
|---|--|--|

SCALE 1/8" = 1'

COLUMNS PIER #5




| CLASS CONCRETE | CORE NO. | TEST | PHYSICAL PROPERTIES | | |
|-------------------|-------------|--|--|---|---|
| | | | OUTSIDE | MIDDLE | BACKSIDE |
| SEV | COS.1S | γ , lb/cu ft w, pct vp, fps qu, psi E, x10 ⁶ psi | 148.7 5.6 4,602 3,860 0.24 | 150.0 5.1 14,303 5,380 0.88 | 154.6 5.0 9,093 5,750 |
| SEV | COS.4S | γ , lb/cu ft w, pct vp, fps qu, psi E, x10 ⁶ psi | | | 147.8 5.4 10,707 3,570 0.36 |
| SEV | COS.1W | No tests | | | |

L LIGHT
 ||| MODERATE
 /// SEVERE

SCALE 1/8" = 1'

COLUMNS PIER #6



| CLASS | CORE | TEST |
|----------|------|------|
| CONCRETE | NO. | |


| PHYSICAL PROPERTIES | | |
|---------------------|--------|----------|
| OUTSIDE | MIDDLE | BACKSIDE |
| | | |

Lf. damage over columns 1, 2 & 4. No core taken.


| | | |
|--|--|---|
| <div style="border: 1px solid black; padding: 2px; display: inline-block;">L</div> LIGHT | <div style="border: 1px solid black; padding: 2px; display: inline-block; background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px);"></div> MODERATE | <div style="border: 1px solid black; padding: 2px; display: inline-block; background: repeating-linear-gradient(-45deg, transparent, transparent 2px, black 2px, black 4px);"></div> SEVERE |
|--|--|---|

SCALE 1/8" = 1'

COLUMNS PIER #7



LOOKING UPSTREAM



LOOKING DOWNSTREAM

| <u>CLASS</u> | <u>CORE</u> | <u>TEST</u> |
|-----------------|-------------|-------------|
| <u>CONCRETE</u> | <u>NO.</u> | |
| OK | C07.3N | No tests |


| <u>PHYSICAL PROPERTIES</u> | | |
|----------------------------|---------------|-----------------|
| <u>OUTSIDE</u> | <u>MIDDLE</u> | <u>BACKSIDE</u> |

Lt. damage over columns 1 & 4


2 LIGHT
 MODERATE
 SEVERE

SCALE 1/8" = 1'

COLUMNS PIER #8



LOOKING UPSTREAM



LOOKING DOWNSTREAM

| <u>CLASS</u> | <u>CORE</u> | <u>TEST</u> |
|--------------|-------------|-------------|
| CONCRETE | NO. | |



| <u>PHYSICAL PROPERTIES</u> | | |
|----------------------------|---------------|-----------------|
| <u>OUTSIDE</u> | <u>MIDDLE</u> | <u>BACKSIDE</u> |
| | | |

Very light damage over column 4

| | | | | | |
|---|------------|--|----------|---|--------|
| <div style="border: 1px solid black; padding: 2px; display: inline-block;">VL</div> | VERY LIGHT | <div style="border: 1px solid black; padding: 2px; display: inline-block; width: 20px; height: 10px; background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px);"></div> | MODERATE | <div style="border: 1px solid black; padding: 2px; display: inline-block; width: 20px; height: 10px; background: repeating-linear-gradient(-45deg, transparent, transparent 2px, black 2px, black 4px);"></div> | SEVERE |
|---|------------|--|----------|---|--------|

SCALE 1/8" = 1'

COLUMNS PIER #9



| | | | <u>PHYSICAL PROPERTIES</u> | | |
|---------------------------------|---------------------------|----------------------|----------------------------|---------------|-----------------|
| <u>CLASS</u> <u>CONCRETE</u> | <u>CORE</u> <u>NO.</u> | <u>TEST</u> | <u>OUTSIDE</u> | <u>MIDDLE</u> | <u>BACKSIDE</u> |
| SEV | CO9.1S | $\gamma, lb/ft^3$ | 149.1 | 149.5 | |
| | | w, pcf | 6.0 | 6.4 | |
| | | V_p, f_{ps} | 5,781 | 11,721 | |
| | | q_u, psi | 2,880 | 3,080 | |
| | | $E, \times 10^6 psi$ | 0.18 | 0.63 | |
| | | | | | |
| MOD | CO9.3N | $\gamma, lb/ft^3$ | 160.8 | 150.8 | |
| | | w, pcf | 5.7 | 4.8 | |
| | | V_p, f_{ps} | 11,050 | 12,725 | |
| | | q_u, psi | 6,680 | 7,040 | |
| | | $E, \times 10^6 psi$ | 1.72 | 2.42 | |
| | | ν | 0.17 | 0.14 | |
| SEV | CO9.4S | $\gamma, lb/ft^3$ | 150.1 | 146.5 | |
| | | w, pcf | 6.2 | 5.5 | |
| | | V_p, f_{ps} | 8,924 | 10,709 | |
| | | q_u, psi | 2,070 | 4,280 | |
| | | $E, \times 10^6 psi$ | 0.25 | 0.38 | |
| | | | | | |



STRUCTURAL
CRACK





MODERATE



SEVERE

SCALE 1/8" = 1'

COLUMNS PIER #10



| CLASS | CORE | TEST |
|----------|------|------|
| CONCRETE | NO. | |

| PHYSICAL PROPERTIES | | |
|---------------------|--------|----------|
| OUTSIDE | MIDDLE | BACKSIDE |
| | | |



No core taken
Very light column 4; light column 1.

* CRACKS CAUSED BY BARGE IMPACT, EPOXY FILLED.

| | | | | | |
|--|------------|---|----------|---|--------|
| <div style="border: 1px solid black; padding: 2px;">VL</div> | VERY LIGHT | <div style="border: 1px solid black; padding: 2px;"> </div> | MODERATE | <div style="border: 1px solid black; padding: 2px;">///</div> | SEVERE |
| <div style="border: 1px solid black; padding: 2px;">L</div> | LIGHT | | | | |

SCALE 1/8" = 1'

COLUMNS PIER #11



| <u>CLASS</u> | <u>CORE</u> | <u>TEST</u> |
|-----------------|-------------|-------------|
| <u>CONCRETE</u> | <u>NO.</u> | |

| <u>PHYSICAL PROPERTIES</u> | | |
|----------------------------|---------------|-----------------|
| <u>OUTSIDE</u> | <u>MIDDLE</u> | <u>BACKSIDE</u> |
| | | |

No core taken.

* Slight honeycombing, no exudation.



LIGHT





MODERATE



SEVERE

SCALE 1/8" = 1'

COLUMNS PIER #12



| <u>CLASS</u> | <u>CORE</u> | <u>TEST</u> |
|--------------|-------------|-------------|
| CONCRETE | NO. | |


| <u>PHYSICAL PROPERTIES</u> | | |
|----------------------------|---------------|-----------------|
| <u>OUTSIDE</u> | <u>MIDDLE</u> | <u>BACKSIDE</u> |
| | | |

No core taken
 Lt damage columns 1 & 4.

| | | | | | |
|--|------------|---|----------|---|--------|
| <div style="border: 1px solid black; padding: 2px;">VL</div> | VERY LIGHT | <div style="border: 1px solid black; padding: 2px; text-align: center;"> </div> | MODERATE | <div style="border: 1px solid black; padding: 2px; text-align: center;">///</div> | SEVERE |
|--|------------|---|----------|---|--------|

SCALE 1/8" = 1'

COLUMNS PIER #13





| <u>CLASS</u> <u>CONCRETE</u> | <u>CORE</u> <u>NO.</u> | <u>TEST</u> |
|---------------------------------|---------------------------|-------------------------------|
| OK | C13.3N | γ , lb/ft ³ |
| | | w, pct |
| | | Vp, fps |
| | | QU, psi |
| | | E, $\times 10^6$ psi |
| | | ν |

| <u>PHYSICAL PROPERTIES</u> | | |
|----------------------------|---------------|-----------------|
| <u>OUTSIDE</u> | <u>MIDDLE</u> | <u>BACKSIDE</u> |
| 157.5 | 152.2 | 158.4 |
| 4.8 | 4.4 | 4.4 |
| 15,333 | 15,134 | 15,073 |
| 9,770 | 9,280 | 10,310 |
| 5.04 | 5.55 | 5.34 |
| 0.25 | 0.19 | 0.18 |

VL VERY LIGHT
 MODERATE
 SEVERE

SCALE 1/8" = 1'

COLUMNS PIER #14



| CLASS | CORE | TEST |
|----------|------|------|
| CONCRETE | NO. | |



| PHYSICAL PROPERTIES | | |
|---------------------|--------|----------|
| OUTSIDE | MIDDLE | BACKSIDE |
| | | |

No core taken.
Very light Columns 1 & 4.

| | | | | | |
|--|------------|---|----------|---|--------|
| <div style="border: 1px solid black; padding: 2px;">VL</div> | VERY LIGHT | <div style="border: 1px solid black; padding: 2px; text-align: center;"> </div> | MODERATE | <div style="border: 1px solid black; padding: 2px; text-align: center;">///</div> | SEVERE |
|--|------------|---|----------|---|--------|

SCALE 1/8" = 1'

COLUMNS PIER #15



| <u>CLASS</u> | <u>CORE</u> | <u>TEST</u> |
|-----------------|-------------|-------------|
| <u>CONCRETE</u> | <u>NO.</u> | |

| <u>PHYSICAL PROPERTIES</u> | | |
|----------------------------|---------------|-----------------|
| <u>OUTSIDE</u> | <u>MIDDLE</u> | <u>BACKSIDE</u> |
| | | |


No core taken.

All columns very light damage to concrete.



| | | | | | |
|--|------------|---|----------|---|--------|
| <div style="border: 1px solid black; padding: 2px;">VL</div> | VERY LIGHT | <div style="border: 1px solid black; padding: 2px; text-align: center;">≡</div> | MODERATE | <div style="border: 1px solid black; padding: 2px; text-align: center;">▨</div> | SEVERE |
|--|------------|---|----------|---|--------|

SCALE 1/8" = 1'

COLUMNS PIER #16





| CLASS CONCRETE | CORE NO. | TEST | PHYSICAL PROPERTIES | | |
|-------------------|-------------|-------------------------------------|---------------------|--------|----------|
| | | | OUTSIDE | MIDDLE | BACKSIDE |
| SEV | C16.1S | $\gamma, lb/ft^3$ | 154.0 | 154.3 | 149.6 |
| | | w, pct | 5.3 | 4.4 | 5.7 |
| | | V_p, fps | 2,774 | 11,111 | 9,385 |
| | | q_u, psi | 2,240 | 6,050 | 2,010 |
| | | $E, \times 10^6 psi$ | 0.18 | 1.50 | 0.20 |
| | | ν | | 0.18 | |
| SEV | C16.1W | $\gamma, lb/ft^3$ | 160.3 | | |
| | | w, pct | 4.9 | | |
| | | q_u, psi | 5,450 | | |
| SEV | C16.2N | No tests due to breaks and repairs. | | | |
| MOD | C16.3E | $\gamma, lb/ft^3$ | | 154.7 | |
| | | w, pct | | 5.1 | |
| | | V_p, fps | | 14,178 | |
| | | q_u, psi | | 6,720 | |



SCALE 1/8" = 1'

COLUMNS PIER #16 (CONT.)



| <u>CLASS</u> <u>CONCRETE</u> | <u>CORE</u> <u>NO.</u> | <u>TEST</u> |
|---------------------------------|---------------------------|--|
| MOD | C16.3N | $\gamma, lb/ft^3$ w, pct v_p, fps q_u, psi $E, \times 10^6 psi$ ν |

| <u>PHYSICAL PROPERTIES</u> | | |
|----------------------------|---------------|-----------------|
| <u>OUTSIDE</u> | <u>MIDDLE</u> | <u>BACKSIDE</u> |
| 154.8 | 152.6 | |
| 5.0 | 5.6 | |
| 10,757 | 13,555 | |
| 6,490 | 8,250 | |
| 1.42 | 3.52 | |
| 0.14 | 0.18 | |



OK




MODERATE





SEVERE


SCALE 1/8" = 1'

PLATE 36














PLATE 40





Photographs showing damaged and undamaged concrete cores selected for compressive strength testing; SEES C05.18 and SWES C05.4S



Photographs of damaged concrete cores selected for compressive strength testing;
SWES C09.1S and SWES C09.4S



Photograph of SWES C16.1S showing damaged concrete core
representing the outside and backside of column No. 1
on pier 16

APPENDIX A: TYPICAL PHOTOGRAPHS
SHOWING DAMAGED CONCRETE




Photo 1. Looking across dam from pier No. 1. Typical cracking pattern with exudation downstream of trunnion pin, pier No. 2



Photo 2. Looking upstream from pier No. 1. Moderately deteriorated concrete on service bridge support column, pier No. 2



Photo 3. Looking at downstream faces of service bridge support columns, pier No. 9. Typical crack pattern and exudation of severe deterioration



Photo 4. Looking downstream on left dam abutment pier No. 16




Photo 5. Looking downstream, left dam abutment pier No. 16. Structural crack high on downstream column. Crack ± 1 -in. wide



Photo 6. Looking downstream, left dam abutment pier No. 16. Structural crack low on upstream column diagonal to column shown in Photo 5



Photo 7. Close up of crack shown in Photo 6. Note large aggregates as well as concrete matrix is fractured




Photo 8. Looking upstream at trunnion shaft area. Typical crack pattern where anchorage collars extend from concrete



Photo 9. Looking upstream at trunnion shaft area. Note wetted area of concrete next to anchorage collar



Photo 10. Looking downstream at trunnion shaft area. Portions of anchorage steel and reinforcing steel exposed by excavating the surrounding concrete



Photo 11. Close up of trunnion shaft anchorage collar,
note minor rusted collar steel



Photo 12. Excavation carried deeper. Note minor rusting
on anchorage collar steel and cross member steel plate

ARMY ENGINEER WATERWAYS EXPERIMENT STATION VICKSBURG--ETC F/6 13/2
CONDITION SURVEY, REPAIR AND REHABILITATION, LOCK AND DAM NUMBE--ETC(U)
AUG 81 R L STOWE, H T THORNTON
WES/MP/SL-81-21 NL

NIL

$\Delta \nabla \Delta$
 $10^2, 6, 6, 4$

END
DATE
FILMED
11-8
PTIC




Photo 13. Looking upstream at cross member steel plate in foreground and anchorage collar in the background partially uncovered

APPENDIX B: FIELD CORE LOGS

Hole No. **SAES-C16.3E-8C**

| | | | |
|---|--|--|--|
| DRILLING LOG | | INSTALLATION | |
| PROJECT St. Louis, Mo | | LOG AND DATA No. 24 | |
| LOG No. 24 | | NO. SHEET AND TYPE OF BIT 6" SEC BELOW | |
| LOCATION (Continuation of Station) | | 17. DEPTH FOR ELEVATION SHOWN (FEET or METERS) | |
| SEE BELOW | | NISL | |
| 1. DRILLING AGENCY | | 12. MANUFACTURER'S DESIGNATION OF DRILL | |
| CH-16.3E | | ELECTRIC RIG - CONG DRILL | |
| 2. HOLE NO. (As shown on drawing title) and its number | | 13. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN | |
| SAES-C16.3E-8C | | | |
| 3. NAME OF DRILLER | | 14. TOTAL NUMBER CORE BOXES | |
| H. McNamee | | ONE | |
| 4. DIRECTION OF HOLE | | 15. ELEVATION GROUND WATER | |
| <input type="checkbox"/> VERTICAL <input checked="" type="checkbox"/> INCLINED 90° OBS. FROM VERT. | | | |
| 5. THICKNESS OF OVERBURDEN | | 16. DATE HOLE | |
| | | 20 NOVEMBER 50 <input checked="" type="checkbox"/> STARTED <input type="checkbox"/> COMPLETED | |
| 6. DEPTH DRILLED INTO ROCK | | 17. ELEVATION TOP OF HOLE | |
| 30' | | 469.0 | |
| 7. TOTAL DEPTH OF HOLE | | 18. TOTAL CORE RECOVERY FOR BORING | |
| | | 100% | |
| | | 19. SIGNATURE OF INSPECTOR | |
| | | [Signature] | |

| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Descriptive) | % CORE RECOVERY | BOX OR SAMPLE NO. | REMARKS (Drilling time, water level, depth of penetration, etc., if significant) |
|---|-------|-----------------------|---|-----------------|-------------------|--|
| 4690 | 10 | CRACKS - CLOSED NB | | | | Run No. 1 20 Nov 50 RL — Run 30 Begad 1000 Rec 30 End 1113 Loss — Time 7 min Gals — Drl time 20 min Hydr pres — Water pressure — RE: 3000 Drl Action Suppl Water ret Barrel Remarks |
| 4690 | 10 | Δ | CONCRETE | 100% | Box 1 | |
| 4690 | 20 | Δ | | | | |
| 4690 | 30 | Δ | Run No. 1 ROD = 88 3/4" | 3.0 | | |
| CONCRETE PHYSICAL PROPERTIES SAME - CONCRETE IS IN FAIR CONDITION. UPPER FOOT IS WEATHERED WITH HAIRLINE CRACKS AND MODERATE REACTION PRODUCT — | | | | | | |

DIAMOND Bit No

81PC120
81PC169

LEGEND

Δ - CONCRETE
 □ - HAIRLINE CRACK
 NB. - NATURAL BREAK
 MB. - MACHINE BREAK

LOCATION

PIER No. 16
 1.5'
 COLUMN 4
 COLUMN 3
 VIEW LOOKING WEST

ENG FORM 1836 MAR 71 PREVIOUS EDITIONS ARE OBSOLETE. PROJECT HOLE NO.

| DRILLING LOG | | DIVISION | | INSTALLATION | | SHEET | |
|---|-------|---------------|---|---|-------------------|--|----------|
| 1. PROJECT | | ST. LOUIS, MO | | LOCE + Dam #24 | | 2 OF 2 SHEETS | |
| 2. LOCATION (Coordinates or Station) | | | | 11. DAY OF ELEVATION KNOWN (YES or NO) | | | |
| 3. DRILLING AGENCY | | | | 12. MANUFACTURER'S DESIGNATION OF DRILL | | | |
| 4. HOLE NO. (As shown on drawing title and site number) | | | | 13. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN | | DISTURBED UNDISTURBED | |
| 5. NAME OF DRILLER | | | | 14. TOTAL NUMBER CORE BOXES | | | |
| 6. DIRECTION OF HOLE <input type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED DEG. FROM VERT. | | | | 15. ELEVATION GROUND WATER | | | |
| 7. THICKNESS OF OVERBURDEN | | | | 16. DATE HOLE | | STARTED COMPLETED | |
| 8. DEPTH DRILLED INTO ROCK | | | | 17. ELEVATION TOP OF HOLE | | | |
| 9. TOTAL DEPTH OF HOLE | | | | 18. TOTAL CORE RECOVERY FOR BORING | | 1 | |
| | | | | 19. SIGNATURE OF INSPECTOR | | | |
| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | SCORE RECOVERY | BOX OR SAMPLE NO. | REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) | |
| 4490 | 100 | Δ | RUN #5 RRD-100% | | | Run #5 | Run 1.65 |
| | | Δ | | | | Run 4.00 | Reo 1.65 |
| | | Δ | | | | End 5.20 | Loss |
| | | Δ | | | | Time 6.00 | Gain |
| 4430 | 110 | Δ | | | | Drill time 8.00 | |
| | | Δ | | | | Hyd press 300 | |
| | | Δ | | | | Water press | |
| | | Δ | | | | SP 75 | |
| | | Δ | | | | Drill Action Smooth | |
| | | Δ | | | | Water ret | |
| | | Δ | | | | Remarks | |
| 4420 | 120 | Δ | NB 1/4" - NEARLY - BLACK DISCOLORATION ON THE SURFACE OF BREAK - OILY APPEARANCE AND SMELL | 100% | Box 3 | | |
| | | Δ | | | | Run #6 | Run 1.65 |
| | | Δ | | | | Run 7.30 | Reo 3.1 |
| | | Δ | | | | End 11.45 | Loss |
| | | Δ | | | | Time 2.00 | Gain |
| | | Δ | | | | Drill time 2.00 | |
| | | Δ | | | | Hyd press 300 | |
| | | Δ | | | | Water press | |
| | | Δ | | | | SP 75 | |
| | | Δ | | | | Drill Action Smooth | |
| | | Δ | | | | Water ret | |
| | | Δ | | | | Remarks | |
| 4410 | 130 | Δ | RUN #6 RRD-100% | | | Run #7 | Run 0.2 |
| | | Δ | | | | Run 12.50 | Reo 0.2 |
| | | Δ | | | | End 2:08 | Loss |
| | | Δ | | | | Time 7.00 | Gain |
| | | Δ | | | | Drill time 7.00 | |
| | | Δ | | | | Hyd press 300 | |
| | | Δ | | | | Water press | |
| | | Δ | | | | SP 75 | |
| | | Δ | | | | Drill Action Smooth | |
| | | Δ | | | | Water ret | |
| | | Δ | | | | Remarks | |
| 4400 | 140 | Δ | CONCRETE - Brownish Grey in color, NATURAL AGGREGATE - SIZE SAND TO COARSE GRAVEL (2") WITH THE MAJORITY OF THE AGGREGATE RUNNING FROM 1/4" TO 3/4". SHAPE, ANGULAR TO ROUNDED WITH MAJORITY BEING ROUNDED IN SHAPE. ORIGIN - GLACIAL OR RIVER, TYPE, IGN. SED. + META. WITH HIGH PER CENTAGE OF CHESTS, GRANITES. CONDITIONS - V. LITTLE TO NO REACTION PRODUCT AND OCCURRING AT SHALLOW DEPTHS. GENERAL CONDITION APPEARS GOOD - NATURAL FRACTURING OF CONCRETE AT 115' AND 6.4'. CONCRETE DISCOLORED AT 115'. MATERIAL HAS AN OIL RESIDUE ON SURFACE OF BREAK. | | | | |
| LEGEND | | | | | | | |
| Δ - CONCRETE | | | | | | | |
| MB - MACHINE BREAK | | | | | | | |
| NB - NATURAL BREAK | | | | | | | |

| DRILLING LOG | | DIVISION | | INSTALLATION | | SHEET | |
|--|-------|---|---|---|-------------------|---|--|
| PROJECT | | ST. LOUIS, MO. | | LOCK & DAM #34 | | OF 2 SHEETS | |
| 1. PROJECT Locks Dam #24 | | 2. LOCATION (Coordinate or Station) Pier No. 4 - 4:30' from U/S side of upper pier surface | | 3. SIZE AND TYPE OF BIT 6" 744 - 5" 1-2" 744 | | 4. DATE FOR ELEVATION SHOWN (Year - Month - Day) 11/5/80 | |
| 5. DRILLING AGENCY CEWES | | 6. NAME OF DRILLER A. McNAHARA | | 7. MANUFACTURER'S DESIGNATION OF DRILL Hiker | | 8. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN DISTURBED: UNDISTURBED: | |
| 9. HOLE NO. (As shown on drawing sheet) and site number SWES-PO4-1-B0 | | 10. NAME OF DRILLER A. McNAHARA | | 11. TOTAL NUMBER CORE BORES Three | | 12. ELEVATION GROUND WATER | |
| 13. DIRECTION OF HOLE Vertical | | 14. DATE HOLE 30 October 80 | | 15. ELEVATION TOP OF HOLE 454.0' | | 16. TOTAL CORE RECOVERY FOR BORING 94.3% | |
| 17. THICKNESS OF OVERBURDEN | | 18. SIGNATURE OF INSPECTOR Joseph B. Dumbare | | 19. SIGNATURE OF INSPECTOR | | 20. SIGNATURE OF INSPECTOR | |
| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | % CORE RECOVERY | BOX OR SAMPLE NO. | REMARKS (Drilling time, water loss, depth of penetration, etc., if significant) | |
| 454.0 | 0.0 | Δ | | | | Run #1 30ft-310ft | |
| | | Δ | | | | WL - 195' | |
| | | Δ | | | | Began 2:00 - 5:10 PM 195' | |
| | | Δ | | | | End 7:30 to 9:00 PM 195' | |
| | | Δ | | | | Time 12:00 PM Gain - | |
| | | Δ | | | | Drl time 270 min | |
| | | Δ | | | | Hyd press 200 PSI | |
| | | Δ | | | | Water press - | |
| | | Δ | | | | RFM 702 | |
| | | Δ | | | | Drl Action Smooth | |
| | | Δ | | | | Water ret | |
| | | Δ | | | | Brown | |
| | | Δ | | | | Remarks | |
| | | Δ | | | | Straining Bbl - changed | |
| | | Δ | | | | B. 15 | |
| | | Δ | | | | Run #2 | |
| | | Δ | | | | WL - Run 195' | |
| | | Δ | | | | Began 9:10 Rec 195' | |
| | | Δ | | | | End 10:40 Loss - | |
| | | Δ | | | | Time 30 min Gain - | |
| | | Δ | | | | Drl time 30 min | |
| | | Δ | | | | Hyd press 250 | |
| | | Δ | | | | Water press - | |
| | | Δ | | | | RFM 702 | |
| | | Δ | | | | Drl Action Smooth | |
| | | Δ | | | | Water ret | |
| | | Δ | | | | Brown | |
| | | Δ | | | | Remarks | |
| | | Δ | | | | Run #3 | |
| | | Δ | | | | WL Run 1/2 | |
| | | Δ | | | | Began 10:50 Rec 0.0 | |
| | | Δ | | | | End 1:00 PM Loss 1/2 | |
| | | Δ | | | | Time 35 min Gain - | |
| | | Δ | | | | Drl time 35 min | |
| | | Δ | | | | Hyd press 200 PSI | |
| | | Δ | | | | Water press - | |
| | | Δ | | | | RFM 702 | |
| | | Δ | | | | Drl Action Smooth | |
| | | Δ | | | | Water ret | |
| | | Δ | | | | Brown | |
| | | Δ | | | | Remarks | |
| | | Δ | | | | Run #4 | |
| | | Δ | | | | WL Run 36' | |
| | | Δ | | | | Began 11:55 Rec 48 | |
| | | Δ | | | | End 3:45 Loss - | |
| | | Δ | | | | Time 25 min Gain 1/2' | |
| | | Δ | | | | Drl time 25 min | |
| | | Δ | | | | Hyd press 300 PSI | |
| | | Δ | | | | Water press - | |
| | | Δ | | | | RFM 702 | |
| | | Δ | | | | Drl Action Smooth | |
| | | Δ | | | | Water ret | |
| | | Δ | | | | Brown | |
| | | Δ | | | | Remarks | |

Hole No. SWES-P02-1-80

| | | | | | | | |
|--|--|----------------------------------|--|---|--|---|--|
| DRILLING LOG | | DIVISION St Louis, Mo. | | INSTALLATION Lock & Dam #24 | | SHEET 1 OF 2 SHEETS | |
| 1. PROJECT Lock & Dam #24 | | | | 10. SIZE AND TYPE OF BIT See Page Two | | | |
| 2. LOCATION (Contingency or Station) See Page Two | | | | 11. DEPTH FOR ELEVATION SHOWN (TBM or BBL) M.S.L. | | | |
| 3. DRILLING AGENCY CFWES | | | | 12. MANUFACTURER'S DESIGNATION OF DRILL HECK | | | |
| 4. HOLE NO. (As shown on drawing title and file number) SWES-P02-1-80 | | | | 13. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN | | DISTURBED <input type="checkbox"/> UNDISTURBED <input type="checkbox"/> | |
| 5. NAME OF DRILLER A. McNAMARA | | | | 14. TOTAL NUMBER CORE BOXES Four | | 15. ELEVATION GROUND WATER | |
| 6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED _____ DEG. FROM VERT. | | | | 16. DATE HOLE 28 October 80 | | COMPLETED 30 October 80 | |
| 7. THICKNESS OF OVERBURDEN 14.2' | | | | 17. ELEVATION TOP OF HOLE 454.0 | | 18. TOTAL CORE RECOVERY FOR BORING 97.2% | |
| 8. DEPTH DRILLED INTO ROCK | | | | 19. SIGNATURE OF INSPECTOR Samuel B. Eubank | | | |
| 9. TOTAL DEPTH OF HOLE | | | | | | | |

| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | % CORE RECOVERY | BOX OR SAMPLE NO. | REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) |
|-----------|-------|--------|--|-----------------|-------------------|--|
| 454.0 | 0.0 | Δ | | 100% | Box 1 | Run #1 28 Oct. 80 WL — Run 0.9' Began 1.30 Rec 0.9' End 3.48 Loss — Time 138 min Gain — Drl time 138 min Hyd press 750 to 700 PSI Water press — RPM 742 Drl Action Smooth Water ret Began Remarks - CHANGED BITS - STARTING BBL |
| 453.0 | 1.0 | Δ | CONCRETE ✓ | 88.1% | Box 1 | Run #2 29 October 80 WL — Run 2.1' Began 4.06-5.20 Rec 1.85' End 8.00-9.10 Loss 0.25' Time 144 min Gain — Drl time 144 min Hyd press 3002 Water press — RPM 702 Drl Action Smooth Water ret Began STARTING Bbl. Remarks |
| 452.0 | 2.0 | Δ | CONCRETE ✓ | 162% | Box 2 | Run #3 1.65' WL — Run 3.05' Began 9.30 Rec — End 11.00 Loss 1.65' Time 90 min Gain — Drl time 90 min Hyd press 3002 Water press — RPM 752 Drl Action Smooth Water ret Began Remarks Continued with STARTING Bbl to Make Bore For 5' Bbl - from DECK |
| 449.0 | 5.0 | Δ | CONCRETE ✓ | 100% | Box 3 | Run #4 WL — Run 3.45' Began 11.15 Rec 4.95' End 2.50 min Loss — Time 215 min Gain 1.90' Drl time 215 min Hyd press 300-500 Water press — RPM 752 Drl Action Smooth Water ret Began Remarks |
| 448.0 | 6.0 | Δ | CONCRETE ✓ | | | |
| 447.0 | 7.0 | Δ | CONCRETE ✓ | | | |
| 446.0 | 8.0 | Δ | CONCRETE ✓ | | | |
| 445.0 | 9.0 | Δ | CONCRETE ✓ | | | |
| 444.0 | 10.0 | Δ | CONCRETE ✓ | | | |

ENG FORM 1836 MAR 71 PREVIOUS EDITIONS ARE OBSOLETE.
(TRANSLOGENT)

PROJECT

HOLE NO.

Male No. SWES-P04 2-60

| DRILLING LOG | | Division | INSTALLATION | SHEET | | |
|---|-------|----------------------|---|-------------------------|----------------------|---|
| 1. PROJECT <i>Lock and Dam No. 24</i> | | <i>St. Louis Mo.</i> | <i>Locks Dam No. 24</i> | 1 OF 1 SHEETS | | |
| 2. LOCATION (Coordinates or Station) <i>See below</i> | | | 10. SIZE AND TYPE OF BIT <i>M.S.G.</i> | | | |
| 3. DRILLING AGENCY <i>BEWES</i> | | | 11. DAY USE FOR ELEVATION MEASUREMENT <i>Below</i> | | | |
| 4. HOLE NO. (As shown on drawing, hole, and file number) <i>SWES-P04 2-60</i> | | | 12. MANUFACTURER'S DESIGNATION OF DRILL <i>Elsevier - Core Drill</i> | | | |
| 5. NAME OF DRILLER <i>A. McNamara</i> | | | 13. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN <i>Disturbed</i> | | | |
| 6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED <i>9.0</i> DEG. FROM VERT. | | | 14. TOTAL NUMBER CORE BOXES <i>THD</i> | | | |
| 7. THICKNESS OF OVERBURDEN <i>1.64</i> | | | 15. ELEVATION GROUND WATER | | | |
| 8. DEPTH DRILLED INTO ROCK <i>1.64</i> | | | 16. DATE HOLE <i>28 Nov 60</i> | | | |
| 9. TOTAL DEPTH OF HOLE <i>1.64</i> | | | 17. ELEVATION TOP OF HOLE <i>448.0</i> | | | |
| | | | 18. TOTAL CORE RECOVERY FOR TESTING <i>100%</i> | | | |
| | | | 19. MEASURE OF PRODUCTION <i>Sample B</i> | | | |
| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | 1. CORE RECOVERY, % | 2. BOX OR SAMPLE NO. | REMARKS (Drilling time, water flow, depth of penetration, etc., if significant) |
| 4480 | 0 | | | | | Run No. 1 28 Nov 60 |
| | | | Concrch. | 100% | Box 1 | WL — Run 1.35 Began 1.30 Rec 1.35 End 1.30 Loss — Time 6 min Gain — Drl time 6 min Hyd press — Water press MID RPM 3005 Drl Action Spout Water ret Brown Remarks |
| 4480 | 10 | | | | | Run No. 2 |
| | | | Concrch. | 100% | Box 1 | WL — Run 2.2 Began 1.35 Rec 2.2 End 3.15 Loss — Time 10 min Gain — Drl time 10 min Hyd press — Water press MID RPM 3005 Drl Action Spout Water ret Brown Remarks |
| 4480 | 20 | | | | | Run No. 3 |
| | | | Concrch. Fair condition — UPPER PORTION IS VERY POOR. Numerous breaks & cracks, always with moderate amounts of reaction product. | 100% | Box 2 | WL — Run 2.85 Began 3.30 Rec 2.85 End 5.40 Loss — Time 13 min Gain — Drl time 13 min Hyd press — Water press MID RPM 3005 Drl Action Spout Water ret Brown Remarks |
| 4480 | 30 | | | | | Run No. 3 RQD = 85.9% |
| 4480 | 40 | | | | | |
| 4480 | 50 | | | | | |
| 4480 | 60 | | | | | |
| | | DIAMOND BITS | | LEGEND | | |
| | | 79PN0437 | | [A] - Concrch | | |
| | | 79PB687 | | [B] - Natural cracks | | |
| | | | | MB - Machine break | | |
| | | | | NB - Natural break | | |
| | | | | LOCATION | | |
| | | | | | | |
| | | | | View Looking up/s | | |
| | | | | 2. Center of pier NO. 4 | | |

ENG FORM 1836 PREVIOUS EDITIONS ARE OBSOLETE
MAR 71 (TRANSLUCENT)

Note No. 5445-209-2-80

| | | | | | | | |
|---|--|--------------------------------|--|---|--|--------------------------------------|--|
| DRILLING LOG | | DIVISION St. Louis, Mo. | | INSTALLATION Lock & Dam No. 24 | | SHEET 1 OF 3 SHEETS | |
| 1. PROJECT Lock & Dam No. 24 | | | | 10. SIZE AND TYPE OF BIT 6.75" - See Page 129 | | | |
| 2. LOCATION (Continent or Station) See Page 129 | | | | 11. DAY OF YEAR FOR ELEVATION DETERMINED MSL | | | |
| 3. DRILLING AGENCY C.E.W.E.S. | | | | 12. MANUFACTURER'S DESIGNATION OF DRILL KEER | | | |
| 4. HOLE NO. (As shown on drawing 100) and the number SWS-P083-R0 | | | | 13. TOTAL NO. OF OVER-BOURDEN SAMPLES TAKEN UNOBTAINED | | | |
| 5. NAME OF DRILLER McNairner | | | | 14. TOTAL NUMBER CORE BOXES THREE | | | |
| 6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED SEE FROM VERT. | | | | 15. ELEVATION GROUND WATER | | | |
| 7. THICKNESS OF CONCRETE 13.1 FT | | | | 16. DATE HOLE STARTED 24 November 1970 COMPLETED | | | |
| 8. DEPTH DRILLED INTO ROCK (Recovered) 12.9 FT | | | | 17. ELEVATION TOP OF HOLE 444.0 FT | | | |
| 9. TOTAL DEPTH OF HOLE 13.1 FT | | | | 18. TOTAL CORE RECOVERY FOR BORING 100% | | | |
| 19. SIGNATURE OF INSPECTOR James B. Vink | | | | | | | |

| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | RECOVERED | BOX OR SAMPLE NO. | REMARKS (Drilling time, water used, loss of circulation, etc., if significant) |
|-----------|-------|--------|---|-----------|-------------------|---|
| 444.0 | 0.0 | Δ | CONCRETE | 100% | Box 1 | Run No. 1 24 Nov. 80 HL — Run 2.50 Began 11:45 Rec 2.50 End 2.30 Loss — Time 245 min Gain — Drl time 245 min Hyd press 750 PSI Water press 1450 RPM 750 Drl Action Smooth Water ret Brown Remarks |
| 443.0 | 1.0 | Δ | | | | |
| 442.0 | 2.0 | Δ | | | | |
| 441.0 | 3.0 | Δ | CONCRETE | 100% | Box 1 | Run No. 2 25 Nov. 80 HL — Run 1.5' Began 7.45 Rec 1.5' End 11.15 Loss — Time 210 min Gain — Drl time 210 min Hyd press 1450 Water press 700 to 100 RPM 750 Drl Action Smooth Water ret Brown Remarks |
| 440.0 | 4.0 | Δ | CONCRETE | 100% | Box 2 | Run No. 3 HL — Run 0.6 Began 11:45 Rec 0.6 End 1.75 Loss 0.6 Time 100 min Gain — Drl time 100 min Hyd press 200 PSI Water press 1450 RPM 700 Drl Action Smooth Water ret Brown Remarks |
| 439.0 | 5.0 | Δ | CONCRETE | 100% | Box 2 | Run No. 4 HL — Run 2.8 Began 1.30 Rec 2.8 End 4.45 Loss — Time 145 min Gain 0.8 Drl time 145 min Hyd press 600 PSI Water press 1450 RPM 750 Drl Action Smooth Water ret Brown Remarks |
| 438.0 | 6.0 | Δ | CONCRETE | 100% | Box 2 | |
| 437.0 | 7.0 | Δ | CONCRETE | 100% | Box 3 | |
| 436.0 | 8.0 | Δ | CONCRETE | 100% | Box 3 | |
| 435.0 | 9.0 | Δ | CONCRETE | 100% | Box 3 | |
| 434.0 | 10.0 | Δ | CONCRETE | 100% | Box 3 | |

ENG FORM 1836 MAR 71 PREVIOUS EDITIONS ARE OBSOLETE. PROJECT HOLE NO.

| DRILLING LOG | | DIVISION | | INSTALLATION | | SHEET 2 | |
|--|-------|---|--|--|-------------------------|--|--|
| 1. PROJECT | | 2. LOCATION (Coordinates or Station) | | 3. DRILLING AGENCY | | 4. HOLE NO. (As shown on drawing No. and the number) | |
| 5. NAME OF DRILLER | | 6. DIRECTION OF HOLE <input type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED _____ DEG. FROM VERT. | | 7. THICKNESS OF OVERBURDEN | | 8. DEPTH DRILLED INTO ROCK | |
| 9. TOTAL DEPTH OF HOLE | | 10. SIZE AND TYPE OF BIT | | 11. DAYUM FOR ELEVATION KNOWN (FT. or M.) | | 12. MANUFACTURER'S DESIGNATION OF DRILL | |
| 13. TOTAL NO. OF OVER- BURDEN SAMPLES TAKEN | | 14. TOTAL NUMBER CORE BOXES | | 15. ELEVATION GROUND WATER | | 16. DATE HOLE | |
| 17. ELEVATION TOP OF HOLE | | 18. TOTAL CORE RECOVERY FOR BORING | | 19. SIGNATURE OF INSPECTOR | | 20. REMARKS (Drilling time, water loss, depth of overburden, etc., if significant) | |
| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | 5. CORE RECOVER- ERY | BOX OR SAMPLE NO. | REMARKS | |
| 444.0 | 10.0 | Δ | Run #5 RQD=100% | | Box 3 | Run #5 Began 3:15 hu. 2.7 End 5:20 Rec 2.7 Time 1:05 min Gain - Drl time 1:05 min Hyd press 500-700 Water press - RPM 50 to 75 Drl Action Smooth Water ret Brown Remarks - | |
| 443.0 | 11.0 | Δ | | | Box 4 | | |
| 442.0 | 12.0 | Δ | CONCRETE | 89.5% | | | |
| 441.0 | 13.0 | Δ | NA CONCRETE HAS ODD APPEARANCE - BREAKS HAS "INNER PLUG" - POSSIBLY TWO PILES - | | 13.3 | Run #6 30 October 60 KL - Run 3.6' Began 7:30 Rec 3.4' End 11:30 Loss 0.4 Time 2:40 min Gain - Drl time 2:40 min Hyd press 500-700 Water press - RPM 50-75 Drl Action Smooth Water ret Brown Remarks Left last 0.4' in hole | |
| 440.0 | 14.0 | Δ | Run #6 RQD=88.0% | | | | |
| <p>CONCRETE - BROWNISH GRAY IV COLOR, NATURAL AGGREGATE - 3/8" SAND TO COARSE GRAVEL (2") WITH MAJORITY OF AGGREGATE RUNNING FROM 1/2" TO 3/4" SHAPE - ANGULAR TO ROUND - 5-20% ANGLULAR WITH REST BEING ROUND - ORIGIN - GLACIAL OR RIVER - TYPE - IGNEOUS - SEDIMENTARY - METAMORPHIC, HIGH PERCENTAGE OF CRYSTALS AND GRANITES - CONDITION - V. LITTLE TO NO REACTION PRODUCT VISIBLE, GENERAL CONDITION APPEARS TO BE GOOD. ODD BREAK AT 13.4'</p> | | | | | | | |
| BITS | | LOCATION | | LEGEND | | | |
| 801B/52 801B/54 | | | | <p>Δ - CONCRETE NA - NATURAL BREAK MB - MAINLINE BREAK</p> | | | |

Note No. SAES 2095-50

| DRILLING LOG | | DIVISION | INSTALLATION | | SHEET 7 OF 8 SHEETS | |
|---|-------|---|---|--|---------------------|--|
| 1. PROJECT | | 10. SIZE AND TYPE OF BIT | | 11. DATE FOR ELEVATION SHOWN (YR - MO - DAY) | | |
| 2. LOCATION (Continent or Station) | | 12. MANUFACTURER'S DESIGNATION OF DRILL | | 13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN | | |
| 3. DRILLING AGENCY | | 14. TOTAL NUMBER CORE BOXES | | 15. ELEVATION GROUND WATER | | |
| 4. HOLE NO. (As shown on drawing title and file number) | | 16. DATE HOLE | | 17. ELEVATION TOP OF HOLE | | |
| 5. NAME OF DRILLER | | 18. TOTAL CORE RECOVERY FOR BORING | | 19. SIGNATURE OF INSPECTOR | | |
| 6. DIRECTION OF HOLE | | 19. SIGNATURE OF INSPECTOR | | | | |
| 7. THICKNESS OF OVERBURDEN | | | | | | |
| 8. DEPTH DRILLED INTO ROCK | | | | | | |
| 9. TOTAL DEPTH OF HOLE | | | | | | |
| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | 1. CORE RECOVERY | BOX OR SAMPLE NO. | REMARKS (Drilling time, water loss, depth of overburden, etc., if significant) |
| | | | CONCRETE: GRAYISH BROWN IN COLOR WITH NATURAL AGGREGATE. THE AGGREGATE RANGES IN SIZE FROM 1/8" TO 2" MAX WITH 80% RUNNING FROM 1/4" TO 1". THE SHAPE OF AGGREGATE IS ANGULAR TO ROUNDED WITH 90% BEING ROUNDED OR SEMI-ROUND. THE CONCRETE IS IN GOOD CONDITION, IN THAT IT LACKS HAIRLINE BREAKS, CRACKS, AND SIGNIFICANT 2 AMOUNTS OF REACTION PRODUCT. ALL BREAKS IN CORE ARE THE RESULT OF MACHINE ACTION (BREAKS AT 10.5' & 12' 2 ARE NATURAL BREAKS). DRILL TIMES FOR EACH RUN INDICATE A VERY "TOUGH," HARD CONCRETE. | | | |

Hole No. 545-89-3 E

| DRILLING LOG | | DIVISION | | INSTALLATION | | SHEET | |
|---|-------|----------|---|---|----------------------|---|--|
| 1. PROJECT | | | | 2. HOLE NO. <u>24</u> | | 3. SHEET <u>2</u> OF <u>3</u> SHEETS | |
| 4. LOCATION (Continent or Station) | | | | 10. SIZE AND TYPE OF BIT | | 11. DAY USE FOR ELEVATION KNOWN (Y/N) = <u>NO</u> | |
| 5. DRILLING AGENCY | | | | 12. MANUFACTURER'S DESIGNATION OF DRILL | | | |
| 6. HOLE NO. (As shown on drawing sheet) and its number | | | | 13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN | | 14. DISTURBED <input type="checkbox"/> UNDISTURBED <input type="checkbox"/> | |
| 7. NAME OF DRILLER | | | | 15. TOTAL NUMBER CORE BOXES | | | |
| 8. DIRECTION OF HOLE <input type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED _____ DEG. FROM VERT. | | | | 16. ELEVATION GROUND WATER | | | |
| 9. THICKNESS OF OVERBURDEN | | | | 17. DATE HOLE STARTED _____ COMPLETED _____ | | | |
| 10. DEPTH DRILLED INTO ROCK | | | | 18. ELEVATION TOP OF HOLE | | | |
| 11. TOTAL DEPTH OF HOLE | | | | 19. TOTAL CORE RECOVERY FOR BORING | | | |
| | | | | 20. SIGNATURE OF INSPECTOR | | | |
| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | 1. CORE RECOVERY | 2. BOX OR SAMPLE NO. | REMARKS (Drilling time, water loss, depth of overburden, etc., if significant) | |
| 4340 | 100 | Δ | Run No. 7 RQD = 100% | | | Run No. 5 26 Nov 60 WL — Run 0.55 Began 7:40 Rec 0.55 End 9:30 Loss — Time 11 min Gain — Drl time 11 min Hvd press 400 PSI Water press 100 PSI RPM 800 Drl Action Smooth Water ret Remarks | |
| 4330 | 110 | Δ | Concrete | 100% | Bx 3 | | |
| | | Δ | Run No. 8 RQD = 100% | | | | |
| 4320 | 120 | Δ | Run No. 9 RQD = 100% | | Bx 3 | | |
| 4310 | 130 | Δ | Run No. 9 | | 138 | Run No. 6 WL — Run 1.11 Began 9:35 Rec 1.11 End 11:00 Loss — Time 15 min Gain — Drl time 15 min Hvd press 400 PSI Water press 100 PSI RPM 800 Drl Action Smooth Water ret Remarks | |
| | | Δ | Run No. 10 | | | Run No. 7 WL — Run 1.45 Began 12:45 Rec 1.45 End 1:25 Loss — Time 20 min Gain — Drl time 20 min Hvd press 400 PSI Water press 100 PSI RPM 800 Drl Action Smooth Water ret Remarks | |
| | | Δ | Run No. 8 | | | Run No. 8 27 Nov 60 WL — Run 1.2 Began 8:30 Rec 1.2 End 11:30 Loss — Time 18 min Gain — Drl time 18 min Hvd press 400 PSI Water press 100 PSI RPM 800 Drl Action Smooth Water ret Remarks | |

LEGEND

Δ CONCRETE

M.B. MACHINE BREAK

N.B. NATURAL BREAK

LOCATION

DIAMOND BITS

- 80 PC 1162

- RS 80 PC 1162

- 801 B 153

PLAN VIEW

SWCS-093-80

ENG FORM 1836 PREVIOUS EDITIONS ARE OBSOLETE
MAR 71

PROJECT

HOLE NO.

Hole No. SWES-P151-80

| DRILLING LOG | | Division | INSTALLATION | SHEET | | |
|--|-------|--|---|-----------------------------|-------------------|--|
| 1. PROJECT <u>Lock 1 Dam #24</u> | | <u>St. Louis, Mo</u> | <u>Lock 1 Dam #24</u> | <u>1</u> of <u>5</u> SHEETS | | |
| 2. LOCATION (Coordinate or Station) <u>Lock 1 Dam #24</u> | | 10. SIZE AND TYPE OF BIT <u>6.75" - SEE PAGE</u> | | | | |
| 3. DRILLING ASPECT <u>CE 104</u> | | 11. DATE FOR ELEVATION DETERMINATION <u>1956</u> | | | | |
| 4. HOLE NO. (As shown on drawing title) <u>SWES-P151-80</u> | | 12. MANUFACTURER'S DESIGNATION OF DRILL | | | | |
| 5. NAME OF DRILLER <u>A. McNamee</u> | | 13. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN | | | | |
| 6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED _____ DEG FROM VERT | | 14. TOTAL NUMBER CORE BOXES <u>11</u> | | | | |
| 7. THICKNESS OF OVERBURDEN <u>0</u> | | 15. ELEVATION GROUND WATER | | | | |
| 8. DEPTH DRILLED INTO ROCK <u>41.1</u> | | 16. DATE HOLE STARTED <u>21 October 1980</u> COMPLETED <u>27 October 1980</u> | | | | |
| 9. TOTAL DEPTH OF HOLE <u>41.1 Concrete</u> | | 17. ELEVATION TOP OF HOLE <u>454.0'</u> | | | | |
| | | 18. TOTAL CORE RECOVERY FOR BORING | | | | |
| | | 19. SIGNATURE OF INSPECTOR <u>See Number 4, ELS</u> | | | | |
| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | % CORE RECOVERY | BOX OR SAMPLE NO. | REMARKS (Drilling time, water loss, depth of penetration, etc., if significant) |
| 454.0 | 00 | Δ | | | | Began 8:00 Run 1.75' |
| | | Δ | 1/4" Rock | | Box 1 | End 10:15 Loss - |
| | | Δ | CONCRETE | 100% | | Time 135min Gain - |
| 453.0 | 10 | Δ | | | | Drl time 135min |
| | | Δ | Run #1 RQD-100% | | | Hyd press 200-400 PSI |
| | | Δ | | | | Water press - |
| | | Δ | | | | RPM 75-150 |
| | | Δ | | | | Drl Action Smooth |
| | | Δ | | | | Water ret |
| | | Δ | | | | Brown |
| | | Δ | | | | Remarks |
| | | Δ | | | | Run #2 |
| 452.0 | 20 | Δ | | | Box 1 | WL Run 1.75' |
| | | Δ | CONCRETE | 100% | | Began 10:30 Rec 1.75' |
| | | Δ | | | | End 11:30 Loss - |
| | | Δ | | | | Time 60min Gain - |
| | | Δ | | | | Drl time 60min |
| | | Δ | | | | Hyd press 400 |
| | | Δ | | | | Water press - |
| | | Δ | | | | RPM 50 |
| | | Δ | | | | Drl Action Smooth |
| | | Δ | | | | Water ret |
| | | Δ | | | | Brown |
| | | Δ | | | | Remarks |
| | | Δ | | | | 11 CHANGED BITS |
| | | Δ | | | | Run #3 |
| 450.0 | 40 | Δ | CONCRETE - GRAY BROWN IN COLOR, NATURAL RUB-GLASS AGG. SAG. TEN. MATH - ANGULAR | | Box 1 | WL Run 4.65' |
| | | Δ | NO TO BOUNDED WITH HARDITY | 4.75 | | Began 1:30 Rec 4.65' |
| | | Δ | BEING ROUNDED AND SIZE DISTRIBUTION IS FROM SAND AND FINE GRAVEL, TO A VERY COARSE GRAVEL, 100% | | | End 4:40 Loss - |
| | | Δ | SLIGHT REACTION PRODUCT ALONG WITH EVIDENT RING | | | Time 170min Gain - |
| | | Δ | IN GRAVEL ARE VISIBLE, AS WELL AS A PURGUS | | | Drl time 150min |
| | | Δ | NO HARDENING CORE | | | Hyd press 200-300 |
| | | Δ | | | | Water press - |
| | | Δ | | | | RPM 70-150 |
| | | Δ | | | | Drl Action Smooth |
| | | Δ | | | | Water ret |
| | | Δ | | | | Brown |
| | | Δ | | | | Remarks |
| | | Δ | | | | Run #4 |
| | | Δ | | | | 22 October 80 |
| | | Δ | | | | WL Run 7.75' |
| | | Δ | | | | Began 5:00-5:10 Rec 7.5' |
| | | Δ | | | | End 7:30-7:40 Loss 0.25 |
| | | Δ | | | | Time 140min Gain - |
| | | Δ | | | | Drl time 140min |
| | | Δ | | | | Hyd press 200-300 |
| | | Δ | | | | Water press - |
| | | Δ | | | | RPM 150 |
| | | Δ | | | | Drl Action Smooth |
| | | Δ | | | | Water ret |
| | | Δ | | | | Brown |
| | | Δ | | | | Remarks |
| | | Δ | | | | Run #5 |
| | | Δ | | | | 11 0.25 in hole |
| 444.0 | 10.0 | Δ | Run #4 RQD-83% | | Box 3 | |

ENG FORM 1836 MAR 71 PREVIOUS EDITIONS ARE OBSOLETE (TRANSLUCENT)

Hole No. 9W65-P151-80

| DRILLING LOG | | DIVISION | | INSTALLATION | | SHEET 3 OF 5 SHEETS | |
|----------------------------|-------|--|---|---|----------------------|---|--|
| 1. PROJECT | | 2. LOCATION (Coordinates or Address) | | 10. SIZE AND TYPE OF BIT | | 11. DAY OF YEAR ELEVATION SHOWN (TBM = 1000) | |
| 3. DRILLING AGENCY | | 4. HOLE NO. (As shown on drawing title and site number) | | 12. MANUFACTURER'S DESIGNATION OF DRILL | | 13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN | |
| 5. NAME OF DRILLER | | 6. DIRECTION OF HOLE <input type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED _____ DEG. FROM VERT | | 14. TOTAL NUMBER CORE BORES | | 15. ELEVATION GROUND WATER | |
| 7. THICKNESS OF OVERBURDEN | | 8. DEPTH DRILLED INTO ROCK | | 16. DATE HOLE STARTED _____ COMPLETED _____ | | 17. ELEVATION TOP OF HOLE | |
| 9. TOTAL DEPTH OF HOLE | | 18. TOTAL CORE RECOVERY FOR BORING | | 19. SIGNATURE OF INSPECTOR | | | |
| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | 1. CORE RECOVERY % | 2. BOX OR SAMPLE NO. | REMARKS (Drilling time, water loss, depth of overburden, etc., if significant) | |
| 434.0 | 20.0 | Δ | Run # 8 | | 20.15 | 23 Oct - 24 Oct 1980 | |
| 433.0 | 21.0 | Δ | CONCRETE | 100% | | Run # 9 WL - Run 4.25 Began 2:15-5:00 Rec 4.25 End 7:50-Rec Loss - Time 355 min Gain - Drl time 340 min Hyd press 150 Water press - Rtd 702 Drl Action Smooth Water ret Blew N Remarks | |
| 432.0 | 22.0 | Δ | | | Box 6 | Run # 10 WL - Run 4.75 Began 1:10 Rec 2.75 End 3:30 Loss - Time 140 min Gain - Drl time 140 min Hyd press 150 Water press - Rtd 502 Drl Action Smooth Water ret Blew N Remarks | |
| 431.6 | 22.4 | Δ | Run # 9 RQD=100% | | 24.4 | Run # 11 25 Oct 80 WL - Run 5.6 Began 3:57-5:05 Rec 5.6 End 7:42-11:00 Loss - Time 278 min Gain - Drl time 278 min Hyd press 200 Water press - Rtd 702 Drl Action Smooth Water ret Blew N Remarks | |
| 430.0 | 24.0 | Δ | | | Box 7 | Run # 12 WL 11:45 Run 4.1 Began 3:20- Rec 4.1 End 3:20- Loss - Time 215 min Gain - Drl time 215 min Hyd press 200 Water press - Rtd 702 Action Smooth Water ret Blew N Remarks | |
| 429.0 | 25.0 | Δ | CONCRETE | 100% | | | |
| 428.0 | 26.0 | Δ | | | Box 8 | | |
| 427.0 | 27.0 | Δ | Run # 10 RQD=100% | | 27.15 | | |
| 426.0 | 28.0 | Δ | CONCRETE | 100% | | | |
| 425.0 | 29.0 | Δ | | | | | |
| 424.0 | 30.0 | Δ | | | | | |

ENG FORM 1836 MAR 71 PREVIOUS EDITIONS ARE OBSOLETE. PROJECT HOLE NO.

(TRANSLUCENT)

| DRILLING LOG | | DIVISION | | INSTALLATION | | SHEET 2 OF 5 SHEETS | |
|---|-------|----------|---|---|-------------------|--|--|
| 1. PROJECT | | | | 2. SIZE AND TYPE OF BIT | | | |
| 3. LOCATION (Coordinates or Township) | | | | 11. MANUFACTURER'S DESIGNATION OF DRILL | | | |
| 4. DRILLING AGENCY | | | | 12. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN | | | |
| 5. HOLE NO. (As shown on drilling site and log number) | | | | 13. TOTAL NUMBER CORE BOXES | | | |
| 6. NAME OF DRILLER | | | | 14. ELEVATION GROUND WATER | | | |
| 7. DIRECTION OF HOLE <input type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED _____ DEG. FROM VERT. | | | | 15. DATE HOLE STARTED COMPLETED | | | |
| 8. THICKNESS OF OVERBURDEN | | | | 16. ELEVATION TOP OF HOLE | | | |
| 9. DEPTH DRILLED INTO ROCK | | | | 17. TOTAL CORE RECOVERY FOR BORING | | | |
| 10. TOTAL DEPTH OF HOLE | | | | 18. SIGNATURE OF INSPECTOR | | | |
| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | % CORE RECOVERY | BOX OR SAMPLE NO. | REMARKS (Drilling time, water loss, depth of penetration, etc., if significant) | |
| 444.0 | 10.0 | Δ | CONCRETE | | Box 3 | Run #5 WL - Run 1.30 Began 10:30 Rec 1.55 End 1:39 Loss - Time 109 min Gain 25 Drl time 18 min Hyd press 250-300 Water press - RPM 150 Drl Action Smooth Water ret Brown Remarks | |
| 443.0 | 11.0 | Δ | Run #5 R&D 100% | | Box 3 | | |
| 442.0 | 12.0 | Δ | CONCRETE | 100% | Box 3 | Run #6 WL - Run 3.3 Began 2:30 Rec 3.3 End 5:30 Loss - Time 180 min Gain - Drl time 170 min Hyd press 200-400 Water press - RPM 70 Drl Action Smooth Water ret Brown Remarks | |
| 441.0 | 13.0 | Δ | CONCRETE | 100% | Box 3 | | |
| 440.0 | 14.0 | Δ | Run #6 R&D 100% | | Box 3 | | |
| 439.0 | 15.0 | Δ | CONCRETE | 100% | Box 3 | | |
| 438.0 | 16.0 | Δ | Run #7 R&D 80% | | Box 4 | Run #7 23 September 80 WL - Run Began 8:30 Rec End 11:30 Loss Time 180 min Gain Drl time 15 min Hyd press 200 Water press - RPM 70 Drl Action Smooth Water ret Brown - changed bits Remarks | |
| 437.0 | 17.0 | Δ | CONCRETE | 100% | Box 4 | | |
| 436.0 | 18.0 | Δ | CONCRETE | 100% | Box 4 | | |
| 435.0 | 19.0 | Δ | CONCRETE | 100% | Box 5 | Run #8 WL - Run 4.5 Began 12:35 Rec 4.5 End 2:30 Loss Time 135 min Gain - Drl time 135 min Hyd press 250 Water press - RPM 70 Drl Action Smooth Water ret Brown | |
| 434.0 | 20.0 | Δ | R&D 100% | | Box 5 | | |

ENG FORM 18-36
MAR 71PREVIOUS EDITIONS ARE OBSOLETE
(TRANSLUCENT)

PROJECT

DATE

HOLE NO.


Hole No. SWES-PIS-2-80

| | | | | |
|--|--|---|--|---|
| DRILLING LOG | | DIVISION <u>St Louis Mo</u> | INSTALLATION <u>Lock + Dam No 24</u> | SHEET <u>1</u> of <u>1</u> SHEETS |
| 1. PROJECT <u>Lock + Dam No. 24</u> | | 10. SIZE AND TYPE OF BIT <u>6 1/2" - 5/8" - 1/2"</u> | | |
| 2. LOCATION (Continent or Section) <u>SEE BELOW</u> | | 11. DATE FOR ELEVATION SHOWN (Time or Date) <u>MSL</u> | | |
| 3. DRILLING AGENCY <u>C.F. N.E.S.</u> | | 12. MANUFACTURER'S DESIGNATION OF DRILL <u>SPEAKE AND HENWOOD</u> | | |
| 4. HOLE NO. (As shown on drawing title) and file number <u>SWES-PIS-2-80</u> | | 13. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN DISTURBED _____ UNDISTURBED _____ | | |
| 5. NAME OF DRILLER <u>A. McNamara</u> | | 14. TOTAL NUMBER CORE BOXES <u>TWO</u> | | |
| 6. DIRECTION OF HOLE <input type="checkbox"/> VERTICAL <input checked="" type="checkbox"/> INCLINED <u>90°</u> DEG. FROM VERT. | | 15. ELEVATION GROUND WATER STARTED _____ COMPLETED _____ | | |
| 7. THICKNESS OF OVERBURDEN <u>6.55'</u> | | 16. DATE HOLE STARTED <u>7 Nov. 80</u> COMPLETED _____ | | |
| 8. DEPTH DRILLED INTO ROCK <u>6.55'</u> | | 17. ELEVATION TOP OF HOLE <u>448.1'</u> | | |
| 9. TOTAL DEPTH OF HOLE <u>6.55'</u> | | 18. TOTAL CORE RECOVERY FOR BORING <u>100%</u> | | |
| | | 19. SIGNATURE OF INSPECTOR <u>James B. Dunt</u> | | |

| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | % CORE RECOVERY | BOX OR SAMPLE NO. | REMARKS (Drilling time, water loss, depth of penetration, etc., if significant) |
|-----------|-------|--------|--|-----------------|-------------------|---|
| 448.1 | 0.0 | | WEATHERED | | | Run No 1 - 7 Nov 80 NL _____ Run 1.50' Began 8:10 Rec 1.50' End 10:30 Loss _____ Time 140 min Gain _____ Drl time 135 min Hyl press 75 Water press low RPM 75 Drl Action Smooth Water ret BROWN |
| 448.1 | 1.0 | | Run No. 1 - RAD. | 100% | Box | Remarks Disturbed Hydraulic Pump |
| 448.1 | 2.0 | | CONCRETE. | | 1 | Run No 2 - 2 Dec 80 NL _____ Run 2.70' Began 9:30 Rec 2.70' End 1:30 Loss _____ Time 240 min Gain _____ Drl time 230 min Hyl press 70-100 Water press MID RPM 75 Drl Action Smooth Water ret BROWN |
| 448.1 | 3.0 | | | 100% | | Remarks - CHANGED B.T. |
| 448.1 | 4.0 | | Run No 2 - RAD - 100% | 4.15 | | Run No 3 - 3 Dec 80 NL _____ Run 2.40' Began 1:30 Rec 2.40' End 9:50 Loss _____ Time 35 min Gain _____ Drl time 30 min Hyl press 70-100 Water press MID RPM 75 Drl Action Smooth Water ret BROWN |
| 448.1 | 5.0 | | CONCRETE: GOOD CONDITION, PHYSICAL PROPERTIES SAME AS PREVIOUS BORINGS - VERY LITTLE TO NO R-P AND HAIRLINE CRACKS | 100% | | Remarks |
| 448.1 | 6.0 | | Run No 3 RAD - 100% | 6.55 | | |

DIAMOND BITS
79 HWT 33
79 PB 607

LEGEND
 CONCRETE
 HAIRLINE BREAK
MB. MACHINE BREAK
NB. NATURAL BREAK

LOCATION
 Pier No. 15
 VIEW LOOKING UP
 TENNISON PIER

 recorder line

Hole No. SUEI-5157-50

| DRILLING LOG | | DIVISION | | INSTALLATION | | SHEET | |
|--|--|----------|--|---|--|--------------------------|--|
| 1. PROJECT | | | | LOCK + DAM #24 | | 2 of 5 SHEETS | |
| 2. LOCATION (Coordinates or Station) | | | | 10. SIZE AND TYPE OF BIT | | | |
| 3. DRILLING AGENCY | | | | 11. DATUM FOR ELEVATION SHOWN (TYP. or MSL) | | | |
| 4. HOLE NO. (As shown on drawing title) and site number | | | | 12. MANUFACTURER'S DESIGNATION OF DRILL | | | |
| 5. NAME OF DRILLER | | | | 13. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN | | DISTURBED UNDISTURBED | |
| 6. DIRECTION OF HOLE <input type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED DEG. FROM VERT. | | | | 14. TOTAL NUMBER CORE BOXES | | | |
| 7. THICKNESS OF OVERBURDEN | | | | 15. ELEVATION GROUND WATER | | | |
| 8. DEPTH DRILLED INTO ROCK | | | | 16. DATE HOLE STARTED COMPLETED | | | |
| 9. TOTAL DEPTH OF HOLE | | | | 17. ELEVATION TOP OF HOLE | | | |
| | | | | 18. TOTAL CORE RECOVERY FOR BORING | | % | |
| | | | | 19. SIGNATURE OF INSPECTOR | | | |

| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | % CORE RECOVERY | BOX OR SAMPLE NO. | REMARKS (Drilling time, water loss, depth of overburden, etc., if significant) |
|-----------|-------|--------|---|-----------------|-------------------|--|
| 4240 | 30° | Δ | | | | |
| | | | RUN #11 RQD=100% | | 36.75 | |
| 4230 | 31° | Δ | | | | |
| | | | | | | |
| 4210 | 32° | Δ | | | | |
| | | | | | | |
| 4200 | 33° | Δ | NO CONCRETE LOT | 100% | Box 9 | |
| | | | | | | |
| 4190 | 34° | Δ | | | | |
| | | | | | | |
| 4180 | 35° | Δ | RUN #12 RQD=100% 2" MACHINE BREAK | | 34.8 | |
| | | | CONCRETE LOT | | | |
| 4174 | 34° | Δ | 3/4" REBAR RUN #13 | | | |
| | | | | | Box 10 | |
| 4160 | 37° | Δ | | | | |
| | | | CONCRETE LOT | | | |
| 4150 | 38° | Δ | | | 37.95 | |
| | | | | | | |
| 4140 | 39° | Δ | | | Box 11 | |
| | | | | | | |
| 4130 | 40° | Δ | RUN #14 | | | |

Run #13
 WL Began 4.05 Run 0.9
 End 5.45 Loss 0.1
 Time 63 min Gain 0.8
 Drl time 6 min
 Hyd press 7002
 Water press —
 RPM 785
 Drl Action Smooth
 Water ret —
 Remarks —

Run #14
 27 October 80
 WL — Run #14
 Began 10.40 Run 42
 End 3.25 Loss —
 Time 75 min Gain 0.8
 Drl time 70 min
 Hyd press 7002
 Water press —
 RPM 502
 Drl Action Smooth
 Water ret —
 Remarks —

BNG FORM 1836 PREVIOUS EDITIONS ARE OBSOLETE.
MAR 71 (TRANSLUCENT)

PROJECT

HOLE NO.

Hole No. SWES-COS-1W-50

| DRILLING LOG | | DIVISION | INSTALLATION | SHEET | | |
|---|-------|---|---|----------------|-------------------|--|
| PROJECT | | ST. LOUIS, MO. | LOCK-DAM No 24 | 1 OF 1 SHEETS | | |
| 1. LOCATION (Compass or Station) | | 10. SIZE AND TYPE OF BIT | | | | |
| 2. DRILLING AGENCY | | 11. DAY FOR ELEVATION FROM (F.M. or M.S.L.) | | | | |
| 3. HOLE NO. (As shown on drawing title) | | 12. MANUFACTURER'S DESIGNATION OF DRILL | | | | |
| 4. NAME OF DRILLER | | 13. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN | | | | |
| 5. DIRECTION OF HOLE | | 14. TOTAL NUMBER CORE BORES | | | | |
| 6. THICKNESS OF OVERBURDEN | | 15. ELEVATION GROUND WATER | | | | |
| 7. DEPTH DRILLED INTO ROCK | | 16. DATE HOLE | | | | |
| 8. TOTAL DEPTH OF HOLE | | 17. ELEVATION TOP OF HOLE | | | | |
| | | 18. TOTAL CORE RECOVERY FOR BORING | | | | |
| | | 19. SIGNATURE OF INSPECTOR | | | | |
| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | SCORE RECOVERY | BOX OR SAMPLE NO. | REMARKS (Drilling time, water loss, depth of overburden, etc., if significant) |
| 466.500 | 0.0 | | ~ BROKEN UP | | | Run No 1 18 Nov 80 |
| 466.510 | 1.0 | | REBAR - 1/2" | | | WL - 0.40 |
| 466.520 | 2.0 | | CONCRETE | 100% | Box 1 | Began 2.20 P. 0.40 |
| 466.530 | 3.0 | | REBAR - 1/2" | | | End 2.35 Lcp - |
| | | | Run No 2 RRD = 100% | | | Time 13min Gull - |
| | | | | | | Drl time 15min |
| | | | | | | Hyd press - |
| | | | | | | Water press HGD |
| | | | | | | RPM 300 |
| | | | | | | Drl Action Smooth |
| | | | | | | Water ret |
| | | | | | | Brown |
| | | | | | | Remarks |
| | | | | | | Run No 2 |
| | | | | | | Run 2.7' |
| | | | | | | Began 2.45 |
| | | | | | | Rec 2.7' |
| | | | | | | End 3.50 |
| | | | | | | Loss - |
| | | | | | | Time 65min |
| | | | | | | Drl time 65min |
| | | | | | | Hyd press - |
| | | | | | | Water press HGD |
| | | | | | | RPM - 300 |
| | | | | | | Drl Action Smooth |
| | | | | | | Water ret |
| | | | | | | Brown |
| | | | | | | Remarks |
| | | | | | | CONCRETE: PHYSICAL PROPERTIES SAME. |
| | | | | | | CONDITION OF CONCRETE IS FAIR. |
| | | | | | | ENDS ARE WEATHERED WITH TOP |
| | | | | | | PORTION BROKEN UP AT REBAR. |
| | | | | | | LITTLE TO NO REACTION PRODUCT |
| | | | | | | IS VISIBLE - |

DIAMOND BIT No

81PC178

81PC173

LEGEND

CONCRETE

HAIRLINE CRACK

MB - MACHINE BREAK

NB - NATURAL BREAK

BROKEN UP - PIECES TOO SMALL TO LOG

LOCATION

VIEW LOOKING EAST

ENG FORM 1836 PREVIOUS EDITIONS ARE OBSOLETE
MAR 71 (TRANSLUCENT)

Hole No. SWS-CO2-2N-50

| | | | | | | | |
|---|--|-----------------------------------|--|---|--|--------------------------------------|--|
| DRILLING LOG | | Division ST. LOUIS, Mo. | | INSTALLATION LOCK & DAM No 24 | | SHEET 1 OF 1 SHEETS | |
| 1. PROJECT LOCK & DAM No 24 | | | | 10. SIZE AND TYPE OF BIT 3 1/2" Delta 626 1/2" | | | |
| 2. LOCATION (Coordinates or Section) SEE BELOW | | | | 11. DAY/TON FOR ELEVATION BROWN (FEET - INCHES) MSL | | | |
| 3. DRILLING AGENCY C.E.W.E.S. | | | | 12. MANUFACTURER'S DESIGNATION OF DRILL ELECTRIC - CORE DRILL | | | |
| 4. HOLE NO. (As shown on drawing 100%) SWS-CO2-2N-50 | | | | 13. TOTAL NO. OF OVER- BURDEN SAMPLES TAKEN DISTURBED UNDISTURBED | | | |
| 5. NAME OF DRILLER H. McNAMARA | | | | 14. TOTAL NUMBER CORE BOXES ONE | | | |
| 6. DIRECTION OF HOLE <input type="checkbox"/> VERTICAL <input checked="" type="checkbox"/> INCLINED 90° DEG. FROM VERT. | | | | 15. ELEVATION GROUND WATER | | | |
| 7. THICKNESS OF OVERBURDEN | | | | 16. DATE HOLE 21 Nov 60 21 Nov 60 | | | |
| 8. DEPTH DRILLED INTO ROCK 3.5' | | | | 17. ELEVATION TOP OF HOLE 468.6 FT. GROUND | | | |
| 9. TOTAL DEPTH OF HOLE | | | | 18. TOTAL CORE RECOVERY FOR BORING 100% | | | |
| 19. SIGNATURE OF INSPECTOR <i>James B. Williams</i> | | | | | | | |

| ELEVATION a | DEPTH b | LEGEND c | CLASSIFICATION OF MATERIALS (Description) d | 5. CORE RECOVERY e | BOX OR SAMPLE NO. f | REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g |
|----------------|------------|-------------|---|--------------------------|------------------------------|---|
| 468.6 00 | | Δ | | | | Run No 1 21 Nov 60 |
| | | Δ | 16" SHN REBAR | | | AL — RC: 3.5' |
| 468.6 10 | | Δ | 16" SHN REBAR | | | Began 10 05 RC 3.5 |
| | | Δ | 16" SHN REBAR | | | End 11 20 LOSS — |
| | | Δ | 16" REBAR | | | Time 75 min GAIN — |
| 468.6 20 | | Δ | 16" REBAR | | | Drill time 10 min |
| | | Δ | 16" REBAR | | | Hyd press — |
| | | Δ | CONCRETE | | | Water press 160 |
| 468.6 30 | | Δ | CONCRETE | | | RFN 5005 |
| | | Δ | Run No 1 R&D 100% | | | Drill Action Smooth |
| | | Δ | | | | Water ret |
| | | Δ | | | | (Beckman) |
| | | Δ | | | | Remarks |

CONCRETE: VERY GOOD CONDITION, NO HAIRLINE
CRACKS, VERY LITTLE TO NO FLAKING PRODUCT,
AND PHYSICAL PROPERTIES SAME AS OTHER
W.E.S. BORINGS

DIAMOND BITS

79PN429

LEGEND

16" CONCRETE

16" HAIRLINE CRACK

MB. MACHINE BREAK

NB. NATURAL BREAK

LOCATION

ENG FORM 1836 PREVIOUS EDITIONS ARE OBSOLETE
MAR 71 (TRANSLUCENT)

Hole No. SWES-COS 45-80

| DRILLING LOG | | DIVISION | | INSTALLATION | | SHEET | |
|---|-------|---|--|---|----------------------|---|--|
| 1. PROJECT | | 2. LOCATION | | 3. DATE AND TYPE OF BIT | | 4. DATE FOR ELEVATION | |
| LOCK + DAM NO. 24 | | SEE BELOW | | M3L | | 11/15/80 | |
| 5. DRILLING AGENCY | | 6. HOLE NO. (As shown on drawing sheet) and site number | | 7. NAME OF DRILLER | | 8. DIRECTION OF HOLE | |
| CEWES | | SWES-COS 45-80 | | McNamara | | 90° DES. FROM VERT. | |
| 9. THICKNESS OF OVERBURDEN | | 10. DEPTH DRILLED INTO ROCK | | 11. TOTAL DEPTH OF HOLE | | 12. DATE HOLE | |
| 3.5 | | 3.5 | | 446.5' - CENTER | | 11/15/80 | |
| 13. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN | | 14. TOTAL NUMBER CORE BOXES | | 15. ELEVATION GROUND WATER | | 16. ELEVATION TOP OF HOLE | |
| 0 | | ONE | | | | 446.5' - CENTER | |
| 17. TOTAL CORE RECOVERY FOR BORING | | 18. SIGNATURE OF INSPECTOR | | 19. SIGNATURE OF DRILLER | | 20. SIGNATURE OF WITNESS | |
| 100% | | [Signature] | | [Signature] | | [Signature] | |
| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | 1. CORE RECOVERY | 2. BOX OR SAMPLE NO. | REMARKS (Drilling time, water loss, depth of overburden, etc., if significant) | |
| 466.5 | 0.0 | | MATERIAL IN RUN NO. 1 IS LOOSE GRAVEL & RUBBLE - CORES ARE VISIBLE FROM BORING | 100% | Box 1 | Run No. 1 18 Nov 80 WL — Run 0.8' Began 11:05 Rec 0.8' End 11:15 Loss — Time 10 min Gals — Drl time 10 min Hyd press — Water press MED RPM 300 Drl Action Smooth Water ret Brown Remarks Blocked off - RUBBLE | |
| 466.5 | 1.0 | | CONCRETE | 100% | Box 1 | Run No. 2 WL — Run 2.7 Began 11:30 Rec 2.7 End 1:30 Loss — Time 120 min Gals — Drl time 120 min Hyd press — Water press MED RPM 300 Drl Action Smooth Water ret Brown Remarks | |
| 466.5 | 2.0 | | | | | | |
| 466.5 | 3.0 | | | | | | |
| <p>Run No. 2 RRD = 96.3% 3.50</p> <p>CONCRETE: PHYSICAL PROPERTIES THE SAME - CONDITION IS VERY POOR FROM 0.0 TO 0.8'. MATERIAL IS RUBBLE - CONDITION IMPROVING WITH DEPTH - MODERATE REACTION PRODUCT.</p> | | | | | | | |
| DIAMOND BIT NO | | LEGEND | | LOCATION | | | |
| 81 PC 175 | | <p>CONCRETE</p> <p>MINOR CRACK</p> <p>MA MACHINE BREAK</p> <p>NB. NATURAL BREAK</p> | | <p>PIER NO. 5</p> <p>CONSTRUCTION JOINT</p> <p>45'</p> <p>SWES COS 45-80</p> <p>CENTER OF COLUMN</p> <p>VIEW LOOKING UP</p> | | | |

BMC FORM 1836 PREVIOUS EDITIONS ARE OBSOLETE. (TRANSLUCENT)

Mole No. SNEX-COS 15-80

| DRILLING LOG | | DIVISION | | INSTALLATION | | SHEET | |
|---|--|------------------|--|--|--|---|--|
| PROJECT | | ST. LOUIS, MO | | LOCK + DAM No 24 | | OF 1 SHEETS | |
| 1. PROJECT | | LOCK + DAM No 24 | | 10. SIZE AND TYPE OF BIT | | 6 INCH - 5/8" DIA | |
| 2. LOCATION (Coordinates or Station) | | SEC BELOW | | 11. DATUM FOR ELEVATION SHOWN (FMS or BBL) | | MSL | |
| 3. DRILLING AGENCY | | CEWES | | 12. MANUFACTURER'S DESIGNATION OF DRILL | | ELECTRIC - CORE DRILL | |
| 4. HOLE NO. (As shown on drawing title and site number) | | SNEX-COS 15-80 | | 13. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN | | DISTURBED | |
| 5. NAME OF DRILLER | | A. McNamara | | 14. TOTAL NUMBER CORE BOXES | | ONE | |
| 6. DIRECTION OF HOLE | | 90° | | 15. ELEVATION GROUND WATER | | | |
| 7. THICKNESS OF OVERBURDEN | | | | 16. DATE HOLE | | STARTED 17 November 80 COMPLETED 17 November 80 | |
| 8. DEPTH DRILLED INTO ROCK | | 35 | | 17. ELEVATION TOP OF HOLE | | 465.5 | |
| 9. TOTAL DEPTH OF HOLE | | | | 18. TOTAL CORE RECOVERY FOR BORING | | 100% | |
| ELEVATION | | DEPTH | | LEGEND | | CLASSIFICATION OF MATERIALS (Description) | |
| 465.5 | | 00 | | Run No 1 | | RQD - 0% | |
| 465.5 | | 10 | | Run No 2 | | RQD - 100% | |
| 465.5 | | 20 | | Run No 3 | | RQD - 100% | |
| 465.5 | | 30 | | Run No 4 | | RQD - 100% | |
| | | | | Run No 5 | | RQD - 100% | |
| | | | | Run No 6 | | RQD - 100% | |
| | | | | Run No 7 | | RQD - 100% | |
| | | | | Run No 8 | | RQD - 100% | |
| | | | | Run No 9 | | RQD - 100% | |
| | | | | Run No 10 | | RQD - 100% | |
| | | | | Run No 11 | | RQD - 100% | |
| | | | | Run No 12 | | RQD - 100% | |
| | | | | Run No 13 | | RQD - 100% | |
| | | | | Run No 14 | | RQD - 100% | |
| | | | | Run No 15 | | RQD - 100% | |
| | | | | Run No 16 | | RQD - 100% | |
| | | | | Run No 17 | | RQD - 100% | |
| | | | | Run No 18 | | RQD - 100% | |
| | | | | Run No 19 | | RQD - 100% | |
| | | | | Run No 20 | | RQD - 100% | |
| | | | | Run No 21 | | RQD - 100% | |
| | | | | Run No 22 | | RQD - 100% | |
| | | | | Run No 23 | | RQD - 100% | |
| | | | | Run No 24 | | RQD - 100% | |
| | | | | Run No 25 | | RQD - 100% | |
| | | | | Run No 26 | | RQD - 100% | |
| | | | | Run No 27 | | RQD - 100% | |
| | | | | Run No 28 | | RQD - 100% | |
| | | | | Run No 29 | | RQD - 100% | |
| | | | | Run No 30 | | RQD - 100% | |
| | | | | Run No 31 | | RQD - 100% | |
| | | | | Run No 32 | | RQD - 100% | |
| | | | | Run No 33 | | RQD - 100% | |
| | | | | Run No 34 | | RQD - 100% | |
| | | | | Run No 35 | | RQD - 100% | |
| | | | | Run No 36 | | RQD - 100% | |
| | | | | Run No 37 | | RQD - 100% | |
| | | | | Run No 38 | | RQD - 100% | |
| | | | | Run No 39 | | RQD - 100% | |
| | | | | Run No 40 | | RQD - 100% | |
| | | | | Run No 41 | | RQD - 100% | |
| | | | | Run No 42 | | RQD - 100% | |
| | | | | Run No 43 | | RQD - 100% | |
| | | | | Run No 44 | | RQD - 100% | |
| | | | | Run No 45 | | RQD - 100% | |
| | | | | Run No 46 | | RQD - 100% | |
| | | | | Run No 47 | | RQD - 100% | |
| | | | | Run No 48 | | RQD - 100% | |
| | | | | Run No 49 | | RQD - 100% | |
| | | | | Run No 50 | | RQD - 100% | |
| | | | | Run No 51 | | RQD - 100% | |
| | | | | Run No 52 | | RQD - 100% | |
| | | | | Run No 53 | | RQD - 100% | |
| | | | | Run No 54 | | RQD - 100% | |
| | | | | Run No 55 | | RQD - 100% | |
| | | | | Run No 56 | | RQD - 100% | |
| | | | | Run No 57 | | RQD - 100% | |
| | | | | Run No 58 | | RQD - 100% | |
| | | | | Run No 59 | | RQD - 100% | |
| | | | | Run No 60 | | RQD - 100% | |
| | | | | Run No 61 | | RQD - 100% | |
| | | | | Run No 62 | | RQD - 100% | |
| | | | | Run No 63 | | RQD - 100% | |
| | | | | Run No 64 | | RQD - 100% | |
| | | | | Run No 65 | | RQD - 100% | |
| | | | | Run No 66 | | RQD - 100% | |
| | | | | Run No 67 | | RQD - 100% | |
| | | | | Run No 68 | | RQD - 100% | |
| | | | | Run No 69 | | RQD - 100% | |
| | | | | Run No 70 | | RQD - 100% | |
| | | | | Run No 71 | | RQD - 100% | |
| | | | | Run No 72 | | RQD - 100% | |
| | | | | Run No 73 | | RQD - 100% | |
| | | | | Run No 74 | | RQD - 100% | |
| | | | | Run No 75 | | RQD - 100% | |
| | | | | Run No 76 | | RQD - 100% | |
| | | | | Run No 77 | | RQD - 100% | |
| | | | | Run No 78 | | RQD - 100% | |
| | | | | Run No 79 | | RQD - 100% | |
| | | | | Run No 80 | | RQD - 100% | |
| | | | | Run No 81 | | RQD - 100% | |
| | | | | Run No 82 | | RQD - 100% | |
| | | | | Run No 83 | | RQD - 100% | |
| | | | | Run No 84 | | RQD - 100% | |
| | | | | Run No 85 | | RQD - 100% | |
| | | | | Run No 86 | | RQD - 100% | |
| | | | | Run No 87 | | RQD - 100% | |
| | | | | Run No 88 | | RQD - 100% | |
| | | | | Run No 89 | | RQD - 100% | |
| | | | | Run No 90 | | RQD - 100% | |
| | | | | Run No 91 | | RQD - 100% | |
| | | | | Run No 92 | | RQD - 100% | |
| | | | | Run No 93 | | RQD - 100% | |
| | | | | Run No 94 | | RQD - 100% | |
| | | | | Run No 95 | | RQD - 100% | |
| | | | | Run No 96 | | RQD - 100% | |
| | | | | Run No 97 | | RQD - 100% | |
| | | | | Run No 98 | | RQD - 100% | |
| | | | | Run No 99 | | RQD - 100% | |
| | | | | Run No 100 | | RQD - 100% | |
| | | | | Run No 101 | | RQD - 100% | |
| | | | | Run No 102 | | RQD - 100% | |
| | | | | Run No 103 | | RQD - 100% | |
| | | | | Run No 104 | | RQD - 100% | |
| | | | | Run No 105 | | RQD - 100% | |
| | | | | Run No 106 | | RQD - 100% | |
| | | | | Run No 107 | | RQD - 100% | |
| | | | | Run No 108 | | RQD - 100% | |
| | | | | Run No 109 | | RQD - 100% | |
| | | | | Run No 110 | | RQD - 100% | |
| | | | | Run No 111 | | RQD - 100% | |
| | | | | Run No 112 | | RQD - 100% | |
| | | | | Run No 113 | | RQD - 100% | |
| | | | | Run No 114 | | RQD - 100% | |
| | | | | Run No 115 | | RQD - 100% | |
| | | | | Run No 116 | | RQD - 100% | |
| | | | | Run No 117 | | RQD - 100% | |
| | | | | Run No 118 | | RQD - 100% | |
| | | | | Run No 119 | | RQD - 100% | |
| | | | | Run No 120 | | RQD - 100% | |
| | | | | Run No 121 | | RQD - 100% | |
| | | | | Run No 122 | | RQD - 100% | |
| | | | | Run No 123 | | RQD - 100% | |
| | | | | Run No 124 | | RQD - 100% | |
| | | | | Run No 125 | | RQD - 100% | |
| | | | | Run No 126 | | RQD - 100% | |
| | | | | Run No 127 | | RQD - 100% | |
| | | | | Run No 128 | | RQD - 100% | |
| | | | | Run No 129 | | RQD - 100% | |
| | | | | Run No 130 | | RQD - 100% | |
| | | | | Run No 131 | | RQD - 100% | |
| | | | | Run No 132 | | RQD - 100% | |
| | | | | Run No 133 | | RQD - 100% | |
| | | | | Run No 134 | | RQD - 100% | |
| | | | | Run No 135 | | RQD - 100% | |
| | | | | Run No 136 | | RQD - 100% | |
| | | | | Run No 137 | | RQD - 100% | |
| | | | | Run No 138 | | RQD - 100% | |
| | | | | Run No 139 | | RQD - 100% | |
| | | | | Run No 140 | | RQD - 100% | |
| | | | | Run No 141 | | RQD - 100% | |
| | | | | Run No 142 | | RQD - 100% | |
| | | | | Run No 143 | | RQD - 100% | |
| | | | | Run No 144 | | RQD - 100% | |
| | | | | Run No 145 | | RQD - 100% | |
| | | | | Run No 146 | | RQD - 100% | |
| | | | | Run No 147 | | RQD - 100% | |
| | | | | Run No 148 | | RQD - 100% | |
| | | | | Run No 149 | | RQD - 100% | |
| | | | | Run No 150 | | RQD - 100% | |
| | | | | Run No 151 | | RQD - 100% | |
| | | | | Run No 152 | | RQD - 100% | |
| | | | | Run No 153 | | RQD - 100% | |
| | | | | Run No 154 | | RQD - 100% | |
| | | | | Run No 155 | | RQD - 100% | |
| | | | | Run No 156 | | RQD - 100% | |
| | | | | Run No 157 | | RQD - 100% | |
| | | | | Run No 158 | | RQD - 100% | |
| | | | | Run No 159 | | RQD - 100% | |
| | | | | Run No 160 | | RQD - 100% | |
| | | | | Run No 161 | | RQD - 100% | |
| | | | | Run No 162 | | RQD - 100% | |
| | | | | Run No 163 | | RQD - 100% | |
| | | | | Run No 164 | | RQD - 100% | |
| | | | | Run No 165 | | RQD - 100% | |
| | | | | Run No 166 | | RQD - 100% | |
| | | | | Run No 167 | | RQD - 100% | |
| | | | | Run No 168 | | RQD - 100% | |
| | | | | Run No 169 | | RQD - 100% | |
| | | | | Run No 170 | | RQD - 100% | |
| | | | | Run No 171 | | RQD - 100% | |
| | | | | Run No 172 | | RQD - 100% | |
| | | | | Run No 173 | | RQD - 100% | |
| | | | | Run No 174 | | RQD - 100% | |
| | | | | Run No 175 | | RQD - 100% | |
| | | | | Run No 176 | | RQD - 100% | |
| | | | | Run No 177 | | RQD - 100% | |
| | | | | Run No 178 | | RQD - 100% | |
| | | | | Run No 179 | | RQD - 100% | |
| | | | | Run No 180 | | RQD - 100% | |
| | | | | Run No 181 | | RQD - 100% | |
| | | | | Run No 182 | | RQD - 100% | |
| | | | | Run No 183 | | RQD - 100% | |
| | | | | Run No 184 | | RQD - 100% | |
| | | | | Run No 185 | | RQD - 100% | |
| | | | | Run No 186 | | RQD - 100% | |
| | | | | Run No 187 | | RQD - 100% | |
| | | | | Run No 188 | | RQD - 100% | |
| | | | | Run No 189 | | RQD - 100% | |
| | | | | Run No 190 | | RQD - 100% | |
| | | | | Run No 191 | | RQD - 100% | |
| | | | | Run No 192 | | RQD - 100% | |
| | | | | Run No 193 | | RQD - 100% | |
| | | | | Run No 194 | | RQD - 100% | |
| | | | | Run No 195 | | RQD - 100% | |
| | | | | Run No 196 | | RQD - 100% | |
| | | | | Run No 197 | | RQD - 100% | |
| | | | | Run No 198 | | RQD - 100% | |
| | | | | Run No 199 | | RQD - 100% | |
| | | | | Run No 200 | | RQD - 100% | |
| | | | | Run No 201 | | RQD - 100% | |
| | | | | Run No 202 | | RQD - 100% | |
| | | | | Run No 203 | | RQD - 100% | |
| | | | | Run No 204 | | RQD - 100% | |
| | | | | Run No 205 | | RQD - 100% | |
| | | | | Run No 206 | | RQD - 100% | |
| | | | | Run No 207 | | RQD - 100% | |
| | | | | Run No 208 | | RQD - 100% | |
| | | | | Run No 209 | | RQD - 100% | |
| | | | | Run No 210 | | RQD - 100% | |
| | | | | | | | |

Hole No. SWES-C07.3N-80

| DRILLING LOG | | DIVISION | | INSTALLATION | | SHEET | |
|---|-------|---|---|--|-------------------|--|--|
| PROJECT | | ST. LOUIS | | LOCK 3 DAM No 24 | | 1 OF 1 SHEETS | |
| 1. PROJECT | | 2. LOCATION (If Supplemental to Station) | | 10. SIZE AND TYPE OF BIT | | 11. DATE FOR ELEVATION THW (TYP) = | |
| Lock + Dam No 24 | | SEE BELOW | | M.S. | | 4647-62 | |
| 3. DRILLING AGENCY | | 4. HOLE NO. (As shown on drawing title and file number) | | 12. MANUFACTURER'S DESIGNATION OF DRILL | | 13. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN | |
| C.S.W.S. | | SWES-C07.3N-80 | | ELECTRIC - C-07.3N-80 | | DISTURBED UNDISTURBED | |
| 5. NAME OF DRILLER | | 6. DIRECTION OF HOLE | | 14. TOTAL NUMBER CORE BOXES | | 15. ELEVATION GROUND WATER | |
| A. McNamara | | <input type="checkbox"/> VERTICAL <input checked="" type="checkbox"/> INCLINED 90 DEG. FROM VERT. | | ONE | | | |
| 7. THICKNESS OF OVERBURDEN | | 8. DEPTH DRILLED INTO ROCK | | 16. DATE HOLE | | 17. ELEVATION TOP OF HOLE | |
| 3.5 | | 3.5 | | 15 November 80 | | 4647 | |
| 9. TOTAL DEPTH OF HOLE | | 18. TOTAL CORE RECOVERY FOR SPRING | | 19. SIGNATURE OF INSPECTOR | | 20. REMARKS | |
| 4647.30 | | 100% | | Joseph B. Dill | | Run No 1 15 Nov 80 RL - Run 3.5 Began 11:30 Re 3.5 End 3:30 Loc - Time 240 min Gals - Drl time 125 min Hyd press - Water press MED RPM 3000 Drl Action Smooth Water ret Brown Remarks Drill Binding UP at 2.5' Drl Depth | |
| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | % CORE RECOVERY | BOX OR SAMPLE NO. | REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) | |
| 4647.00 | 0.0 | Δ | 1" x 1" STEEL | | | | |
| 4647.10 | 0.1 | Δ | 1/2" REBAR | | | | |
| 4647.20 | 0.2 | Δ | 1/2" REBAR | | | | |
| 4647.30 | 0.3 | Δ | CONCRETE: | 100% | Box 1 | | |
| | | | HAIRLINE CRACK (1/16" TO 1/8" MAX WIDTH) | | | | |
| | | | 1" x 1" REBAR | | | | |
| | | | 1/2" REBAR | | | | |
| | | | Run No 1 RCD=100% | | 35 | | |
| <p>CONCRETE: Physical Properties Same. Condition Appears Good. LARGE CRACK AT 2.5' TO 3.5' WAS FOUND ON CORE. VERY LITTLE REACTION PRODUCT WAS VISIBLE.</p> | | | | | | | |
| <p>DIAMOND BIT No 81PC 172 81PC 175</p> | | | | <p>LEGEND [A] - CONCRETE MB - MACHINE BIT NB - NATURAL BIT</p> | | | |
| | | | | <p>LOCATION PIER No. 7 VIEW LOOKING D/S SWES-C 07.3N-80 Center of column Column # 3</p> | | | |

ENG FORM 1836 MAR 71 PREVIOUS EDITIONS ARE OBSOLETE. (TRANSLUCENT)

PROJECT HOLE NO.

Hole No. SWES-HS1-60

| | | | | | | | |
|---|--|-------------------------------|--|--|--|-----------------------------------|--|
| DRILLING LOG | | DIVISION <u>St. Louis, Mo</u> | | INSTALLATION <u>Lake & Dam No 24</u> | | SHEET <u>1</u> OF <u>1</u> SHEETS | |
| 1. PROJECT <u>Lock & Dam No. 24</u> | | | | 10. SIZE AND TYPE OF BIT <u>6 x 4 1/2"</u> | | | |
| 2. LOCATION (To nearest or known) <u>SEE BELOW</u> | | | | 11. STATUS FOR ELEVATION FROM ITEM 10 <u>MSL</u> | | | |
| 3. DRILLING AGENCY <u>CEWES</u> | | | | 12. MANUFACTURER'S DESIGNATION OF DRILL <u>ELECTRIC - CORE DRILL</u> | | | |
| 4. HOLE NO. (As shown on opening note) and the number <u>SWES-HS1-60</u> | | | | 13. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN <u>UNDISTURBED</u> | | | |
| 5. NAME OF DRILLER <u>H. Mc Namara</u> | | | | 14. TOTAL NUMBER CORE BOXES <u>ONE</u> | | | |
| 6. DIRECTION OF HOLE <input type="checkbox"/> VERTICAL <input checked="" type="checkbox"/> INCLINED <u>90°</u> DEG. FROM VERT. | | | | 15. ELEVATION GROUND WATER | | | |
| 7. THICKNESS OF OVERBURDEN <u>0.2'</u> | | | | 16. DATE HOLE STARTED <u>1 Dec 50</u> COMPLETED <u>1 Dec 50</u> | | | |
| 8. DEPTH DRILLED INTO ROCK | | | | 17. ELEVATION TOP OF HOLE <u>271.6 - Center</u> | | | |
| 9. TOTAL DEPTH OF HOLE | | | | 18. TOTAL CORE RECOVERY FOR BORING <u>100%</u> | | | |
| 19. SIGNATURE OF INSPECTOR <u>Jan 15 1951</u> | | | | | | | |

| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | 3 CORE RECOVERY | BOX OR SAMPLE NO. | REMARKS (Drilling time, water loss, depth of penetration, etc., if significant) |
|--|-------|--------|--|-----------------|-------------------|--|
| 4733.80 | 0.0 | • 8.0 | CONCRETE - GOOD CONDITION - | | | |
| | | • 6.0 | REBAR - 1/2" - RUN NO. 1 | | | ROD = 100% |
| 4733.10 | 1.0 | | LOCATION - PIER NO 5 | | | |
| | | | | | | AL — • Fur. 0.72 Began 10:30 Rec 0.72 End 10:45 Loss — Time 15 min Gain — Dri time 10 min Hyd press — Water press Hand RPM 3000 Dri Action Signal Water ret Brown Remarks |
| | | | 1.7' 23" SWES-HS1-60 CENTERLINE VIEW LOOKING U/S | | | |
| LEGEND LB - CONCRETE MB - MACHINE BREAK NB - NATURAL BREAK DIAMOND BITS 79PB689 | | | | | | |

BIC FORM 1836 MAR 71 PREVIOUS EDITIONS ARE OBSOLETE. PROJECT HOLE NO.

| DRILLING LOG | | DIVISION | | INSTALLATION | | SHEET | |
|--|-------|----------------|--|--|--------------------------|---|--|
| PROJECT Lock & Dam No. 24 | | St. Louis, Mo. | | Lock & Dam No. 24 | | OF 1 SHEETS | |
| LOCATION (Continuation of Section) | | SEE BELOW | | NO. SIZE AND TYPE OF BIT 6" SEE BELOW | | | |
| DRILLING AGENCY CE WES | | | | 11. DAY/TON FOR ELEVATION SHOWING TIME & DATE M.S.L. | | | |
| HOLE NO. (As shown on drawing sheet and No. number) | | SWES-C09.15-80 | | 12. MANUFACTURER'S DESIGNATION OF DRILL ELECTRIC - Core Drill | | | |
| NAME OF DRILLER A. McNamara | | | | 13. TOTAL NO. OF OVER- BURDEN SAMPLES TAKEN | | DISTURBED UNDISTURBED | |
| DIRECTION OF HOLE <input type="checkbox"/> VERTICAL <input checked="" type="checkbox"/> INCLINED 90° DEG. FROM VERT. | | | | 14. TOTAL NUMBER CORE BOXES | | CNC | |
| THICKNESS OF OVERBURDEN | | | | 15. ELEVATION GROUND WATER | | | |
| DEPTH DRILLED INTO ROCK | | 3.50' | | 16. DATE HOLE STARTED 11/10/80 COMPLETED 11/10/80 | | | |
| TOTAL DEPTH OF HOLE | | | | 17. ELEVATION TOP OF HOLE | | 468.0 FT | |
| | | | | 18. TOTAL CORE RECOVERY FOR BORING | | 100% | |
| | | | | 19. SIGNATURE OF INSPECTOR | | [Signature] | |
| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Designation) | 1. CORE RECOVERY % | 2. CORE SAMPLE NO. | REMARKS (Drilling time, water level, depth of penetration, etc., if significant) | |
| 468.0 | 0.0 | | Weathered - Poor Condition | | | 11/10/80 8:55 Began 11:00 Ret 5:5 End 3:00 LGS - Time 240 min Gals - Drl time 200 min Hyd press - water press MED RPM 300 ft Drl Action Smooth Water ret Brown Remarks | |
| 468.0 | 1.0 | | | 100% | Box 1 | | |
| 468.0 | 2.0 | | 1/2" REBAR AGE CRACKED CONCRETE. | | | | |
| 468.0 | 3.0 | | 1/2" REBAR - 1"x1" | | | | |
| | | | Run 1 RQD - 85.7% | 3.50 | | | |
| <p>CONCRETE Physical Properties same as other W.S. borings. Intense weathering on upper surface (0.0-2.0') of core. Numerous hairline cracks and breaks are found along with moderate reaction product on surfaces. Concrete is in Poor Condition.</p> | | | | | | | |
| <p>Diamond Bit No. 81PC174 81PC172</p> | | | | <p>LEGEND CONCRETE HAIRLINE CRACK MACHINE BREAK NATURAL BREAK </p> | | | |
| | | | | <p>LOCATION CENTER OF COLUMN CONSTANT JOINT VIEW LOOKING U/S COLUMN No. 1 Piece No. 5 </p> | | | |

| DRILLING LOG | | DIVISION | | INSTALLATION | | SHEET | |
|--|-------|---------------------|---|---------------------------------------|-------------------|---|--|
| PROJECT | | ST. LOUIS MO | | Locks Dam No. 24 | | 1 OF 1 SHEETS | |
| LOCATION (Continent or Station) | | SEE BELOW | | MSL | | | |
| DRILLING AGENCY | | C.F.W.E.S. | | MANUFACTURER'S DESIGNATION OF DRILL | | ELECTRIC - CORE DRILL | |
| HOLE NO. (As shown on drawing title) | | SWES-C09-1W-80 | | TOTAL NO. OF OVERBURDEN SAMPLES TAKEN | | DISTURBED UNDISTURBED | |
| NAME OF DRILLER | | A. McNamara | | TOTAL NUMBER CORE BOXES | | ONE | |
| DIRECTION OF HOLE | | 90° DEG. FROM VERT. | | DATE HOLE | | STARTED 14 NOVEMBER 1980 COMPLETED 14 NOVEMBER 1980 | |
| THICKNESS OF OVERBURDEN | | 3.05' | | ELEVATION TOP OF HOLE | | 4660 | |
| DEPTH DRILLED INTO ROCK | | 3.05' | | TOTAL CORE RECOVERY FOR BORING | | 100% | |
| TOTAL DEPTH OF HOLE | | 3.05' | | SIGNATURE OF INSPECTOR | | J. B. Numb | |
| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | SCORE | BOX OR SAMPLE NO. | REMARKS (Drilling time, water loss, depth of overburden, etc., if significant) | |
| 4660 00 | | Δ | Run No. 1 RQD = 0.0% | | | WL 14 NOV 80 Run 8.15 Began 3:45 Rec 0.15 End 4:00 Loss - Time 15min Gain - Drl time 15min Hyd press - Water press MED RPM 300± Drl Action Smooth Water ret Brown Remarks Blacked off on REBAR | |
| 4660 10 | | Δ | CONCRETE | | | | |
| 4660 20 | | Δ | CONCRETE | | | | |
| 4660 30 | | Δ | Run No. 2 RQD = 88.8% | | | WL Run 2.7 Began 4:05 Rec 2.7 End 5:10 Loss - Time 65min Gain - Drl time 65min Hyd press - Water press MED RPM 300± Drl Action Smooth Water ret Brown Remarks | |
| <p>CONCRETE PHYSICAL PROPERTIES THE SAME AS OTHER W.E.S. BORINGS - COAR, AGG. ETC. CONDITION OF CONCRETE APPEARS GOOD NO HAIRLINE CRACKS, SLIGHT REACTION PRODUCT, ALONG WITH V. HIGH RQD - BREAK AT 2.5 WAS DONE IN HANDLING.</p> | | | | | | | |
| <p>DIAMOND Bit No. 81PC172 81PC175</p> <p>LEGEND</p> <p>Δ - CONCRETE</p> <p>--- - HAIRLINE CRACK</p> <p>MB - MACHINE BREAK</p> <p>NB - NATURAL BREAK</p> | | | | | | | |
| <p>LOCATION</p> <p>ON CONSTRUCTION JOINT COLUMN No. 1</p> <p>50'</p> <p>ON CENTER OF COLUMN</p> <p>PIER No. 9</p> | | | | | | | |

| DRILLING LOG | | SYMBOL | | INSTALLATION | | SHEET | |
|---|-------|-------------------|---|---|-------------------|--|--|
| PROJECT | | St Louis, Mo | | Lock & Dam No 24 | | of 1 SHEETS | |
| 1. LOCATION (Continuation of Section) | | SEE BELOW | | 10. SIZE AND TYPE OF BIT | | 11. DATE FOR ELEVATION MEASUREMENT | |
| 2. DRILLING AGENCY | | C.E.W.E.S. | | 12. MANUFACTURER'S DESIGNATION OF DRILL | | 13. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN | |
| 3. HOLE NO. (As shown on drawing only) and file number | | SND-CO-45-80 | | 14. TOTAL NUMBER CORE BOXES | | 15. ELEVATION GROUND WATER | |
| 4. NAME OF DRILLER | | H. McVANNHED | | 16. DATE HOLE | | 17. ELEVATION TOP OF HOLE | |
| 5. DIRECTION OF HOLE | | 90° | | 18. DATE HOLE | | 19. TOTAL CORE RECOVERY FOR BORING | |
| 6. THICKNESS OF OVERBURDEN | | 3.3 | | 19. SIGNATURE OF INSPECTOR | | 20. SIGNATURE OF INSPECTOR | |
| 7. TOTAL DEPTH OF HOLE | | 3.3 | | 20. SIGNATURE OF INSPECTOR | | 21. SIGNATURE OF INSPECTOR | |
| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | CORE RECOVERY % | BOX OR SAMPLE NO. | REMARKS (Including time, water level, depth of overburden, etc., if significant) | |
| 4657.00 | 0.0 | MB | Run No. 2 R.D. 0.0% | | | Run 1 19 Nov 80 | |
| 4657.10 | 1.0 | Δ | CONCRETE | 100% | Box 1 | FL — 0.25 Began 2:50 — 0.25 End 3:05 — 0.25 Time 15 min Drill time 15 min Water press — Drill Action — Smooth Water ret — Brown Remarks — RUSTEEL | |
| 4657.20 | 2.0 | Δ | CONCRETE | 100% | Box 1 | Run 2 FL — Run 3:25 Began 3:40 — Run 3:25 End 4:05 — Run 3:25 Time 25 min Drill time 25 min Water press — Drill Action — Smooth Water ret — Brown Remarks — | |
| 4657.30 | 3.0 | Δ | CONCRETE | 100% | Box 1 | Run 3 FL — Run 3:25 Began 3:40 — Run 3:25 End 4:05 — Run 3:25 Time 25 min Drill time 25 min Water press — Drill Action — Smooth Water ret — Brown Remarks — | |
| CONCRETE PHYSICAL PROPERTIES SAME FAIR CONDITION - LITTLE TO NO REACTION PRODUCT WITH NO OXIDATION ON STEEL'S SURFACE. ENDS ARE SLIGHTLY WEATHERED. | | | | | | | |
| DIAMOND BITS | | LEGEND | | LOCATION | | Center of column | |
| 81RCHB | | 10. CONCRETE | | Pace No. 9 | | VIEW LOOKING U/S | |
| 81RCHB | | 11. MACHINE BREAK | | SND-CO-45-80 | | 10 | |
| | | NB. NATURAL BREAK | | COLUMN No. 4 | | | |

 ENG FORM 1836 PREVIOUS EDITIONS ARE OBSOLETE
 MAR 71 (TRANSLUCENT)

| DRILLING LOG | | Division | INSTALLATION | Hole No. | DATE |
|--|--|--|---------------------------------------|---------------------|---------------------|
| PROJECT | | ST. LOUIS, MO | LOCK & DAM No. 24 | SNES-09-3N-0 | 19 NOV 80 |
| LOCATION (Coordinate or Station) | | SEE BELOW | SIZE AND TYPE OF BIT | SEE BELOW - 6" | |
| DRILLING AGENCY | | CENES | STATUS FOR ELEVATION (Type - H, M, S) | M.S.L. | |
| HOLE NO. (As shown on drawing title) and file number | | SNES-09-3N-00 | MANUFACTURER'S DESIGNATION OF DRILL | ELSCOR - CORE DRILL | |
| NAME OF DRILLER | | A. McNamara | TOTAL NO. OF OVERBURDEN SAMPLES TAKEN | DISTURBED | UNDISTURBED |
| DIRECTION OF HOLE | | VERTICAL <input type="checkbox"/> INCLINED <input checked="" type="checkbox"/> 90° OBS. FROM VERT. | TOTAL NUMBER CORE BOXES | CNC | |
| THICKNESS OF OVERBURDEN | | | ELEVATION GROUND WATER | | |
| DEPTH DRILLED INTO ROCK | | 3.5 | DATE HOLE | STARTED 19 NOV 80 | COMPLETED 19 NOV 80 |
| TOTAL DEPTH OF HOLE | | | ELEVATION TOP OF HOLE | 467.3 FT. | |
| | | | TOTAL CORE RECOVERY FOR BORING | 100% | |
| | | | SIGNATURE OF INSPECTOR | Joseph B. Dinkler | |

| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | SCORE RECORDED | BOX OR SAMPLE NO. | REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) |
|-----------|-------|--------|---|----------------|-------------------|--|
| 467.3 | 00 | | 1/4" HOLE | | | Run No. 1 19 Nov. 80 |
| | | | STEEL 1" x 1" | | | AL Run 0.4 |
| | | | CONCRETE BROWN UP AROUND | | | Began 10:05 Rec 0.4 |
| | | | STEEL | | | End 10:25 Loss |
| 467.3 | 10 | | 1/4" HOLE | | | Time 20 min Gain |
| | | | REBAR | | | Drill time 20 min |
| | | | | | | Hyd press - |
| | | | | | | Water press 700 |
| | | | | | | RPM 600 |
| | | | | | | Drill Action Smooth |
| | | | | | | Water ret |
| | | | | | | Brown |
| | | | | | | Remarks |
| | | | | | | REBAR |
| 467.3 | 20 | | CONCRETE | | | Run No. 2 |
| | | | STEEL - 1" x 1" | | | AL Run 3.1 |
| | | | REBAR | | | Began 10:35 Rec 3.1 |
| | | | | | | End 10:50 Loss |
| | | | | | | Time 15 min Gain |
| | | | | | | Drill time 15 min |
| | | | | | | Hyd press - |
| | | | | | | Water press 700 |
| | | | | | | RPM 300 |
| | | | | | | Drill Action Smooth |
| | | | | | | Water ret |
| | | | | | | Brown |
| | | | | | | Remarks |
| | | | | | | |

CONCRETE: PHYSICAL PROPERTIES THE SAME AS OTHER W.B.S. BORINGS. CONDITION IS POOR GRADING TOWARDS FAIR AT CENTER OF COLUMN. ENDS ARE WEATHERED WITH SLIGHT REACTION PRODUCT. STEEL APPEARS UNOXIDIZED

DIAMOND BITS
81K173
81PC169

LEGEND
[] - CONCRETE
[] - HAIRLINE CRACK
NB - NATURAL BREAK
MB - MACHINE BREAK

LOCATION
PIER NO. 9
6"
CENTER OF COLUMN
COLUMN No. 3
VIEW LOOKING DIS

ENG FORM 1836 PREVIOUS EDITIONS ARE OBSOLETE
MAR 71 (TRANSLUCENT)

PROJECT

HOLE NO.

Hole No. S.W.E.S.-C09-24-50

| DRILLING LOG | | DIVISION | INSTALLATION | SHEET 1 OF 1 SHEETS | | |
|---|-------|----------|---|---------------------|-------------------|---|
| 1. PROJECT | | | 10. SIZE AND TYPE OF BIT | | | |
| 2. LOCATION (Continent or Island) | | | 11. DAYS FOR ELEVATION BROWN (TIME or MILE) | | | |
| 3. DRILLING AGENCY | | | 12. MANUFACTURER'S DESIGNATION OF DRILL | | | |
| 4. HOLE NO. (As shown on drawing 1100) and No. of sample | | | 13. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN | | | |
| 5. NAME OF DRILLER | | | 14. TOTAL NUMBER CORE BOXES | | | |
| 6. DIRECTION OF HOLE <input type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED _____ DEG. FROM VERT. | | | 15. ELEVATION GROUND WATER | | | |
| 7. THICKNESS OF OVERBURDEN | | | 16. DATE HOLE STARTED COMPLETED | | | |
| 8. DEPTH DRILLED INTO ROCK | | | 17. ELEVATION TOP OF HOLE | | | |
| 9. TOTAL DEPTH OF HOLE | | | 18. TOTAL CORE RECOVERY FOR BORING | | | |
| | | | 19. SIGNATURE OF INSPECTOR | | | |
| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Described) | % CORE RECOVERY | BOX OR SAMPLE NO. | REMARKS (Drilling time, water used, depth of penetration, etc., if significant) |
| 4692 | 00 | | CLOSED OPEN - CRACKS | | | |
| 4692 | 10 | | HAIRLINE - CLOSED | | | |
| 4692 | 20 | | AS VIEWED INSIDE BORING | | | |

ENG FORM 1836 MAR 71 PREVIOUS EDITIONS ARE OBSOLETE (TRANSLUCENT)

PROJECT

HOLE NO.

Hole No. 9463-C13-3A-80

| | | | | | | | |
|--|--|---------------------|--|---|--|-----------------------|--|
| DRILLING LOG | | REVISION | | INSTALLATION | | SHEET | |
| PROJECT | | Sr. 411 + Mo. | | LOCK AND DAM No. 24 | | OF 1 SHEETS | |
| LOCATION (If possible, give name of Station) | | SEE BELOW | | 10. SIZE AND TYPE OF BIT | | 6 3/4" - SEE BELOW | |
| DRILLING AGENCY | | C.F.W.E.S. | | 11. DATE FOR ELEVATION MEASUREMENT (If any) | | M.S.L. | |
| HOLE NO. (As shown on drawing sheet and file number) | | SWES-C13.3N-50 | | 12. MANUFACTURER'S DESIGNATION OF DRILL | | ELECTRIC - CORE DRILL | |
| NAME OF DRILLER | | D. McNamee | | 13. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN | | UNOBTAINED | |
| DIRECTION OF HOLE | | 90° DEC. FROM VERT. | | 14. TOTAL NUMBER CORE BOXES | | ONE | |
| THICKNESS OF OVERBURDEN | | 3.55 | | 15. ELEVATION GROUND WATER | | | |
| DEPTH DRILLED INTO ROCK | | 3.55 | | 16. DATE HOLE STARTED | | 21 NOVEMBER 1960 | |
| TOTAL DEPTH OF HOLE | | 3.55 | | 17. ELEVATION TOP OF HOLE | | 166.0' CENTER ROAD | |
| | | | | 18. TOTAL CORE RECOVERY FOR BORING | | 100% | |
| | | | | 19. SIGNATURE OF DRILLER | | Joseph B. Smith | |

| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | % CORE RECOVERY | BOX OR SAMPLE NO. | REMARKS (Drilling time, water loss, depth of penetration, etc., if significant) |
|---|-------|------------|---|-----------------|-------------------|--|
| 460.00 | 00 | 1/2" Rebar | STEEL | | | Run No. 1 21 Nov 60 |
| 460.10 | 10 | | CONCRETE SAME | 100% | Box 1 | Run 3.55 Began 3-5.0 Reo 3.55 End 7-45-10.45 Loss - Time 12 min. 45 sec - Drl time 120 min Hyl press - Water press mtd RPM 300 Drl Action Smooth Water ret Brown |
| 460.30 | 30 | 1/2" Rebar | STEEL | | | Remarks Drill bit binding up 3 intermittent |
| 460.30 | 30 | | Run No. 1 RQD = 100% | 355 | | |
| <p>CONCRETE - PHYSICAL PROPERTIES SAME AS OTHER WES. BORINGS. CONDITION OF CONCRETE IS GOOD - VERY LITTLE TO NO REACTION AND NO SIGNS OF WEATHERING. SLIGHT OXIDATION OF STEEL AT 0.35 FT</p> | | | | | | |

DIAMOND BIT

79PN429

79PN430

LEGEND

13- CONCRETE

14- MACHINE CORNER

113- MACHINE REBAR

114- NATURAL REBAR

LOCATION

VIEW LOOKING 45°

ENG FORM 1836 MAR 71 PREVIOUS EDITIONS ARE OBSOLETE (TRANSLUCENT) PROJECT HOLE NO.

Hole No. SWES-C13.240

| | | | | |
|---|--|--|--|---|
| DRILLING LOG | | SUBJECT <u>St Louis, Mo</u> | INSTALLATION <u>LOCK 3 Dam #24</u> | SHEET <u>1</u> OF <u>1</u> SHEETS |
| 1. PROJECT <u>LOCK # Dam #24</u> | | 10. SIZE AND TYPE OF BIT <u>6" SEE BELOW</u> | | |
| 2. LOCATION (Coordinates or Section) <u>SEE BELOW</u> | | 11. DATUM FOR ELEVATION MEASUREMENT <u>MSL</u> | | |
| 3. DRILLING AGENCY <u>CEWES</u> | | 12. MANUFACTURER'S DESIGNATION OF DRILL <u>Alker</u> | | |
| 4. HOLE NO. (As shown on drawing and hole number) <u>SWES-C13.2400</u> | | 13. TOTAL NO. OF OVER- BURDEN SAMPLES TAKEN | | |
| 5. NAME OF DRILLER <u>H. McNamee</u> | | 14. TOTAL NUMBER CORE BOXES <u>ONE</u> | | |
| 6. DIRECTION OF HOLE <input type="checkbox"/> VERTICAL <input checked="" type="checkbox"/> INCLINED <u>90°</u> DEG. FROM VERT. | | 15. ELEVATION GROUND WATER | | |
| 7. THICKNESS OF OVERBURDEN | | 16. DATE HOLE STARTED <u>11 November 1912</u> COMPLETED <u>12 November 1912</u> | | |
| 8. DEPTH DRILLED INTO ROCK <u>3.5</u> | | 17. ELEVATION TOP OF HOLE <u>462.0</u> CENTER BORING | | |
| 9. TOTAL DEPTH OF HOLE | | 18. TOTAL CORE RECOVERY FOR BORING <u>100%</u> | | |
| | | 19. SIGNATURE OF INSPECTOR <u>James B. Smith</u> | | |

| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | % CORE RECOVERY | BOX OR SAMPLE NO. | REMARKS (Drilling time, water loss, depth of overburden, etc., if significant) |
|--|-------|--------|---|-----------------|-------------------|---|
| 4620 | 00 | Δ | 1" Round Rod #1 | 100% | | Run #1 11 November 1912 Began 12:19 Run 0:25 End 1:20 Loss 0:35 Time 71 min Gain — Drl time 71 min Hyd press 100 PSI Water press 100 PSI RPM 70.5 Drl Action Smooth Water ret Bored Remarks Tide up Temperature 20° on Day of Boring |
| 4620 | 10 | Δ | 1" of Rod - 1" x 2" Steel | | | |
| 4620 | 20 | Δ | 1/4" Round | 100% | Box 1 | Run #2 11/12 November 1912 Began 2:30 - 5:15 Run 3:15 End 7:30 - 10:30 Loss — Time 340 min Gain — Drl time 340 min Hyd press 100 PSI Water press 100 PSI RPM 80.5 Drl Action Smooth Water ret Bored Remarks |
| 4620 | 30 | Δ | 1/4" Round | | | |
| | | | Run #2 ROD 100% | 5.5' | | |
| <p>CONCRETE - GREY BROWN IN COLOR, NATURAL AGGREGATE (SIZE AND SHAPE AS INDICATED IN OTHER W.E.S. BORINGS), STEEL APPEARS UN-OXIDIZED AND CONDITION OF CONCRETE FROM THIS COLUMN IS VERY GOOD. LITTLE TO NO R.P. AND WITH NO OTHER SIGNS OF WEATHERING, VISIBLE.</p> | | | | | | |

DIAMOND BITS

790690

790432

LEGEND

Δ - CONCRETE

MB - MACHINE BREAK

NB - NATURAL BREAK

R.P. - REACTION PRODUCT

LOCATION

PIER #13

3'

6'

SWES-C13.2400

CENTER OF BOREHOLE HAS BEEN OFFSET 3' TO RIGHT

ENG FORM 1836 MAR 71 PREVIOUS EDITIONS ARE OBSOLETE. PROJECT HOLE NO. (TRANSLUCENT)

Hole No. SNES-C16-15-80

| | | | | |
|--|--|---|---------------------------------------|----------------------------------|
| DRILLING LOG | | DIVISION St. Louis, Mo. | INSTALLATION LOCK 3 DAM #24 | SHEET 1 OF 1 SHEETS |
| 1. PROJECT LOCK 3 DAM #24 | | 10. SIZE AND TYPE OF BIT 6" SAE Bit for No. 3 | | |
| 2. LOCATION (Coordinates or Station) SEE BELOW | | 11. DATUM FOR ELEVATION SHOWN (True or Mean) M.S.L. | | |
| 3. DRILLING AGENCY PC NES | | 12. MANUFACTURER'S DESIGNATION OF DRILL HEER | | |
| 4. HOLE NO. (As shown on drawing and not the number) SNES-C16-15-80 | | 13. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN DISTURBED UNDISTURBED | | |
| 5. NAME OF DRILLER A. McNamee | | 14. TOTAL NUMBER CORE BOXES ONE | | |
| 6. DIRECTION OF HOLE <input type="checkbox"/> VERTICAL <input checked="" type="checkbox"/> INCLINED 90 DEG. FROM VERT. | | 15. DATE HOLE STARTED 8 November 80 COMPLETED 10 November 80 | | |
| 7. THICKNESS OF OVERBURDEN | | 16. ELEVATION TOP OF HOLE 475.45 - Center Boring | | |
| 8. DEPTH DRILLED INTO ROCK 3.6' | | 17. TOTAL CORE RECOVERY FOR BORING 100.0 % | | |
| 9. TOTAL DEPTH OF HOLE | | 18. SIGNATURE OF INSPECTOR James B. Bunker 468.45 | | |

| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | SCORE RECOVERY | BOX OR SAMPLE NO. | REMARKS (Drilling time, water loss, depth of penetration, etc., if significant) |
|-----------|-------|--------|---|----------------|-------------------|---|
| 475.45 | 0.0 | | MB C.C. - 1.5' & 2.5' - 3.6' | | | Run #1 8 November 80 |
| | | | HAIRLINE CRACKS DUE TO FREST DAMAGE - FREEZE THAW | | | AL Run 19 |
| 475.45 | 10 | Δ | REBAR 2"x1" CONCRETE | 222% | Box 1 | Began 3:00 Recd 0.4 |
| | | Δ | 1/2" REBAR | | | End 6:50 Loss 1.5 |
| | | | Run #1 RRD: 78.9% | | | Time 160 min Gain - |
| 475.45 | 20 | Δ | REBAR 2"x1" CONCRETE | | | Drl time 160 min |
| | | Δ | 1/2" CONCRETE REBAR | 188% | Box 1 | Hyd press 50 to 80 PSI |
| 475.45 | 30 | Δ | 1/2" REBAR | | | Water press LOW 10 MPD |
| | | | Run #2 RRD: 82.3% | 3.6 | | RPM 50 to 70 |
| | | | | | | Drl Action SMOOTH |
| | | | | | | Water ret Brown |
| | | | | | | Remarks CHANGING BITS |
| | | | | | | Run #2 10 November 80 |
| | | | | | | AL Run 17 |
| | | | | | | Began 8:00 Recd 3.2 |
| | | | | | | End 11:30 Loss - |
| | | | | | | Time 190 min Gain 1.6' |
| | | | | | | Drl time 190 min |
| | | | | | | Hyd press 80 PSI |
| | | | | | | Water press LOW 10 MPD |
| | | | | | | RPM 70 |
| | | | | | | Drl Action SMOOTH |
| | | | | | | Water ret Brown |
| | | | | | | Remarks |

CONCRETE: PHYSICAL PROPERTIES ARE SAME AS ENCOUNTERED IN OTHER BORINGS (AGGREGATE, COLOR OF CONCRETE, ETC.)

CONDITION OF CONCRETE IS POOR. INTENSE WEATHERING WAS FOUND IN THE CONCRETE. NUMEROUS HAIRLINE CRACKS WITH REACTION PRODUCT AND REACTION RIMS ON THE AGGREGATE WERE VISIBLE. STEEL SURFACES WERE NOT OXIDIZED WHERE VISIBLE. - BOTH STEEL AND COPPER REBAR WAS ENCOUNTERED

DIAMOND
BITS
81PC 177
81PC 170

LEGEND

- Δ CONCRETE
- HAIRLINE CRACKS
- MB MACHINE BREAK
- NB NATURAL BREAK

LOCATION PIEC #16

SNES-C16-15-80

COLUMN NO. 1
VIEW LOOKING U/S

Hole No. SWES CIL 3N 80

| DRILLING LOG | | DIVISION | | INSTALLATION | | SHEET | |
|---|-------|---|---|---|----------------------|--|--|
| 1. PROJECT <u>LOCK & DAM #24</u> | | <u>ST. LOUIS, MO</u> | | <u>LOCK & DAM #24</u> | | <u>1</u> OF <u>1</u> SHEETS | |
| 2. LOCATION (Continuation of Form) | | 3. DRILLING AGENCY | | 10. SIZE AND TYPE OF BIT | | 11. DATE FOR ELEVATION INFORMATION | |
| <u>SEE BELOW</u> | | <u>CEW'S</u> | | <u>M5L</u> | | <u>11-16-79</u> | |
| 4. HOLE NO. (As shown on drawing sheet and log number) | | 5. NAME OF DRILLER | | 12. MANUFACTURER'S DESIGNATION OF DRILL | | 13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN | |
| <u>SWES CIL 3N 80</u> | | <u>A. McNamara</u> | | <u>ACCEL</u> | | <u>0</u> | |
| 6. DIRECTION OF HOLE | | 7. THICKNESS OF OVERBURDEN | | 14. TOTAL NUMBER CORE BOXES | | 15. ELEVATION GROUND WATER | |
| <input checked="" type="checkbox"/> VERTICAL <input checked="" type="checkbox"/> INCLINED <u>90°</u> DES. FROM VERT | | <u>35'</u> | | <u>ONE</u> | | <u>---</u> | |
| 8. DEPTH DRILLED INTO ROCK | | 9. TOTAL DEPTH OF HOLE | | 16. DATE HOLE | | 17. ELEVATION TOP OF HOLE | |
| <u>---</u> | | <u>---</u> | | <u>10 November 80</u> | | <u>415.4' CENTER OF HOLE</u> | |
| 18. TOTAL CORE RECOVERY FOR BORING | | 19. SIGNATURE OF INSPECTOR | | 20. SIGNATURE OF DRILLER | | 21. SIGNATURE OF OPERATOR | |
| <u>100%</u> | | <u>[Signature]</u> | | <u>[Signature]</u> | | <u>[Signature]</u> | |
| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | 1. CORE RECOVERY | 2. BOX OR SAMPLE NO. | REMARKS (Drilling time, water used, depth of penetration, etc.; if significant) | |
| 475.48 | 0.0 | MB | REBAR-2"x1" | | | <u>Run #1</u> M. Run 350 Began 3:30-5:30 Reg 350 End 7:45-11:15 Log Time 330 min. Gain Drl time 30 min Hy. press 80 to 100 PSI Water press MED RPM 702 Drl Action Smooth Water ret Brown Remarks | |
| 475.45 | 1.0 | MB | 1' VISUAL EXTENT OF FREEZE-THAW DAMAGE | 100% | 304 | | |
| 475.45 | 2.0 | MB | CONCRETE | | 1 | | |
| 475.45 | 3.0 | MB | | | | | |
| 475.45 | 4.0 | MB | | | | | |
| | | | Run #2 RQD: 77.1% | | | | |
| <p><u>CONCRETE: PHYSICAL PROPERTIES SAME AS OTHER BORINGS (COLOR, AGGREGATE, ETC)</u></p> <p><u>CONDITION OF CONCRETE IS FAIR.</u></p> <p><u>ONLY THE FIRST FOOT IS INTENSELY WEATHERED AND REMAINING CONCRETE APPEARS TO BE IN GOOD CONDITION.</u></p> <p><u>NUMEROUS HAIRLINE CRACKS, BREAKS, AND MOD. REACTION PRODUCT IS VISIBLE IN THE FIRST FOOT. STEEL LOOKS TO BE IN GOOD CONDITION. THERE IS NO OXIDATION FOUND ON STEEL'S SURFACE (BAR @ 0.35')</u></p> | | | | | | | |
| DIAMOND BIT | | LEGEND | | LOCATION PER #16 | | | |
| 79PN0432 | | <input checked="" type="checkbox"/> CONCRETE <input checked="" type="checkbox"/> HAIRLINE CRACKS MB MACHINE BREAK NB NATURAL BREAK | | | | | |

ENG FORM 1836 MAR 71 PREVIOUS EDITIONS ARE OBSOLETE (TRANSLUCENT)

| DRILLING LOG | | INSTALLATION | | SHEET | |
|--|--|--|--|---|--|
| PROJECT: <u>LOCK 1 Dam #24</u> | | DATE: <u>10/10/60</u> | | OF 1 SHEETS | |
| 1. LOCATION: <u>LOCK 1 Dam #24</u> | | 2. NAME AND TYPE OF BIT: <u>6"-5 1/2" Bit</u> | | | |
| 3. DRILLING METHOD: <u>MSL</u> | | 4. MANUFACTURER'S DESIGNATION OF DRILL: <u>MSL</u> | | | |
| 5. DRILLING AGENT: <u>C.E.W.S.</u> | | 6. TOTAL NO. OF OVERBURDEN SAMPLES TAKEN: <u>1</u> | | 7. DISTURBED: <u>UNDISTURBED</u> | |
| 8. HOLE NO. (As shown on drilling plan and the number): <u>SWES-CK-2N-Rc</u> | | 9. TOTAL NUMBER CORE BOXES: <u>ONE</u> | | 10. ELEVATION GROUND WATER: <u>467.45'</u> | |
| 11. NAME OF DRILLER: <u>A. McVay</u> | | 12. DATE HOLE: <u>10/10/60</u> | | 13. COMPLETED: <u>10/10/60</u> | |
| 14. DIRECTION OF HOLE: <u>90°</u> | | 15. ELEVATION TOP OF HOLE: <u>467.45'</u> | | 16. TOTAL CORE RECOVERY FOR BORING: <u>100%</u> | |
| 17. THICKNESS OF OVERBURDEN: <u>3.5</u> | | 18. SIGNATURE OF INSPECTOR: <u>John B. Taylor</u> | | | |
| 19. DEPTH DRILLED INTO ROCK: <u>3.5</u> | | 20. TOTAL DEPTH OF HOLE: <u>467.45'</u> | | | |

| ELEVATION | DEPTH | LEGEND | CLASSIFICATION OF MATERIALS (Description) | CORE RECOVERY | BOX OR SAMPLE NO. | REMARKS (Drilling data, sample logs, depth of overburden, etc., if significant) |
|---|-------|--------|---|---------------|-------------------|---|
| 467.45 | 0.0 | | HAIRLINE CRACKS | | | Run #1 10/10/60 |
| 467.45 | 1.0 | | STEEL REBAR | | Box 1 | Run 12/5 Began 12/5 End 1/3 Time 30 min Drl time 50 min Hyd press 600 Water press 100 to 140 RPM 700 Drl Action Smooth Water ret Bowl Remarks STRENGTH HARD ON CORE BIT |
| 467.45 | 2.0 | | CONCRETE | | Box 1 | Run #2 13/10/60 |
| 467.45 | 3.0 | | HAIRLINE CRACKS | | 3.5 | Run 2.6 Began 8:30 End 10:00 Time 1:30 min Drl time 1:30 min Hyd press 750 Water press 100 RPM 750 Drl Action Smooth Water ret Bowl Remarks |
| <p>CONCRETE: WEATHERED AT ENDS WITH NUMEROUS HAIRLINE CRACKS, MODERATE REACTION PRODUCT, AND NATURAL BETAS - CENTER OF CORE APPROX IN CONDITION BUT STILL NOT NEARLY AS SLIGHT AMOUNT OF REACTION PRODUCT. STEEL WARE EXPOSED DOES NOT APPEAR OXIDIZED OR CORRODED. - ENDS ARE IN POOR CONDITION WHILE CENTER IS IN FAIR CONDITION.</p> | | | | | | |

DIAMOND BIT

81 PC 17H

81 PC 17C

LEGEND

□ - CONCRETE

MB - MACHINE BREAK

NB - NATURAL BREAK

— - HAIRLINE CRACK

LOCATION

APPENDIX C: REPORT OF PETROGRAPHIC
EXAMINATION OF CONCRETE CORES

| | | |
|---|---|--|
| Corps of Engineers, USAE Waterways Experiment Station | Concrete Report | Structures Laboratory P. O. Box 631 Vicksburg, Mississippi |
| Project | Investigation of Concrete Deterioration, Lock and Dam 24 | Date 13 March 1981 GSW |

Samples

1. Portions of concrete from five cores from Lock and Dam No. 24 were selected for detailed petrographic examination. A general description of the 6-in.-diameter concrete cores is as follows:

| <u>Field Identification No.</u> | <u>Description</u> |
|---------------------------------|---|
| S WES-C16.2 N-80 | Horizontal core into badly deteriorated concrete |
| S WES-C16.3 E-80 | Horizontal core into moderately deteriorated concrete |
| S WES-C13.2 N | Horizontal core into good concrete |
| S WES-P04.1 | Vertical core into good concrete |
| S WES-P09.1 | Vertical core into good concrete |

Test procedures

2. The concrete cores that were examined represented different visual physical conditions of the concrete. Some portions of the concrete examined were deep interior concrete while other concrete represented the near surface material.
3. The appearance and condition of this concrete was compared to that of the concrete previously examined from the same structure in 1976⁽¹⁾ and 1978.⁽²⁾ The current samples are more representative of the general condition of the concrete deterioration and the extent of the damage.
4. Twenty-five cores were examined megascopically to determine the overall homogeneity of the concrete. Portions of the concrete cores described earlier were selected for further examination.
5. Several pieces of core were sawed longitudinally. One of each pair of sawed surfaces was ground smooth and examined with a stereomicroscope.
6. The core surfaces were examined for signs of deleterious chemical reaction and/or physical degradation. Fresh fracture surfaces were also examined. A stereomicroscope was used as needed to aid in the examination.

WES FORM No. 1115
Rev Feb 1970

7. Reaction products from interior concrete surfaces and exudation from core surfaces were examined as oil immersion mounts using a polarizing microscope.

8. A black substance coating a break in core S WES-P04.1 at about 12.5-ft depth was also examined. Acetone was used to remove the coating from the break surface before the concrete was examined.

Results

9. Concrete from core S WES-C16.2 N-80 represented severely deteriorated concrete. This concrete was highly fractured and tended to disaggregate easily during drilling and handling. The concrete from boring S WES-C16.3 E-80 represented moderately deteriorated concrete. This concrete contained a major longitudinal crack in the center of the core in which a white exudation is collecting on the exposed surface of the concrete. All other concrete cores represented intact concrete from both the interior and near surface concrete of the structure.

10. The concrete in all the cores examined contained gravel and sand of mixed composition. The maximum size coarse aggregate was about 1-1/2 in. The aggregate consisted of sandstone, quartz, chert, carbonate rock particles, dark fine-grained igneous rock particles, coarse-grained igneous rock particles, and some particles of ironstone. Chalcedony in chert particles was identified as the most common reactive aggregate material in this group of concrete cores. This finding is similar to the observations made in the two earlier reports.^(1,2)

11. Some of the concrete contained pale yellowish brown (10 YR 6/2)⁽³⁾ paste while the remainder of the concrete contained medium light gray (N6)⁽³⁾ paste. There was no apparent physical difference between the different colored pastes. White alkali silica gel was present in both colors of paste.

12. The general deterioration consisted of parallel to subparallel cracking occurring parallel to the formed surface of the cores. These partings tended to be closely spaced near the outer surface of the concrete and were absent in the interior concrete. The photographs in Figure C1 are a set of pictures of core S WES-C16.2 N-80 drilled through a column on pier No. 16. Deterioration was present at both ends of this core while the central portion of it remained relatively intact.

13. Examination of ground surfaces indicated that this concrete was not air entrained. The concrete contained a few entrapped air voids but generally the concrete was dense and intact.

14. The maximum depth of deterioration was to a depth of 1.5 ft as found in core S WES-C16.2 N-80. Most of the deterioration was confined to the exterior 0.6 ft of concrete.

15. This concrete also tended to be saturated with white alkali-silica gel. This gel was present coating the cracks and as surface exudation. Some calcium hydroxide was also carried to surfaces in solution and deposited as white deposits. The alkali-silica gel ranged from a thick white to a clear material totally encasing the reactive aggregate and penetrating into the adjacent paste.

16. The black material coating the broken surface of core S WES-P04.1 at about 12.5 ft was a pliable black tar-like substance. The concrete beneath the coating was undisturbed. The coating appeared to have been put on the concrete as some sort of a bond breaker.

Conclusions

17. The lack of entrained air in this concrete caused the concrete to be susceptible to frost damage. The repeated freezing and thawing of the concrete while critically saturated has caused delamination of the concrete, especially near surfaces.

18. The opening of the concrete by frost action has accelerated the alkali-silica reaction. This deleterious chemical reaction has caused additional disaggregation of the frost-damaged concrete. The interior concrete shows slight indications of alkali-silica reaction, but has not caused any significant damage to the interior concrete.

References Cited

1. U. S. Army Engineer Waterways Experiment Station petrographic report dated 30 January 1976 to the U. S. Army Engineer District, St. Louis, subject: "Test and Examination of Concrete Cores from Lock and Dam 24 and Lock and Dam 25."
2. U. S. Army Engineer Waterways Experiment Station petrographic report dated December 1978 to the U. S. Army Engineer District, St. Louis, subject: "Examination of Concrete Cores from Lock and Dam 24."
3. The Rock Color Chart Committee, E. N. Goddard, Chm, "Rock Color Chart," 1975, The Geological Society of America, Boulder, Colo.



(a)



(b)

Figure C1. Opposite ends of core S WES-C16.2 N-80 drilled through a concrete column. The cracking is parallel to the formed surface and tends to go around the aggregate particles as well as through them

APPENDIX D: PHOTOGRAPHS SHOWING BURST PIPE



Photo 1. Fractured concrete wedge before removal. Column 3 on pier No. 16.



Photo 2. Concrete wedge removed exposing burst pipe, reinforcing steel, and wetted concrete.



Photo 3. Close-up of area shown in Photo 2. Notice burst pipe and wetter concrete. Most all large aggregate show clean tensile failure surfaces.



4
The above described concrete is not a
standard concrete, but a special concrete
used for the construction of the bridge.



Fig. 10. Floor surface atop of bridge support column. X-ray diffraction plates removed during next to condition. In upper plate seen in upper left of photograph, dirt on floor is visible near column and plate, top of column is visible in lower right.

In accordance with letter from DAEN-RDC, DAEN-ASI dated 22 July 1977, Subject: Facsimile Catalog Cards for Laboratory Technical Publications, a facsimile catalog card in Library of Congress MARC format is reproduced below.

Stowe, Richard L.

Condition survey repair and rehabilitation Lock and Dam No. 24, Mississippi River / by Richard L. Stowe, Henry T. Thornton, Jr. (Structures Laboratory, U.S. Army Engineer Waterways Experiment Station). -- Vicksburg, Miss. : The Station ; Springfield, Va. : available from NTIS, 1981.

90 p. in various pagings, 46 p. of plates : ill. ; 27 cm. -- (Miscellaneous paper / U.S. Army Engineer Waterways Experiment Station ; SL-81-21)

Cover title.

"August 1981."

"Prepared for U.S. Army Engineer District, St. Louis."

Final report.

Bibliography: p. 33.

1. Concrete dams. 2. Concrete research. 3. Locks (Hydraulic engineering). 4. Mississippi River.
I. Thornton, Henry T., Jr. II. United States. Army.

Stowe, Richard L.

Condition survey repair and rehabilitation : ... 1981.
(Card 2)

Corps of Engineers. St. Louis District. III. U.S. Army Engineer Waterways Experiment Station. Structures Laboratory. IV. Title V. Series: Miscellaneous paper (U.S. Army Engineer Waterways Experiment Station) ; SL-81-21.
TA7.W34m no.SL-81-21